



R Y THOMSON & SON

15 Ash Street, Dundee. DD1 5AR
VAT No 327 2180 76

Tel: 01382 221460

Email: info@rythomson.co.uk

Risk Assessment For Odour

Odour control must be designed to prevent odour nuisance in a given situation. The following score methodology is suggested as a means of determining odour control requirements using a simple risk assessment approach.

Impact Risk	Odour Control Requirement	Significance Score*
Low to Medium	Low level odour control	Less than 20
High	High level odour control	20 to 35
Very High	Very high odour control	More than 35

*Based on the sum of contributions from dispersion, proximity of receptors, size of kitchen and cooking type.

Criteria	Score	Score	Details
Dispersion	Very Poor	20	Low level discharge, discharge into courtyard or restriction on stack.
	Poor	15	Not low level but below eaves, or discharge at below 10 m/s.
	Moderate	10	Discharging 1m above eaves at 10 – 15 m/s.
	Good	5	Discharging 1m above ridge at 15 m/s.
Proximity of receptors	Close	10	Closest sensitive receptor less than 20m from kitchen discharge.
	Medium	5	Closest sensitive receptor between 20m and 100m from kitchen discharge.
	Far	1	Closest sensitive receptor more than 100m from kitchen discharge.
Size of kitchen	Large	5	More than 100 covers or large sized takeaway.
	Medium	3	Between 30 and 100 covers or medium sized takeaway.
	Small	1	Less than 30 covers or small takeaway.
Cooking type (odour and grease loading)	Very High	10	Pub (high level of fried food), fried chicken, burgers or fish and chips. Turkish, Middle Eastern or any premises cooking with solid fuel.
	High	7	Vietnamese, Thai, Indian, Japanese, Chinese or Steakhouse.
	Medium	4	Cantonese, Italian, French, Pizza (Gas Fired)
	Low	1	Most Pubs(no fried food, mainly reheating and sandwiches) Tea Rooms.



R Y THOMSON & SON

15 Ash Street, Dundee. DD1 5AR
VAT No 327 2180 76

Tel: 01382 221460

Email: info@rythomson.co.uk

Site Details

Contractor	R Y Thomson & Son
Site Name	Seaview
Site Address	38 Cunzie Street Anstruther KY10 3DF
Evaluation Date	28/03/24

Below is an evaluation for the site based on the criteria on the previous page.

Criteria	Rating	Score	Details
Dispersion	Moderate	10	Discharge 1m above eaves at 10-15m/s velocity.
Proximity of Receptors	Close	10	Residential Building approx 4m distance.
Size of Kitchen	Small	1	Small Takeaway
Cooking Type	High	7	Indian Takeaway

Impact Risk	Odour Control Requirement	Significance Score
High	High Level Odour	28