

Planting Schedule								
Plant Code	Botanical Name	Common Name	Girth/ Dia.cm	Heightm	Specification	RootCondition/ Container Size	Ctr m	Qty
<b>Proposed Trees</b>								
ACE CAM	<i>Acer campestre</i>	Common Maple	16-18	400-450	3x; Extra heavy standard; Clear stem min. 200cm; 5 brks	RB		1
ACE PLA	<i>Acer platanoides</i>	Norway Maple	18-20	450-650	3x; Extra heavy standard; Clear stem min. 200cm	RB		4
ACE SUN	<i>Acer rubrum 'Red Sunset'</i>	Red Maple 'Red Sunset'	18-20	450-650	3x; Extra heavy standard; Clear stem min. 200cm	RB		9
BET PEN	<i>Betula pendula</i>	Common Silver Birch	16-18	400-450	3x; Extra heavy standard; Clear stem min. 200cm	RB		6
BET PUB	<i>Betula pubescens</i>	Downy Birch	18-20	450-500	3x; Extra Heavy Standard; Clear stem min. 200cm	RB		4
CAR FAS	<i>Carpinus betulus 'Fastigiata'</i>	Fastigiata Hornbeam	16-18	400-450	3x; Extra heavy standard; Clear stem min. 200cm	RB		7
PRU AVI	<i>Prunus avium</i>	Wild Cherry	18-20	450-500	3x; Extra heavy standard; Clear stem min. 200cm	RB		6
TIL EUC	<i>Tilia x euchlora</i>	Caucasian Lime	18-20	450-500	3x; Extra heavy standard; Clear stem min. 200cm	RB		8
Plant Code	BotanicalName	CommonName	Girth/ Dia.cm	Heightcm	Specification	RootCondition/ Container Size	Density	
<b>Proposed Hedgerow</b>								
CAR BET	<i>Carpinus betulus</i>	Common Hornbeam	n/a	100-125	100-125cm height, RB, Double Staggered Rows 450mm apart, 450mm spacing	RB		4 per linear m
GRI LIT	<i>Griselinia littoralis</i>	Broadleaf	n/a	60-80	Bushy, 7 brks, 10L, Double Staggered Rows 450mm apart, 450mm spacing	10L		4 per linear m
<b>Proposed Block Planting</b>								
SKI RUB	<i>Skimmia japonica 'Rubella'</i>	Japanese Skimmia	n/a	30-40	Bushy; 3 brks	3L		2 per sqm

Planting Schedule						
Mix%	Botanical Name	Common Name	Specification	Container Size	Density	Groupings
<b>Bulb Underplanting Mixture</b>						
40	<i>Allium 'Globemaster'</i>	Ornamental Onion 'Globemaster'	Grade 20/+	n/a	10 per sqm	Scatter & plant randomly through out area
60	<i>Narcissus 'Thalia'</i>	Daffodil 'Thalia'	Grade 10/12	n/a	20 per sqm	
<b>MIX A - Entrance Amenity Mixture</b>						
15	<i>Astrantia major 'Hadspen Blood'</i>	Masterwort 'Hadspen Blood'	Full pot	3L	5 per sqm	1, 3 or 5
15	<i>Deschampsia cespitosa</i>	Tufted Hair Grass	Full pot	3L		
10	<i>Echinacea purpurea</i>	Purple Coneflower	Full pot	3L		
20	<i>Heuchera cylindrica 'Greenfinch'</i>	Lava Alumroot 'Greenfinch'	Full pot	3L		
10	<i>Lavandula angustifolia 'Hidcote'</i>	Lavender 'Hidcote'	Bushy; 5 brks	3L		
5	<i>Lonicera nitida 'Maigrün'</i>	Box Honeysuckle 'Maigrün'	Bushy; 6 brks	3L		
15	<i>Rudbeckia fulgida sullivanii 'Goldsturm'</i>	Black-eyed Susan 'Goldsturm'	Full pot	3L	5 per sqm	3 or 5
10	<i>Salvia officinalis</i>	Common Sage	Full pot	3L		
<b>MIX B - General Amenity Mixture</b>						
15	<i>Centaurea montana</i>	Mountain Knapweed	Full pot	3L	5 per sqm	3 or 5
20	<i>Geranium macrorrhizum 'Album'</i>	Balkan Cranesbill 'Album'	Full pot	3L		
10	<i>Luzula sylvatica</i>	Great Wood-rush	Full pot	3L		
10	<i>Miscanthus sinensis 'Morning Light'</i>	Eulalia 'Morning Light'	Full pot	3L		
5	<i>Rosmarinus officinalis 'Miss Jessopp's Upright'</i>	Rosemary 'Miss Jessopp's Upright'	Bushy; 4 brks	3L		
15	<i>Salvia officinalis 'Purpurascens'</i>	Purple Sage	Full pot	3L		
10	<i>Santolina chamaecyparissus</i>	Cotton Lavender	Bushy; 7 brks	3L	5 per sqm	3 or 5
15	<i>Veronica spicata</i>	Spiked Speedwell	Full pot	3L		
<b>MIX C - Boundary Bloom Mixture</b>						
15	<i>Acanthus mollis</i>	Bear's Breeches	Full pot	3L	5 per sqm	3 or 5
15	<i>Bergenia 'Silberlicht'</i>	Elephant's Ears 'Silberlicht'	Full pot	3L		
15	<i>Centranthus ruber</i>	Red Valerian	Full pot	3L		
10	<i>Hosta sieboldiana elegans</i>	Plantain Lily elegans	Full pot; 2 buds	3L		
10	<i>Lavandula angustifolia 'Hidcote'</i>	Lavender 'Hidcote'	Bushy; 5 brks	3L		
15	<i>Mentha pulegium</i>	Pennyroyal	Full pot	3L		
20	<i>Thymus 'Doone Valley'</i>	Thyme 'Doone Valley'	Full pot	3L		
<b>MIX D - Shade Tolerant Mixture</b>						
15	<i>Asplenium scolopendrium</i>	Hart's Tongue Fern	Full pot	3L	5 per sqm	3 or 5
15	<i>Astrantia major 'Hadspen Blood'</i>	Masterwort 'Hadspen Blood'	Full pot	3L		
15	<i>Bergenia 'Bressingham Ruby'</i>	Elephant's Ears 'Bressingham Ruby'	Full pot	3L		
10	<i>Brunnera macrophylla</i>	Siberian Bugloss	Full pot	3L		
15	<i>Carex elata 'Aurea'</i>	Bowles' Golden Sedge	Full pot	3L		
20	<i>Pachysandra terminalis</i>	Japanese Spurge	Several shoots; 9 brks	3L		
10	<i>Tiarella cordifolia</i>	a Foam Flower	Full pot	3L		
<b>MIX E - Native Structure Mixture</b>						
25	<i>Alopecurus pratensis</i>	Meadow Foxtail	Full pot; Sept to April planting;	1L	7 per sqm	5
20	<i>Arrhenatherum elatius</i>	False Oat Grass	Full pot; Sept to April planting;	1L		
25	<i>Calluna vulgaris</i>	Scots Heather	Bushy	2L		
10	<i>Corylus avellana</i>	Common Hazel	Branched; 3 brks	3L		
20	<i>Dryopteris filix-mas</i>	Male Fern	Full pot	3L		
<b>MIX F - Evergreen Structure Mixture</b>						
30	<i>Brachypodium sylvaticum</i>	Slender False-brome	Full pot; Sept to April planting;	1L	6 per sqm	3 or 5
20	<i>Carex pendula</i>	Pendulous Sedge	Full pot	3L		
25	<i>Dryopteris filix-mas</i>	Male Fern	Full pot	3L		
25	<i>Polystichum setiferum</i>	Soft Shield Fern	Full pot	3L		
<b>MIX G - Tall Grass Meadow Mixture</b>						
5	<i>Anthemis tinctoria 'E.C. Buxton'</i>	Dyer's Chamomile 'E.C. Buxton'	Full pot	2L	6 per sqm	3, 5 or 7
25	<i>Cynosurus cristatus</i>	Crested Dog's-tail	Full pot; Sept to April planting;	1L		
15	<i>Daucus carota</i>	Wild Carrot	Full pot; Sept to April planting;	1L		
10	<i>Echinacea purpurea 'Magnus'</i>	Purple Coneflower 'Magnus'	Full pot	2L		
10	<i>Miscanthus sinensis</i>	Eulalia	Full pot	3L		
10	<i>Monarda 'Beauty of Cobham'</i>	Bergamot 'Beauty of Cobham'	Full pot	3L		
10	<i>Pennisetum alopecuroides 'Hameln'</i>	Fountain Grass 'Hameln'	Full pot	3L	6 per sqm	3, 5 or 7
5	<i>Stipa gigantea</i>	Giant Feather Grass	Full pot	3L		
10	<i>Verbena bonariensis</i>	Argentinian Vervain	Full pot	3L		
<b>MIX H - Tall Grass Shade Mixture</b>						
25	<i>Anthoxanthum odoratum</i>	Sweet Vernal Grass	Full pot; Sept to April planting;	1L	6 per sqm	3, 5 or 7
25	<i>Campanula lactiflora 'Loddon Anna'</i>	Milky Bellflower 'Loddon Anna'	Full pot	3L		
30	<i>Molinia caerulea</i>	Purple Moor Grass	Full pot	2L		
20	<i>Veronicastrum virginicum 'Fascination'</i>	Culver's Root 'Fascination'	Full pot	2L		
<b>MIX I - Rain Garden Mixture</b>						
15	<i>Filipendula ulmaria</i>	Meadowsweet	Full pot; Sept to April planting;	3L	4 per sqm	min groups of 5
25	<i>Glyceria maxima</i>	Reed Sweet Grass	Full pot; Sept to April planting;	2L		
15	<i>Mentha aquatica</i>	Water Mint	Full pot	3-4L		
25	<i>Myosotis scorpioides</i>	Water Forget-me-not	Full pot; Sept to April planting;	2L		
20	<i>Silene flos-cuculi</i>	Ragged Robin	Full pot; Sept to April planting;	1L		

P01 25/03/2024 Issued for Planning.

REV DATE DESCRIPTION

CLIENT



CONTRACTOR



CONSULTANT

ALA



PROJECT

One Degree Academy

DRAWING TITLE

Planting Schedules

DRAWING PURPOSE

S2 - Planning

DRAWN BY	DATE	CHK'D BY	SCALE	MEDIA
AF	25/03/2024	TB	NTS	A1

CONTRACT DRAWING REFERENCE (AS REQUIRED)

PROJECT - ORIGINATOR - ZONE - LEVEL - TYPE - ROLE - NUMBER

FS0404-ALA-ZZ-00-DR-L-0323

REVISION

P01