


Proposed floor plan 1:50




**Roof Covering** to be of Marley (or similar) elastomeric felt, laid with each layer to break joint, 75 mm end & 50mm side laps, all fully bonded in hot bitumen. 1st layer to be 180E sanded underlay with 350E mineral surfaced polyester cap sheet. felt welded at verges & eaves & dressed 150mm up abutments with Code 4 lead-cover flashings.

**Roof Structure** formed with timbers to sizes & ccs shown. Joists hung on walls in galv. m.s. hangers & set on 100 x 50mm s.w. wallplate on new walls. Solid strutting at mid-span. All strapped to walls with 30 x 50mm galv. m.s. straps at 1200 ccs, plugged and screwed. S.w. fittings set on joists to give 1 in 80 fall with 50 x 50mm s.w. cross battens & 22mm ext. ply deck. 100mm PIR insulation between roof joists & 65mm PIR below to u/s of joists to form 'cold roof'. 19mm ext. ply fascia set.

**Rainwater Disposal** by means of 100mm dia. uPVC gutters fixed to falls to fascias with stop-ends & outlet to 63mm dia. r.w.p., connected at base to b.i.g. & run via drain to new brick stein S/A min. 5m from buildings.


New beams formed of RSA's to sizes shown & bolted together with 8mm bolts at 600mm ccs with gas barrel spacers. All encased in 2 no. layers 9.5mm plasterboard, fixed to break joint with 1.6mm tying wire at 100mm pitch. All taped & skimmed. 50 x 50mm s.w. cradle formed to fix cladding.

**Parapet Wall** raised as shown & closed with D.P.C. with either double creasing tile course with brick-on-edge coping or weathered coping stones.




**Foundations** to be formed to sizes & depths shown & agreed on-site with B.C.O. to suit prevailing soil conditions. All in 1:2.4 conc.


Block plans 1:200



Scale Bars (m)



Exg floor plan 1:100



**External Walls** to be of 215mm conc. blocks laid in 1.3cm below DPC 'Hyload' DPC connected to exg. & min. 150mm a.g.l. above DPC walls of 215mm Celotex Solar blocks, plastered internally. Blocks laid in 1:1.6 gm in stretcher bond with E.M.L. in every 3rd course, between windows and below windows within a 45 degree angle. New work bonded to exg. at junctions with s.s. profiles. Walls sealed externally and rendered with 1:1.6 render with drip above DPC. Internally, walls lined with 80mm Kingspan Kooltherm K112 insulated plasterboard on 25mm battens & 3mm skim. Windows bridged with catnic insul. Lintels with min. 150mm end brgs. Windows dble-glazed with glass area min. 10% floor area, operable area min. 5% floor area. Render to be 20mm thick, 2 coat finish.

**S.d.p.** to be 100mm dia. uPVC connected to drain at base & terminated 900mm above head of windows. Bosses to be built-in to receive waste pipes & access plate at base. Fittings with uPVC wastes and traps. Bath - 38mm dia., 75mm d.s. trap. Basin - 32mm dia., 75mm d.s. trap. W.C. - 100mm dia., 'p' trap. Rodding eyes at all changes of direction. Centre line of WC connection min. 200mm below centre line of bath or shower waste.

**New M/H** formed on drain run as shown with min. 150mm conc. base & 225mm semi-eng'g blk walls in 1.3cm. Drains in MH in channel section with benching around. MH to have pressed metal cover & frame. Internally MH's to have bolt-down, air-tight, double seal cover.

**Ext. Drains** Where becoming internal to be surrounded in 150mm pea-shingle & bridged where passing through structure with r.c. lintels with Flexcel between drain & lintel.

**New Drains** to be of 100mm dia. Supersleeve, laid to 1 in 40 falls & run as shown, with 150mm thick pea-shingle bedding. Where internal, new drains to be encased as for exg. (i.e. surround in 150mm pea-shingle). Bridged with 2 no. 100 x 150mm r.c. lintels.

**Electrical:** All electrical work required to meet the requirements of Part P (electrical safety) must be designed, installed, inspected and tested by a competent person registered under a competent person self-certification scheme such as BRE Certification Ltd, BSI, NICEIC Certification Services or Zurich Ltd. An appropriate BS 7671 Electrical Installation Certificate is to be issued for the work by a person competent to do so. A copy of a Part P Certificate will be given to the Council.

**Lighting:** to new rooms to be provided with min. 1 no. light fitting with luminous efficacy of n.l.l. 40 lumens / circuit watt. 1 fitting / 25m² & 75% of fittings to be low energy.


**Ventilation** to rooms as follows:- Habitable Rooms:- 10,000 sq mm background ventilation. Kitchens:- 4000 sq mm back. vent & ext. fan to extract 60 litres/sec.

**Smoke Detection:** Mains operated linked smoke alarm detection system to BS 5446 - 1:2000 and BS 5839 - 6:2004 to at least a Grade D category LD3 standard and to be mains powered with battery back-up. Smoke alarms should be sited so that there is a smoke alarm in the circulation space on all levels/storeroys and within 7.5m of the door to every habitable room. If ceiling mounted they should be 300mm from the walls and light fittings. Where the kitchen area is not separated from the stairway or circulation space by a door, there should be an interlinked heat detector in the kitchen. Heat detector to be activated at temperature of 58°C. Upon completion Certificate of Installation to be provided to B.C.O.


Exg. central heating system to be extended into extension with pressed steel radiators, TRV's & insulated pipework. If boiler position to be changed new positioning to be decided by Gas Safe registered engineer.

**New Solid Floor** formed of min. 150mm thick, well rammed, broken brick hardcore, blinded with 50mm sand. 100mm thick 1:2.4 conc. slab. Marley 'Dampseal' DPM connected to exg. & new DPC's min. 1200g 100mm dia. PVC air-ducts built in as necessary to vent. exg. timber floor. Floor to have 100mm Kingspan K103 PIR insulation & 65mm 1:4 c.s. screed. Perimeter insulation upstands & separating membrane.

Elevations 1:100



Roof plans 1:100



Prior to commencement of work contractor and client to confirm exact boundary positions. Contractor to inform architect of any anomalies between plans and elevations/section prior to start of work. Any key elements of the existing structure such as foundations and/or lintels, which by virtue of the proposed works, will be accepting greater loadings will need to be exposed for consideration by the building control surveyor and upgraded or replaced if found necessary. All measurements are to be checked on site prior to ordering any materials. The Party Wall Act 1996 must be adhered to wherever relevant. It is the client's responsibility to seek expert advice from a professional party wall surveyor to ensure full compliance with the regulations. Water board agreement must be provided in writing when necessary, prior to commencement of works. Heating, lighting and internal finishes are to be agreed between the owner and chosen builder. All structural timber members are to be grade c24 treated softwood marked KD (kiln dried) or dry to ensure the timbers have been properly stored. All leadwork should be fixed and installed in accordance with the Lead Development Associations Handbook - 'Lead Sheet Building - A Guide to Good Practice'.

PLAN & SURVEY BUILDING SURVEYORS

25 Alton Close, Bexley, Kent. DA5 3QJ  
Mike Course  
Email: planandsurvey@btinternet.com Mobile: 07767 881 391

Client  
Mr P. James

Job Title  
8, Saltash Road,  
Welling, Kent.  
DA16 1HB

Drawing Title  
Garage conversion

Scale 1:50 1:100 1:200