

MANHOLE SCHEDULE

DT02-0915



The Gate House | Bays 2&3 Pattenden Lane
Marden | Tonbridge | Kent | TN12 9QS
Tel: 01732 617555
Email: mail@hodel.uk

Project No: **19-014** Sheet No. **SW- MHS**
Made By: **RR** Revision: **-**
Date: **28/03/2024** Project: **Cull Farm**

MH REF	COVER LEVEL	INVERT LEVEL	DEPTH TO INVERT	CHAMBER TYPE	CHAMBER SIZE	REMARKS
S1	79.74	78.64	1.10	PPIC	450 Ø	
S2	79.28	78.18	1.10	PPIC	450 Ø	
S3	79.11	18.01	61.10	PPIC	450 Ø	Restricted access chamber.
S4	78.87	77.67	1.20	PC Ring	1050 Ø	PC ring catchpit min 600mm sump.
RE5.1	79.25	78.75	0.50	RE	100 Ø	Rodding eye.
RE5.2	79.25	78.75	0.50	RE	100 Ø	Rodding eye.
S5	79.25	78.60	0.65	PPIC	450 Ø	PPIC catchpit min 300mm sump.
RE6.1	79.25	78.75	0.50	RE	100 Ø	Rodding eye.
RE6.2	79.25	78.75	0.50	RE	100 Ø	Rodding eye.
S6	79.25	78.60	0.65	PPIC	450 Ø	PPIC catchpit min 300mm sump.
S7	79.01	77.91	1.10	PPIC	450 Ø	
RE8.1	79.65	79.05	0.60	RE	100 Ø	Rodding eye.
S8	79.29	78.69	0.60	PPIC	450 Ø	
S9	79.75	78.60	1.15	PPIC	450 Ø	
S10	79.74	79.14	0.60	PPIC	450 Ø	
S11	79.50	78.50	1.00	PPIC	450 Ø	PPIC catchpit min 300mm sump.
RE12.1	78.50	78.00	0.50	RE	100 Ø	Rodding eye.
S12	78.45	77.87	0.58	PPIC	450 Ø	
RE13.1	78.50	78.00	0.50	RE	100 Ø	Rodding eye.
S13	78.43	77.70	0.73	PPIC	450 Ø	PPIC catchpit min 300mm sump.
S14	77.90	76.70	1.20	PC Ring	1050 Ø	PC ring catchpit min 600mm sump.
S15	78.88	77.78	1.10	PPIC	450 Ø	
S16	78.02	76.99	1.03	PPIC	450 Ø	
S17	77.83	76.95	0.88	PPIC	450 Ø	
S18	77.61	76.84	0.77	PPIC	450 Ø	
RE19.1	77.80	77.30	0.50	RE	100 Ø	Rodding eye.
S19	77.85	77.12	0.73	PPIC	450 Ø	
S20	77.85	76.99	0.86	PPIC	450 Ø	PPIC catchpit min 300mm sump.
RE20.1	78.10	77.30	0.80	RE	100 Ø	Rodding eye.
RE21.1	77.80	77.30	0.50	RE	100 Ø	Rodding eye.
S21	77.85	77.12	0.73	PPIC	450 Ø	
S22	77.85	76.99	0.86	PPIC	450 Ø	
RE22.1	78.15	77.30	0.85	RE	100 Ø	Rodding eye.
S23	77.90	76.50	1.40	PC Ring	1200 Ø	
RE24.1	77.75	77.25	0.50	RE	100 Ø	Rodding eye.

MANHOLE SCHEDULE

DT02-0915



The Gate House | Bays 2&3 Pattenden Lane
Marden | Tonbridge | Kent | TN12 9QS
Tel: 01732 617555
Email: mail@hodel.uk

Project No: **19-014** Sheet No. **SW- MHS**
Made By: **RR** Revision: **-**
Date: **28/03/2024** Project: **Cull Farm**

MH REF	COVER LEVEL	INVERT LEVEL	DEPTH TO INVERT	CHAMBER TYPE	CHAMBER SIZE	REMARKS
S24	77.54	76.54	1.00	PPIC	450 Ø	
S25	77.43	75.89	1.54	PPIC	450 Ø	PPIC catchpit min 300mm sump. Restricted access chamber.
RE26.1	77.75	77.25	0.50	RE	100 Ø	Rodding eye.
S26	77.18	75.98	1.20	PPIC	450 Ø	
S27	77.30	75.63	1.67	PPIC	450 Ø	Restricted access chamber.
S28	77.00	75.54	1.46	PPIC	600 Ø	Restricted access chamber.
RE29.1	76.95	76.45	0.50	RE	100 Ø	Rodding eye.
S29	77.10	76.20	0.90	PPIC	450 Ø	
RE30.1	76.75	76.25	0.50	RE	100 Ø	Rodding eye.
S30	76.76	76.12	0.64	PPIC	450 Ø	
S31	76.75	75.97	0.78	PPIC	450 Ø	PPIC catchpit min 300mm sump.
S32	76.40	75.24	1.16	-	-	Aco V-Septor 1000 Hydrodynamic Separator
RE33.1	77.05	76.55	0.50	RE	100 Ø	Rodding eye.
S33	76.95	76.40	0.55	PPIC	450 Ø	
RE34.1	77.05	76.55	0.50	RE	100 Ø	Rodding eye.
S34	76.95	76.25	0.70	PPIC	450 Ø	PPIC catchpit min 300mm sump.