












Tree Survey Report

Client: Wolsley Trust
 Site: Healthy Living centre





Ref.	What 3 Words	Species	Description	Measurements	Survey Notes	Str. Condition	Phys. Condition	Target Range	Size	PoF	RoH	Inspect Period	Recommendations	Photo
G005	///rash.skings.gasp	Horse Chestnut (<i>Aesculus hippocastanum</i>) Norway Maple x3 (<i>Acer platanoides</i>) European Lime x2 (<i>Tilia x europaea</i>) European hop-hornbeam (<i>Ostrya carpinifolia</i>)	Target # - building Target # - car park	Height (m): 9 Crown Radius (m): 4 Diameter (mm): 420 Trees: 7 Life Stage: Early Mature Life Exp.: 10+ Years	Vitality good - historically pollarded car park trees with approx 4-5 years growth Ash tree with severe ADB	Fair	Fair	Property(3) £20,000 - £2,000	Property	PoF(4) 1/1K - 1/10K	1/300K	1 Year	Control Measures 1: Fell single Ash tree in group Re-pollard trees (except for hornbeam) to previous cut height circa 6 metres Timescale: 16-Apr-2024 (6 Months) Recommendations: Replace ash with gingko	
G010	///taps.raves.ladder	Common Ash x2 (<i>Fraxinus excelsior</i>)	Tree in open space Target # - building Target # - car park	Height (m): 13 Crown Radius (m): 5 Diameter (mm): 480 Trees: 2 Life Stage: Mature Life Exp.: <10 years	Vitality fair - 2 ash trees growing as cohesive group. ADB throughout canopy.	Fair	Poor	Property(3) £20,000 - £2,000	Property	PoF(3) 1/100 - 1/1K	1/30K	1 Year	Control Measures 1: Sectional dismantle and fell. Timescale: 16-Apr-2024 (6 Months) Recommendations: Replant with 2 lime trees	
G011	///marker.tr.eat.fears	Common Lime x2 (<i>Tilia x vulgaris</i>)	Target # - building Target # - footpath	Height (m): 14 Crown Radius (m): 4 Diameter (mm): 350 Trees: 2 Life Stage: Early Mature Life Exp.: 20+ Years	Vitality good - trees encroaching on adjacent building	Good	Good	Property(4) £2,000 - £200	Property	PoF(6) 1/100K - 1/1M	1/300M	1 Year	Control Measures 1: No action required. Timescale: Management Recommendations: Crown reduce by 2-3 metres allowing for up to 2 metres clearance from building	

Ref.	What 3 Words	Species	Description	Measurements	Survey Notes	Str. Condition	Phys. Condition	Target Range	Size	PoF	RoH	Inspect Period	Recommendations	Photo
G012	///boxing.e mail.cave	Sycamore x4 (<i>Acer pseudoplatanus</i>)	Target # - building Target # - footpath Target # - road	Height (m): 12 Crown Radius (m): 4 Diameter (mm): 400 Trees: 4 Life Stage: Early Mature Life Exp.: 20+ Years	Vitality good	Good	Good	Property(4) £2,000 - £200	Property	PoF(6) 1/100K - 1/1M	1/300M	1 Year	No action required. Timescale: Management	
G016	///mint.onio ns.lunch	Leyland Cypress x6 (<i>Cupressocyparis leylandii</i> X)	Tree in open space Target # - footpath	Height (m): 15 Crown Radius (m): 4 Diameter (mm): 380 Trees: 6 Life Stage: Early Mature Life Exp.: 10+ Years	Vitality fair - trees growing as cohesive group	Fair	Fair	Human(5) 2/day - 2/week	Size(3) 250mm - 110mm dia.	PoF(5) 1/10K - 1/100K	1/5B	1 Year	No action required. Timescale: Management	No Photo
G017	///opera.ord er.town	Black Hybrid Poplar x4 (<i>Populus x canadensis</i>)	Tree in open space Target # - building Target # - dwelling Target # - footpath	Height (m): 22 Crown Radius (m): 7 Diameter (mm): 700 Trees: 4 Life Stage: Mature Life Exp.: <10 years	Vitality fair - 4 trees with significant lean in an easterly direction towards neighbouring properties due to Leyland cypress group. Trees have reached maturity.	Fair	Fair	Property(3) £20,000 - £2,000	Property	PoF(4) 1/1K - 1/10K	1/300K	1 Year	Control Measures 1: Pollard all 4 trees at 4 metres in height. Timescale: 16-Apr-2024 (6 Months) Recommendations: Replant with walnut trees and tulip trees	
G020	///answer.g ossip.shared	Common Lime x7 (<i>Tilia x vulgaris</i>)	Target # - building Target # - footpath	Height (m): 9 Crown Radius (m): 4 Diameter (mm): 320 Trees: 7 Life Stage: Semi Mature Life Exp.: 20+ Years	Vitality good - trees historically pollarded	Good	Good	Property(4) £2,000 - £200	Property	PoF(6) 1/100K - 1/1M	1/300M	1 Year	Control Measures 1: No action required. Timescale: Management Recommendations: Repollard all trees to previous pollard points	
T001	///paused.fi ag.pinch	Black Hybrid Poplar (<i>Populus x canadensis</i>)	Target # - car park	Height (m): 15 Crown Radius (m): 5 Diameter (mm): 1310 Life Stage: Mature Life Exp.: <10 years	Vitality fair - tree historically pollarded at 8 metres Fruiting bodies on main stem Hollowing when tapped with mallet on northern aspect Tree leans NW over parking area	Fair	Fair	Property(3) £20,000 - £2,000	Property	PoF(4) 1/1K - 1/10K	1/300K	1 Year	Re-pollard at previous cut point approximately 8 metres from ground level. PICUS test to understand extent of decay. Timescale: 16-Apr-2024 (6 Months)	

Ref.	What 3 Words	Species	Description	Measurements	Survey Notes	Str. Condition	Phys. Condition	Target Range	Size	PoF	RoH	Inspect Period	Recommendations	Photo
T002	///deep.vital .host	Weeping Ash (<i>Fraxinus excelsior</i> 'Pendula')	Target # - car park	Height (m): 7 Crown Radius (m): 4 Diameter (mm): 430 Life Stage: Semi Mature Life Exp.: <10 years	Vitality poor - ADB throughout crown	Fair	Poor	Human(3) 7/hour 2/hour	Size(2) 450mm - 260mm dia.	PoF(3) 1/100 - 1/1K	1/100K	1 Year	Control Measures 1: Sectional dismantle and fell. Timescale: 16-Apr-2024 (6 Months) Recommendations: Replant with Tulip Tree	
T003	///heat.outfi t.lime	Weeping Beech (<i>Fagus sylvatica</i> 'Pendula')	Target # - car park	Height (m): 10 Crown Radius (m): 6 Diameter (mm): 610 Life Stage: Mature Life Exp.: 10+ Years	Vitality good - large calous wood on main trunk, unusual. Tree historically pollarded	Fair	Fair	Property(3) £20,000 - £2,000	Property	PoF(5) 1/10K - 1/100K	1/3M	1 Year	No action required. Timescale: Management	
T004	///wiser.you th.focus	Wild Cherry (<i>Prunus avium</i>)	Target # - car park	Height (m): 6 Crown Radius (m): 2 Diameter (mm): 220 Life Stage: Semi Mature	Dead tree	Dead	Dead	Property(3) £20,000 - £2,000	Property	PoF(2) 1/10 - 1/100	1/3K	1 Year	Straight fell Timescale: 16-Apr-2024 (6 Months)	
T006	///rigid.scul pture.upon	Goat Willow (<i>Salix caprea</i>)	Target # - building Target # - footpath Target # - road	Height (m): 8 Crown Radius (m): 4 Diameter (mm): 310 Life Stage: Semi Mature Life Exp.: 10+ Years	Vitality fair - historically coppiced tree Bark included junctions at base	Fair	Fair	Vehicle(2) 4,700 - 480 @ 50kph (32mph)	Size(3) 250mm - 110mm dia.	PoF(5) 1/10K - 1/100K	1/5M	1 Year	No action required. Timescale: Management	No Photo
T007	///rift.faces. when	Common Lime (<i>Tilia x vulgaris</i>)	Tree in open space Target # - building Target # - footpath	Height (m): 14 Crown Radius (m): 4 Diameter (mm): 400 Life Stage: Early Mature Life Exp.: 20+ Years	Vitality good - ivy clad tree restricts inspection of main stem NW crown encroaching on main building	Good	Good	Property(3) £20,000 - £2,000	Property	PoF(5) 1/10K - 1/100K	1/3M	1 Year	Control Measures 1: No action required. Timescale: Management Recommendations: Reuce NW aspect away from building by leaving a 2 metres gap.	

Ref.	What 3 Words	Species	Description	Measurements	Survey Notes	Str. Condition	Phys. Condition	Target Range	Size	PoF	RoH	Inspect Period	Recommendations	Photo
T008	///tilt.panel.crown	Common Lime <i>Tilia x vulgaris</i>	Tree in open space Target # - building Target # - footpath	Height (m): 14 Crown Radius (m): 4 Diameter (mm): 400 Life Stage: Early Mature Life Exp.: 20+ Years	Vitality good - ivy clad tree restricts inspection of main stem NW crown encroaching on main building Tree historically pruned on NW aspect.	Good	Good	Property(3) £20,000 - £2,000	Property	PoF(5) 1/10K - 1/100K	1/3M	1 Year	Control Measures 1: No action required. Timescale: Management Recommendations: Reduce NW aspect away from building by leaving a 2 metres gap.	
T009	///doing.corn.full	Common Ash <i>Fraxinus excelsior</i>	Target # - building Target # - car park	Height (m): 9 Crown Radius (m): 2 Diameter (mm): 400 Life Stage: Dead	Dead tree	Dead	Dead	Property(4) £2,000 - £200	Property	PoF(1) 1/1 - 1/10	1/3K	1 Year	Sectional dismantle and fell. Timescale: 16-Oct-2023 (Urgent)	
T013	///wakes.sounds.scenes	Black Hybrid Poplar <i>Populus x canadensis</i>	Target # - building Target # - car park Target # - footpath Target # - road	Height (m): 15 Crown Radius (m): 5 Diameter (mm): 1250 Life Stage: Mature Life Exp.: <10 years	Vitality poor - tree has recently been pollarded high (15 metres) Large fruiting bodies at base significant hollowing on NW aspect	Poor	Poor	Property(3) £20,000 - £2,000	Property	PoF(3) 1/100 - 1/1K	1/30K	1 Year	Monolith tree at 4 metres from ground level Timescale: 16-Apr-2024 (6 Months)	
T014	///flame.list.cute	Black Hybrid Poplar <i>Populus x canadensis</i>	Target # - car park Target # - footpath	Height (m): 14 Crown Radius (m): 5 Diameter (mm): 1100 Life Stage: Mature Life Exp.: <10 years	Vitality fair - tree recently pollarded high. Large bark included junction at 1 metre from ground level	Fair	Fair	Property(3) £20,000 - £2,000	Property	PoF(4) 1/1K - 1/10K	1/300K	1 Year	Control Measures 1: No action required. Timescale: Management Recommendations: No action required.	

Ref.	What 3 Words	Species	Description	Measurements	Survey Notes	Str. Condition	Phys. Condition	Target Range	Size	PoF	RoH	Inspect Period	Recommendations	Photo
T015	///slide.stud.narrow	Black Hybrid Poplar (<i>Populus x canadensis</i>)	Target # - car park Target # - footpath	Height (m): 14 Crown Radius (m): 5 Diameter (mm): 1100 Life Stage: Mature Life Exp.: <10 years	Vitality fair - tree recently pollarded high.	Fair	Fair	Property(3) £20,000 - £2,000	Property	PoF(4) 1/1K - 1/10K	1/300K	1 Year	Control Measures 1: No action required. Timescale: Management Recommendations: No action required.	
T018	///stroke.tulip.unrealistic	Common Ash (<i>Fraxinus excelsior</i>)	Tree in open space Target # - building Target # - footpath	Height (m): 15 Crown Radius (m): 5 Diameter (mm): 700 Life Stage: Mature Life Exp.: <10 years	Vitality poor - ADB throughout canopy Eastern aspect of trunk has significant delamination of bark	Poor	Poor	Property(3) £20,000 - £2,000	Property	PoF(2) 1/10 - 1/100	1/3K	1 Year	Sectional dismantle and fell. Timescale: 16-Apr-2024 (6 Months)	
T019	///hush.forum.hung	Lombardy Poplar (<i>Populus nigra italica</i>)	Tree in open space Target # - car park	Height (m): 13 Crown Radius (m): 2 Diameter (mm): 310 Life Stage: Semi Mature Life Exp.: 20+ Years	Vitality good	Good	Good	Property(4) £2,000 - £200	Property	PoF(6) 1/100K - 1/1M	1/300M	1 Year	No action required. Timescale: Management	No Photo