







Reef Directional

Reef CCT Directional Wall Light Black
Code: AREELEDWLD

Category	Wall Lights
Application	Hospitality, Outdoor, Residential, Retail
Specification	Architectural



PRODUCT FEATURES

- Durable outdoor directional wall light suitable for residential and hospitality applications
- Choice of matt white or black finishes
- CCT selectable between 3000K, 4000K and 6000K
- Non-dimmable
- Installation in either upward or downward orientation
- Polycarbonate construction ideal for coastal applications
- Unique lockable installation base plate with push fit loop-in loop-out terminals for ease of installation

GENERAL INFORMATION	
Wattage	5W
Lumens Delivered	430lm - 410lm (3000K - 6000K)
Lm/W	85lm/W - 82lm/W (3000K - 6000K)
Beam Angle	90
CRI	80
CCT	3000/4000/6000K
Input	220/240V
Operating Temp	-20°C - 40°C
SDCM	6
Product Weight without Packaging	0.215 kg

TECHNICAL INFORMATION	
Light Source	LED
Colour / Finish	Black
IP Rating	IP65
Class Protection	2
Internal / External	Internal / External
Surface / Recessed / Suspended	Wall
Lumen Depreciation	L80 54,000h
Warranty (Years)	3
CE Mark	Yes
Diameter	85 mm
Height	128 mm

