

All levels and dimensions to be checked on site prior to construction / fabrication; report discrepancies immediately.

This drawing is copyright protected.

REVISION		
A	120324	PVs updated TF

NBS Specification : Q37

BIODIVERSE ROOF SPECIFICATION
Contractor Design Element; subject to equal & approved specification
Products

Drainage Layer
Material: Thermoformed recycled polypropylene
 TBC by specialist contractor design / consultant civil engineer

- Depth:
- Retention Volume:
- Horizontal Flow Rate:
- Vertical Flow Rate:
- Compressive Strength: 150kPa

Filter Membrane
Material: Thermally strengthened non-woven polypropylene

- Mass: 0.120 kg/m²
- Thickness: 2mm

Extensive Biodiverse Substrate
Material: Lightweight crushed brick & expanded clay substrate. Inorganic and organic growing medium consisting of crushed brick, expanded clay and organic matter of composted bark fines

- **Depth: 80-150mm**
- Porosity: 63%
- Water Holding Capacity: 25-30%
- Bulk Density DIN EN 1097-3: 1 T/m³
- Density at Max Water Holding Capacity: 1.25 T/m³

PH Value: 7.0-8.0
 Vegetation Planting Mix: Various wildflower species in plug plant trays and seed form
 Root Ball Size (plugs): 50mm
 Coverage Rate (seeds): Varies; up to 5g/m²
 Coverage Rate (Plugs): 10 per m²
 Vegetation Coverage: 5% minimum

Habitat Creation / Biodiversity Enhancements
 Log / Sand Piles

Edge Retaining/Separating Profile
Material: Aluminium

- Description/Profile: Slotted; 3m length
- Height: 100mm (subject to system build-up/depth)

Inspection/Access Chambers
Material: Plastic coated steel

- Dimensions: 250x250mm
- Height: 80mm
- Colour: Black
- Access Covers: Black, plastic coated steel with handle
- Features: 300x300mm flange attached for stability and to lap filter sheet

Vegetation Barrier
Material: Rounded washed pebbles (20-40mm)

- Depth: 70mm (subject to system build-up/depth)

Width: 300mm minimum Execution

Edge Retaining Profile Installation
 Cutting: Neat, accurate and without spalling

- Junctions: vertical, secured using proprietary connectors
- Position: True to line and level. Smooth continuous lines
- Fixing: Loose laid onto fleece, ballasted by weight on foot plate, or secured to waterproof membrane using proprietary fixing system
- Suitable for pitched roofs of 5 degrees or less

Inspection Chamber Installation
 Location: Install centrally over rainwater outlet

- Orientation: Align parallel with adjacent features
- Bedding: Position flanges on to crowns of drainage layer
- Backfill: Ballast flanges with pebbles
- Surround: 300mm diameter circle/square of 20-40 rounded pebbles

COMPLETION
Inspection
 Timing: Prior to handover
 Notice period (minimum): 3 working days
 Completion
 General: Leave the works in a clean and tidy condition
 Surfaces: Clean immediately prior to handover
 Outlets: Clean and clear of any obstructions
 Completed green roofs: Protect from adjacent or high level working as best as possible.

Installation Generally

- Preparation: Clear all surfaces of debris
- Timing: After certification of waterproof membrane integrity
- Surface condition: Visually inspect waterproof membrane, report any damage
- Faults in waterproof membrane: Report prior to commencement of works
- Contamination: Do not use materials detrimental to healthy growth of plants
- Storage: Do not overload - point loads avoided
- Outlets: Do not block
- Outlet grilles: Installed

Adverse Weather

- Unfinished work: Secure for damage and wind uplift
- Conditions: Do not install or work with frozen materials

Drainage Layer Installation

- Extent: Loose lay continuously over entire roof area
- Fitting: Close butt-joint boards or rolls; staggering joints if applicable
- Upstands: Cut to fit 300mm from penetrations and outlets, using a heavy duty knife or smooth-toothed saw

Filter Membrane Installation

- Extent: Loose lay continuously over entire roof area
- Fitting: Loose laid (bonded to drainage board)
- Joints: Minimize
- Overlaps (minimum): 150mm overlap excess on drainage roll

Growing Medium Installation
 Handling: Minimize handling. Deliver to roof in small sacks, bulk bag or pump, spreading the specified depth on to filter sheet, allowing the settlement factor of 20%

Conditions: Handle in the driest condition possible. Do not handle or install when wet or frozen

Layers:

- Depth: 80-150 mm settled
- Sequence: Gently firm each layer before spreading the next. Vegetation Installation

Handling Seeds:

- Extent: Continuous and even across area to be planted
- Timing: Not to be installed if temperature is below 0C
- Storage: Must be stored in a cool and shaded area; not to be stacked excessively

Application

- Wildflower seeds to be installed within 48 hours of delivery. Irrigate to saturation.
- Watering: Thoroughly, after laying and account for climatic variation and seasonality.


Documentation
 Timing: Submit at handover
 Contents:

- Growing Medium declaration of analysis
- Manufacturers guarantees and warranties
- Maintenance Procedures
- Record Drawings showing the location of planting and associated features
- Number of copies: 1

Green Roofs Maintenance Procedure
 This set of procedures is a guide outlining the minimum maintenance measures required to keep a green roof in its designed state.

The plant selection includes a species mix which will provide a balanced plant community on the roof. This will require basic maintenance to ensure a sustainable system for the long term.

Living roof maintenance is best carried out twice to four times annually, during springtime and in late autumn, or as required. Monitoring/controlling the effect of leaf litter to the vegetation is important; this can be deemed to be beneficial to biodiversity, but may need to be removed if this begins to affect plant life.



EGR SPECIES MIX
[subject to specialist contractor design]

Wildflower Species Flower


Birdsfoot Trefoil - Lotus corniculatus
 Black Medick - Medicago lupulina
 Common Knapweed - Centaurea nigra
 Corn Chamomile - Anthemis arvensis
 Corn Cockle - Agrostemma githago
 Corn Marigold - Chrysanthemum segetum
 Cornflower - Centaurea cyanus
 Cowslip - Primula veris
 Field Forget-Me-Not - Myosotis arvensis
 Field Poppy - Papaver rhoeas
 Foxglove - Digitalis purpurea
 Goatsbeard - Tragopogon
 Greater Knapweed - Centaurea scabiosa
 Hoary Plantain - Plantago media
 Ladys Bedstraw - Galium verum
 Meadow Buttercup - Ranunculus acris
 Musk Mallow - Malva moschata
 Night-flowering Catchfly Silene noctiflora
 Ox-eye Daisy - Leucanthemum vulgare
 Red Campion - Silene dioica
 Ribwort Plantain - Plantago lanceolata
 Salad Burnet - Sanguisorba minor ssp minor
 Self Heal Prunella - vulgaris
 Sorrel - Rumex acetosa
 White Campion - Silene alba
 Wild Carrot - Daucus carota
 Wild Clary - Agrimonia
 Yarrow - Achillea millefolium

Companion grasses:
 Common Bentgrass - Agrostis castellana
 Crested Dogstail - Cynosurus cristatus
 Sheep's Fescue - Festuca ovina
 Smooth Stalked Meadow Grass - Poa pratensis
 Strong Creeping Red Fescue - Festuca rubra rubra

Sedum species:
 Sedum Acre Aureum
 Sedum Album Athough
 Sedum Reflexum
 Sedum Voodoo
 Sedum Album Coral Carpet

Material Key:

- Biodiverse Roof 226sqm
- Photovoltaic panels on proprietary feet system
Brown roof below PV Panels
- Composite Roof Panel on ext. structural frame
- Lift Overrun Insulated panel lined in single ply membrane
- Single Ply Insulated gutters on prop. straps and fixings



PLANNING

SCALE	DATE	DRAWN	CHECKED
1:200@A1	JAN'24	HM	TF

PROJECT
EQT EXETER
 400 Edgware Road,
 Cricklewood, London: NW2 6ND

DRAWING
Roof Plan
 (Extension to existing building)

Threesixty Architecture

10 MONTROSE STREET
 GLASGOW
 G1 1RE

0141 229 7575
 www.360architecture.com