LEGEND

Private Utility Duct

FP Feeder Pillar
(Lucy Zodion 4812 Mini Feeder Pillar 163mm x 170mm)

Private Bollard
1m Gemma Hamilton black 20w NW LED with factory fitted photocell

Private Street Lighting Column Type B
5m Tubular section galvanized steel with glass flake root treatment. Post top mounted Orangeleck Aria Mini 1.64mm NW LED factory finished in RAL 9005 Black Analed mini 10 WTX 4.0 70 450 1843 10N2M3X003XXXX NICHIA 219C 4000K with 0-degree tilt.

Trees - Within Private Court Yards
As detailed within B20003-401C_402C_403C_404C_405C 406C_407C_Stanton Cross Parcel 10a & 10b Detailed Planting Plan

NOTES
1. ALL ELECTRICAL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH BS 7671:2018 IET WIRING REGULATIONS 18TH EDITION.
2. COLUMNS & BOLLARDS TO BE ELECTRICALLY TESTED UPON COMPLETION OF WORKS.
3. AS LAID POSITION OF SERVICES TO BE RECORDED BY GPS AND PROVIDED TO VISTRY NHC, IN ACCORDANCE WITH CDM 2015.

RESIDUAL DESIGN HAZARDS

CONTRACTORS MUST SEEK MOST UP-TO-DATE UTILITY DRAWINGS BEFORE ANY WORK COMMENCES. UTILITIES MUST BE SCANNED AND LOCATED TO IDENTIFY AS-LAID LOCATION OF SERVICES PRIOR TO EXCAVATION.

HAND EXCAVATIONS OR VAC-EXCAVATION ONLY.

ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH THE HSE HS47 GUIDANCE - AVOIDING DANGER FROM UNDERGROUND SERVICES.

RESIDUAL HAZARD DESCRIPTION
1. SITE WIDE STRIKING OF UNDERGROUND UTILITY SERVICES DURING INSTALLATION, MAINTENANCE & DEMOLITION.

CHECK LIST	INITIALS
COLUMN & FEEDER PILLAR CLASHES WITH WINDOWS	
COLUMN & BOLLARD POSITIONS WITH TREES	
DUCTING FROM PLOTS OR FEEDER PILLARS	
COLUMN SHIELDS WITHIN CLOSE PROXIMITY TO WINDOWS	

Rev	Date	Details	By
C	09.05.23	Relocation of column to the rear of 69 to accommodate RH change.	LS
B	09.01.23	Bollards outside 229, 260, 262 & 265 moved. Street lighting columns outside 135, 84 & 307 moved. Feeder Pillars FP2, FP13 moved. 1 x bollard added in court yards 228-230. Column outside 68 relocated and 1 x column added in court yard 67-70. Feeder Pillars 14 to 17 added to site layout including, trees and ducting.	LS
A	11.11.22	Removable of Adoptable Street Lighting & addition of lighting within 177 - 181 + FP13.	LS

Vistry
Vistry - Housebuilding
Northern Home Counties
Building 7
Caldecotte Lake Business Park
Milton Keynes
MK7 8JU
Tel: 01908 088500

SITE
STANTON-CROSS
PARCEL_10_(PHASE_2)

DRAWING TITLE
PRIVATE-STREET-LIGHTING LAYOUT

DRAWN BY	DATE	DRAWING NO.	REV
LS	06.06.22	WE10B-09	C
SCALE: 1:500@A0	CHECKED/DATE		