## **BARNARD & ASSOCIATES Ltd.**

Consulting Civil & Structural Engineers 18 Northfields Prospect Northfields London SW18 1PE



**☎** Email barnard@intonet.co.uk



# INTRODUCTION TO BELOW GROUND DRAINAGE STORMWATER CALCULATIONS TO

# STAPLEFORD COTTAGE, DANES HILL WOKING GU22

#### **JOB NUMBER 23170**

TJB				
MD				
APRIL 24				



#### Introduction

These calculations been prepared to be submitted in response to planning condition 4.

A stormwater drainage strategy has been previously produced and approved by the planning authority in relation to the proposed development and should be read in conjunction with these calculations.

The condition states the following:

# **Planning Condition 4**

No works pursuant to the development hereby permitted (other than any permitted demolition to ground level) must be undertaken until a surface water drainage scheme for the site based on sustainable drainage principles and an assessment of the hydrological and ydrogeological context of the development has been submitted to and approved in writing by the Local Planning Authority.

The drainage scheme must demonstrate that the surface water run-off generated up to and including the 1 in 100 plus climate change critical storm will not exceed the run-off from the existing site following the corresponding rainfall event.

*The drainage scheme details to be submitted for approval must also include:* 

- i. Calculations demonstrating no increase in surface water runoff rates and volumes discharged from the site compared to the existing scenario up to the 1 in 100 plus climate change storm event.
- ii. Calculations demonstrating no on site flooding up to the 1 in 30 storm event and that any flooding between the 1 in 30 and 1 in 100 plus climate change storm event will be safely stored on site ensuring no overland flow routes.
- iii. Detailed drainage plans showing where surface water will be accommodated on site.
- iv. A management and maintenance plan for the lifetime of the development which must include the arrangements for adoption by any public body or statutory undertaker, or any other arrangements to secure the operation of the sustainable drainage scheme throughout its lifetime.

The surface water drainage scheme must be fully implemented in accordance with the approved details prior to the first occupation of the development hereby permitted and thereafter be permanently managed and maintained in accordance with the approved details.



## Stormwater drainage proposals

The stormwater drainage system proposes a soakaway so that all run-off is infiltrated into the ground, as is the existing situation.

Item i) is therefore met confirming that no surface water run-off will occur from the site for the 1 in 100 year plus climate change storm event.

The soakaway is sized to cater for the full run-off from the 1 in 100 year plus climate change storm event so that no overland flow will occur. Item ii) is therefore met by the drainage proposals.

Item iii) Layout drawings of the proposed stormwater drainage system are to be read in conjunction with these calculations.

Item iv) A management and maintenance plan has been produced separately and should be read in conjunction with these calculations.



D.J.CD	
Brief Description of Project	Construction of new residential building on site with majority of accommodation located below ground floor level, level with the existing ground level at front of site.
	The ground level at the rear of the site is level with the proposed lower ground floor level accommodation.
	New foul drainage networks to discharge to existing gravity foul sewer outfall that currently serves the existing cottage on the site.
	New stormwater drainage to discharge to soakaway at the rear of the site.
Ground Conditions	Thin layer of made ground over
	Bagshot Formation, encountered to the limit of investigation of 22.0m depth. The formation was overwhelmingly granular in nature with occasional cohesive horizons.
	Orange brown, brown and grey mottled silty sand with occasional clay layers in the lower reaches to 15.7m depth.
	A grey green very silty sand below 15.7 m depth transgressing to firm to stiff dark grey and brown very sandy clay at 17 m depth. Clay was underlain by a grey silty sand with occasional clay layers to 22 m depth.
	In situ testing of sand indicates medium dense, becoming very dense state of compaction.
	Groundwater encountered at 17.5, rising to 15.8m
Consideration of SUDS drainage proposals for the development.	Refer to Whitby Wood Drainage Strategy Report P450434-WW-XX-ZZ-RP-C-0002 dated September 2021, approved at Planning Stage of the project for further information.
development.	It is intended to adhere to the proposal set out in the drainage strategy approved at planning stage.
Description of below ground Foul-water	Piped foul sewer outfall to front of site to discharge under gravity to ex foul sewer outfall manhole.
drainage system proposed	Foul drains at lower ground floor and basement drains to pump station in basement which discharges via rising main to existing foul sewer outfall manhole.
Description of below ground storm-water drainage system proposed	Piped stormwater to discharge at rear of site into soakaways via rainwater harvesting tank.
<u> </u>	L



Infiltration	BRE365 infiltration testing is to be undertaken on site at the rear, close to
Rate	the proposed footprint of the Soakaways.
	Access to undertake the infiltration testing is not yet available, until the existing buildings on the site are demolished. For modelling purposes, an infiltration rate of 1 x $10^{-6}$ has been assumed in the soakaway design.  Once infiltration testing is complete, the size of the soakaway will be adjusted accordingly.
Software Used and modelling	The storm-water drainage system has been designed using XP Solutions MicroDrainage Source Control version 2016.1.1.
of stormwater drainage system	A model has been created to calculate the volume of the soakaway required to cater for a 1 in 100y +40% event using the FSR rainfall method.
Exceedance Design	The exceedance flow route will remain as existing.



### Consider Design of below ground stormwater drainage

A below ground drainage strategy has been previously prepared and approved for the development proposal.

Refer to Whitby Wood Drainage Strategy Report dated September 2021 reference P450434-WW-XX-ZZ-RP-C-002 (actually produced by Cube Engineers)

- The strategy proposes the following
- Foul discharge to sewers
- Storm water to soakaway
- Design to accommodate 1 in 100 + 40% storm

Refer to the approved strategy report, which should be read in conjunction with this report

#### **Infiltration Rate**

The drainage strategy assumed an infiltration rate of 1 x 10<sup>-6</sup> m/sec in the initial drainage review

# **BRE 365 Testing**

Access is not yet available for BRE 365 testing

Currently, a working assumption of infiltration rate of  $1 \times 10^{-6}$  m/sec is assumed for the new drainage proposals (Fine Silty Sand)

### Soakaway Sizing

Final sizing of soakaway will follow the completion of BRE 365 infiltration tests on site.

# **Consider Catchment Area of Stormwater Design**

The built area is 579m<sup>2</sup>

The rear patio area is  $61\text{m}^2$ 

The total area is 640m<sup>2</sup>

Allow 10% for future increase =  $0.1 \times 640 = 64 \text{m}^2$ 

Design for catchment = 704m<sup>2</sup>

Consider soakaway to cater for catchment of  $704m^2$  and assumed infiltration rate of 1 x  $10^{-6}$  m/sec



# **Stapleford Cottage:- coordinates 501531, 158100**

(GU22 7HQ)

 $Catchment = 704m^2 = 0.07ha$ 

Infiltration rate =  $1 \times 10^{-6} \text{ m/s}$  assumed

Equates to  $1 \times 10^{-6} \times 60 \times 60 = 3.6 \times 10^{-3} \text{ m/hr} (0.036 \text{ m/hr})$ 

Cover level 36.700m

Invert level 35.343m -- 1.4m deep

Set soakaway below 1.4m depth

IL = 36.700 - 3.4 = 33.3m

Try cellular storage:- 28m<sup>2</sup> x 2m deep



8m x 3.5m x 2m deep



# From the following Microdrainage print out:-

Cellular soakaway  $28m^2$  (2m deep)  $\rightarrow$  (8x3.5)

Half drain down time = 1376minutes = 22.9hrs

Utilise  $8m \times 3.5m \times 2m$  deep cellular storage with assumed infiltration rate =  $1 \times 10^{-6}$  m/sec

BRE 365 testing required to verify infiltration rate assumed


Soakaway size TBC after infiltration testing

DR4

P03

1250

CU CONSULTING BE ENGINEERS INDICATIVE IRRIGATION NETWORK ILLUSTRATION, DESIGN BY SPECIAL PROPOSED SURFACE WATER DR whitby wood PROPOSED FOUL WATER RISING PROPOSED INFILTRATION DEVIC 91-94 LOWDON SELTAB, UNITED KINGDOM +44 (D)20 7442 2216 WWW WHIDSWOOD COM BELOW GROUND DRAINAGE LAYOUT PRELIMINARY ISSUE AOR 04/08/2021 POJ 24/09/7027 PRE-MINIMEN SAIR
POJ 14/09/7027 PRE-MINIMEN SAIR
V PAGE-77827 PRE-MINIMEN SAIR
V PAGE-77827 PRE-MINIMEN SAIR STAPLEFORD COTTAGE AP 1056-C-DR-0100 A.P 056 EXSTING PRIVATE GRANIAGE ASSUMED TO SERVE ENSTING SHOWN PEDCATMER, LIME, EVIL AND CONDITION THE D FEALCHLE PAYING TO SUNCES COURTYARD, TO DIS MAR SURFACE WATER HETWORK THROUGH THE PRO DOSTING PRIVATE DRAINAGE TO SE ARANDONED WHIRE NO LONGER REQUIRED



Barnard & Associates Ltd				Page 1
18 Northfields Prospect		STAPLEFORD COTTAGE		
Northfields		501531, 158100		
London SW18 1PE	3	Soakaway 1 x 10-6		Micco
Date 15/03/2024		Designed by TJB		Designation
File SA FSR Cellular.SRCX		Checked by	- 2	nianiada
XP Solutions		Source Control 2019.1		

# Summary of Results for 100 year Return Period (+40%)

Half Drain Time : 1376 minutes.

	Stori Even		Max Level (m)	Max Depth (m)	Max Infiltra (1/s)		Max Overflow Σ (1/s)	Max Outflow (1/s)	Max Volume (m³)	Status	j
15	min	Summer	33.975	0.675		0.2	0.0	0.2	18.0	ОК	
30	min	Summer	34.182	0.882		0.2	0.0	0.2	23.5	ОК	
60	min	Summer	34.392	1.092		0.3	0.0	0.3	29.0	ОК	
120	min	Summer	34.594	1.294		0.3	0.0	0.3	34.4	ОК	
180	min	Summer	34.701	1.401		0.3	0.0	0.3	37.3	ОК	
240	min	Summer	34.766	1.466	999	0.3	0.0	0.3	39.0	ОК	
360	min	Summer	34.844	1.544		0.3	0.0	0.3	41.1	ОК	
480	min	Summer	34.888	1.588		0.3	0.0	0.3	42.2	ОК	:
600	min	Summer	34.910	1.610		0.3	0.0	0.3	42.8	ОК	
720	min	Summer	34.919	1.619		0.3	0.0	0.3	43.1	ОК	
960	min	Summer	34.911	1.611		0.3	0.0	0.3	42.9	0 к	
1440	min	Summer	34.876	1.576		0.3	0.0	0.3	41.9	ОК	_
2160	min	Summer	34.811	1.511		0.3	0.0	0.3	40.2	ОК	
2880	min	Summer	34.742	1.442		0.3	0.0	0.3	38.4	ОК	
4320	min	Summer	34.613	1.313		0.3	0.0	0.3	34.9	O K	
5760	min	Summer	34.503	1.203		0.3	0.0	0.3	32.0	- 0 K	
7200	min	Summer	34.405	1.105		0.3	0.0	0.3	29.4	0 K	
8640	min	Summer	34.317	1.017		0.3	0.0	0.3	27.0	0 K	0
10080	min	Summer	34.236	0.936		0.2	0.0	0.2	24.9	O K	
15	min	Winter	34.057	0.757		0.2	0.0	0.2	20.1	O K	

		Stor	m	Rain	Flooded	Overflow	Time-Peak	
		Even	t	(mm/hr)	Volume	Volume	(mins)	
					(m³)	(m³)		
	15	min	Summer	138.153	0.0	0.0	19	
	30	min	Summer	90.705	0.0	0.0	34	
	60	min	Summer	56.713	0.0	0.0	64	
	120	min	Summer	34.246	0.0	0.0	124	
	180	min	Summer	25.149	0.0	0.0	182	
	240	min	Summer	20.078	0.0	0.0	242	
	360	min	Summer	14.585	0.0	0.0	362	
	480	min	Summer	11.622	0.0	0.0	482	
	600	min	Summer	9.738	0.0	0.0	602	
	720	min	Summer	8.424	0.0	0.0	720	
	960	min	Summer	6.697	0.0	0.0	934	
	1440	min	Summer	4.839	0.0	0.0	1154	
	2160	min	Summer	3.490	0.0	0.0	1536	
	2880	min	Summer	2.766	0.0	0.0	1960	
	4320	min	Summer	1.989	0.0	0.0	2768	
	5760	min	Summer	1.573	0.0	0.0	3624	
	7200	min	Summer	1.311	0.0	0.0	4400	
	8640	min	Summer	1.129	0.0	0.0	5192	
1	0800	min	Summer	0.994	0.0	0.0	5960	
	15	min	Winter	138.153	0.0	0.0	19	

©1982-2019 Innovyze

Barnard & Associates Ltd		Page 2
18 Northfields Prospect	STAPLEFORD COTTAGE	
Northfields	501531, 158100	
London SW18 1PE	Soakaway 1 x 10-6	Micro
Date 15/03/2024	Designed by TJB	Drainage
File SA FSR Cellular.SRCX	Checked by	namaye
XP Solutions	Source Control 2019.1	

# Summary of Results for 100 year Return Period (+40%)

		Stor		Max Level	Max Depth		Max tration	Max n Overflow	Max Σ Outflow	Max Volume	Status	
				(m)	(m)	(1	./s)	(1/s)	(1/s)	(m³)		
	30	min	Winter	34.289	0.989		0.3	0.0	0.3	26.3	ОК	
	60	min	Winter	34.525	1.225		0.3	0.0	0.3	32.6	OK	
S	120	min	Winter	34.755	1.455		0.3	0.0	0.3	38.7	ОК	
	180	min	Winter	34.877	1.577		0.3	0.0	0.3	42.0	ОК	
	240	min	Winter	34.953	1.653		0.3	0.0	0.3	44.0	ОК	
	360	min	Winter	35.046	1.746		0.3	0.0	0.3	46.5	ОК	
	480	min	Winter	35.101	1.801		0.3	0.0	0.3	47.9	ОК	
	600	min	Winter	35.132	1.832		0.4	0.0	0.4	48.7	ОК	
	720	min	Winter	35.149	1.849		0.4	0.0	0.4	49.2	ОК	
	960	min	Winter	35.154	1.854		0.4	0.0	0.4	49.3	ОК	
	1440	min	Winter	35.109	1.809		0.3	0.0	0.3	48.1	ОК	
	2160	min	Winter	35.036	1.736		0.3	0.0	0.3	46.2	ОК	
	2880	min	Winter	34.947	1.647		0.3	0.0	0.3	43.8	ОК	
	4320	min	Winter	34.765	1.465		0.3	0.0	03	39.0	ОК	
	5760	min	Winter	34.608	1.308		0.3	0.0	0.3	34.8	ОК	
	7200	min	Winter	34.470	1.170		0.3	0.0	0.3	31.1	ОК	
	8640	min	Winter	34.345	1.045		0.3	0.0	0.3	27.8	O K	
	10080	min	Winter	34.234	0.934		0.2	0.0	0.2	24.8	O K	

	Stor	m	Rain	Flo	oded	Over	flow	Time	-Peak	
	Even	it v	(mm/hr)	Vo.	lume	Vol	une	(m	ins)	
				(1	n³)	(m	<sup>3</sup> )			
-30	min	Winter	90.705		0.0	128	0.0		34	
60	min	Winter	56.713		0.0		0.0		64	
120	min	Winter	34.246		0.0		0.0		122	
180	min	Winter	25.149		0.0		0.0		180	
240	min	Winter	20.078		0.0		0.0		240	
360	min	Winter	14.585		0.0		0.0		356	
480	min	Winter	11.622		0.0		0.0		472	
600	min	Winter	9.738		0.0		0.0		586	
720	min	Winter	8.424		0.0		0.0		700	
960	min	Winter	6.697		0.0		0.0		916	
1440	min	Winter	4.839		0.0		0.0		1298	
2160	min	Winter	3.490		0.0		0.0		1640	
2880	min	Winter	2.766		0.0		0.0		2104	
4320	min	Winter	1.989		0.0		0.0		3024	
5760	min	Winter	1.573		0.0	1	0.0		3872	
7200	min	Winter	1.311		0.0		0.0		4752	
8640	min	Winter	1.129		0.0		0.0		5536	
10080	min	Winter	0.994		0.0		0.0		6352	

Barnard & Associates Ltd	Page 3	
18 Northfields Prospect	STAPLEFORD COTTAGE	
Northfields	501531, 158100	
London SW18 1PE	Soakaway 1 x 10-6	Micro
Date 15/03/2024 .	Designed by TJB	
File SA FSR Cellular.SRCX	Checked by	Drainage
XP Solutions	Source Control 2019.1	

# Rainfall Details

 Return
 Return
 Period (years)
 100
 Cv (Summer)
 0.750

 Region
 England and Wales
 Cv (Winter)
 0.840

 M5-60 (mm)
 20.000
 Shortest Storm (mins)
 15

 Ratio R
 0.400
 Longest Storm (mins)
 10080

 Summer Storms
 Yes
 Climate Change %
 +40

## Time Area Diagram

Total Area (ha) 0.070

Time (mins) Area From: To: (ha)

0 4 0.070

Barnard & Associates Ltd		Page 4
18 Northfields Prospect	STAPLEFORD COTTAGE	
Northfields	501531, 158100	
London SW18 1PE	Soakaway 1 x 10-6	Micro
Date 15/03/2024	Designed by TJB	Drainage
File SA FSR Cellular.SRCX	Checked by	Dialiacle
XP Solutions	Source Control 2019.1	

#### Model Details

Storage is Online Cover Level (m) 36.700

#### Cellular Storage Structure

Invert Level (m) 33.300 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.03600 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.03600

# Depth (m) Area (m²) Inf. Area (m²) Depth (m) Area (m²) Inf. Area (m²) 0.000 28.0 28.0 2.001 0.0 74.0 2.000 28.0 74.0 74.0 74.0

## Pipe Overflow Control

Diameter (m) 0.150 Entry Loss Coefficient 0.500 Slope (1:X) 60.0 Coefficient of Contraction 0.600 Length (m) 10.000 Upstream Invert Level (m) 35.340 Roughness k (mm) 0.600

# whitby wood

Project: Stapleford Cottage, Danes Hill, Woking, GU22 7HQ


Client: Dr Roland Tegeder

P450434-WW-XX-ZZ-RP-C-0002

# **Drainage Strategy Report**

Prepared for Full Planning Submission to Woking Borough Council

September 2021



# Stapleford Cottage Drainage Strategy

Project No.: 1056


Document Ref: 1056-C-RP-0100

Issue: P3

Date: 28/09/2021

Prepared in partnership with

whitby wood





# Stapleford Cottage Drainage Strategy

# **QUALITY CONTROL**

ISSUE:	DATE:	PREPARED:	CHECKED:	APPROVED:	COMMENTS:
P1	04/08/2021 AP AOR AOR		2021 AP AOR AOR		PRELIMINARY ISSUE
P2	13/09/2021	/2021 AP AOR AO		AOR	PRELIMINARY ISSUE
P3	28/09/2021	AP	AOR	AOR	PRELIMINARY ISSUE

- Cube Consulting Engineers 1056-C-RP-0100 Page | 1



# **CONTENTS**

Quality Control	1
Contents	2
Executive summary	3
Introduction	4
Existing Site	5
Site location	5
Existing Drainage	5
Existing Foul Water Sewers	5
Existing Surface Water Sewers	6
Proposed Drainage Strategy	7
Foul Water Drainage	7
Drainage Design Parameters	7
Proposed Foul Water Drainage Strategy	7
Surface Water Drainage	7
Drainage Design Parameters	7
Surface Water Disposal Hierarchy	8
Offsite Impact	8
Overland Flow and Exceedance	8
Drainage Maintenance Strategy	9
Manholes and Inspection Chambers	9
Soakaways	10



# **EXECUTIVE SUMMARY**

The existing site is understood to be served by a below ground foul water drainage network that discharges unrestricted to the offsite public sewers. It is understood the surface water from the existing site infiltrates into the ground via soakaway to the rear of the property.

A gravity below ground foul water drainage network is proposed to serve the new building, which will discharge unrestricted to the existing foul water public sewer in Danes Hill via the existing connection. Drainage from the lower levels of the proposed building will be pumped to ground floor where it will converge with discharge from the rest of the building and fall to the public sewer.

A separate gravity below ground surface water drainage network is also proposed, to collect surface water from the hardstanding areas and building roofs and discharge to soakaway in the rear garden, at a significantly lower level than the proposed building. Rainwater harvesting is also proposed to collect rainwater from the building roofs and reuse if for irrigation.

The proposed surface water drainage network will be deigned to accommodate a 1 in 100 year storm with a 40% allowance for climate change without flooding.

**Cube Consulting Engineers** 1056-C-RP-0100 Page | 3



# **INTRODUCTION**

Cube Consulting Engineers on behalf of Whitby Wood have been appointed to undertake this Drainage Strategy for Stapleford Cottage. The purpose of this document is to support the planning application for the project.

This Drainage Strategy has been produced in line with the requirements of the National Planning Policy Framework (NPPF) and the London Plan. In addition to these the following documents, polices and resources have been used to inform this document:

Surrey Council Design Guidance

This Drainage Strategy makes partial use of third party information and may contain Google maps, Environment Agency, BGS and Defra copyright information.

Cube Consulting Engineers
Page | 4



# **EXISTING SITE**

## SITE LOCATION

The proposed site is located in Woking, Surrey. The site area is 0.1 Ha. The site is occupied by an existing residential building and hardstanding area, that is to be demolished and replaced with a new residential building and hardstanding area. The extent of the site boundary in red can be seen in the figure below.

The site is centred at:

National Grid Reference: TQ015581
 Easting, Northing: 501536 , 158149
 Nearest Postcode: GU22 7HQ



Figure 1 - Proposed Site

## **EXISTING DRAINAGE**

## **Existing Foul Water Sewers**

There are dedicated foul water public sewers in Danes Hill, east of the site. It is assumed that the existing house connects to the public sewer in Danes Hill, south east of the site (chamber ref. 5101). It is assumed that a short length of private drainage links the house to the offsite public sewer.

Refer to Figure 2 below and Appendix A for further information. The site is shown bounded in green.

- Cube Consultir 1056-C-RP-0100






Figure 2 – Extract of Public Sewer Record

# Existing Surface Water Sewers

No surface water public sewers are shown on the public sewer records. It is assumed that the individual houses in this area have private drainage networks that discharge to onsite soakaways. Therefore, it is assumed that currently there is no surface water discharge leaving the site.



# PROPOSED DRAINAGE STRATEGY

#### FOUL WATER DRAINAGE

# Drainage Design Parameters

The below ground foul water drainage system will be designed in accordance with Design and Construction Guidance for foul and surface water sewers or "the Code", BS EN 752 Parts 3 & 4, and Building Regulations Approved Document H where appropriate.

# Proposed Foul Water Drainage Strategy

A below ground, gravity foul water drainage network is proposed to serve the proposed building at ground floor level. The discharge from the ground floor level will be collected and conveyed by gravity via a new piped network to the existing private foul water sewers located to the east of the building. From here the foul water will drain via the existing private foul sewers to the public foul water sewer in Danes Hill. Foul water will be discharged at an unrestricted rate.

Drainage from the lower ground levels will drain to the plant room on the lowest level, from where it will be pumped up to the proposed gravity drainage to the east of the building. From here it will converge with the foul discharge from the rest of the building and fall to the existing public sewer.

Discharge from the pools at lower ground floor levels will connect to the foul drainage subject to Thames Water approval. Pool design and discharge is to be advised by specialist.

Refer to the below ground drainage layout drawing 1056-C-DR-0100 in Appendix B for further details.

#### SURFACE WATER DRAINAGE

# Drainage Design Parameters

The below ground surface water drainage system will be designed in accordance with local policy, local Sustainable Drainage System (SuDS) guidance, national standards and best practice. Industry standards along with the Environment Agency and Design and Construction Guidance for foul and surface water sewers or "the Code" dictate that for below ground surface water systems:

- The system should not surcharge for a 1 in 2 year storm event;
- The system should not flood any part of the site in a 1 in 30 year storm event; and
- Controlled flooding of the site is permitted in a 1 in 100 year storm event including a climate change allowance provided the flood water is contained within the site and does not affect the safe ingress and egress from the site.

The Environment Agency have completed an assessment of the impacts of Climate Change on peak rainfall intensity for small catchments (less than 5km2). These are summarised in Table 1 extracted from EA guidance 'Flood Risk Assessments: Climate Change allowances' issued on 19th February 2016 with subsequent revisions.

APPLIES ACROSS	TOTAL POTENTIAL CHANGE	TOTAL POTENTIAL CHANGE	TOTAL POTENTIAL CHANGE
ALL OF ENGLAND	FOR '2020S' (2015 TO 2039)	FOR '2050S' (2040 TO 2069)	FOR '2080S' (2070 TO 2115)
Upper End	10%	20%	40%
Central	5%	10%	20%

Table 1: Peak rainfall intensity climate change allowances

A typical lifespan for a new development is 100 years, under national and local policy this development will be assessed against a 1 in 100 year storm event including a 40% climate change allowance using FEH rainfall.

**Cube Consulting Engineers** 1056-C-RP-0100 Page | 7



# Surface Water Disposal Hierarchy

In accordance with Building Regulations Approved Document H, all drainage strategies should manage surface water discharge based on the following hierarchy:

- 1. Infiltration or a soakaway on site;
- 2. Discharge to a watercourse; or
- 3. Discharge to a sewer.

Infiltration is proposed, by utilising soakaways to soak surface water into the ground. Ground conditions are understood to be suitable for infiltration and there is a garden to the rear of the building to accommodate a soakaway. The garden area where infiltration devices are proposed is lower than the building, so there is no risk of flood water from an exceedance event flooding the building. An assumed infiltration rate of 1x10<sup>-6</sup>m/s has been used in the design, based on the known ground conditions.

Infiltration testing is to be undertaken in due course to enable detailed design of the infiltration devices to be undertaken.

Rainwater harvesting is also proposed to intercept rainwater from the building roof and reuse it for irrigation.

The proposed surface water drainage strategy will result in all surface water being either captured for reuse on the site, or infiltrated into the ground on the site.

Refer to the below ground drainage layout drawing 1056-C-DR-0100 in Appendix B for further details. Refer to Appendix C for hydraulic modelling information.

## **OFFSITE IMPACT**

The proposed surface water drainage strategy outlined in this document demonstrates that the proposed drainage network included in the development will manage all surface water run off during events up to and including the 100 year return period storm including the upper end allowance for climate change. The development will result in no increase in flood risk downstream.

#### OVERLAND FLOW AND EXCEEDANCE

The proposed building is located at the high point of the site, with the land to the rear falling away. The infiltration device serving the site is located in the rear garden from where the ground falls away from the proposed building. The risk of the building flooding from exceedance event or blockage of the drainage network is therefore very low.

Refer to the exceedance flow routes on drawing 1056-C-DR-0100 in Appendix B for further details.

Cube Consulting Engineers
Page | 8



# DRAINAGE MAINTENANCE STRATEGY

The following drainage maintenance and management strategy has been produced in accordance with the SuDS Manual, best practice and manufactures guidance. This is not intended to be an exhaustive list but outline guidance for the recommended requirements which are to be reviewed and updated based on the specific site requirements. It is expected that the maintenance for the drainage of the proposed development will be undertaken by the management company and will be suitably qualified to undertake the required maintenance.

This schedule should be read in accordance with the manufacturer's guidance and the SuDS Manual.

# MANHOLES AND INSPECTION CHAMBERS

MAINTENANCE SCHEDULE	REQUIRED ACTION	TYPICAL FREQUENCY	
Regular Maintenance	Inspect chambers (from ground level) to ensure no build- up of water, debris or sediments are occurring in the chamber. If required clean or take remedial action. Do not attempt to enter chambers, refer to remedial actions.	6 monthly	
	Any public manholes are the responsibility of the sewerage undertaker and may require permissions to access or lift covers. Maintenance/monitoring of these chamber is not required, should any issues be identified these should be highlighted to the sewerage undertaker.	As deemed necessary by asset owner	
Remedial actions	Call out to drainage maintenance company for bespoke advice.  Entering manhole chambers is a dangerous task as they are a confined space with potential toxic gas and/or low oxygen environments. Any such, cleaning and repairs should always be handled by a qualified engineer with experience working in confined spaces.  Do not attempt to enter inspection chambers.	As required	
Monitoring	Visually inspect chambers (from ground level) to monitor any build-up of water, debris or sediments occurring in the chamber.	6 monthly of after large storms	

Table 2: Operation and maintenance requirements for manhole and inspection chambers



# SOAKAWAYS

MAINTENANCE SCHEDULE	required action	TYPICAL FREQUENCY	
Regular maintenance	Inspect for sediment and debris in pre-treatment components and floor of inspection tube or chamber and inside concrete manhole rings	Annually	
	Cleaning of gutters and any filters on downpipes	Annually (or as required based on inspections)	
	Trimming any roots that may be causing blockages	Annually (or as required)	
Occasional maintenance	Remove sediments and debris from pre-treatment components and floor of inspection tube or chamber and inside of concrete manhole rings.	As required, based on inspections	
Daga dial articus	Reconstruct soakaways and/or replace or clean void fill, if performance deteriorates or failure occurs	As required	
Remedial actions	Replacement of clogged geotextile (will require reconstruction of soakaway	As required	
Monitoring	Inspect silt traps and note rate of sediment accumulation	Monthly in the first year and then annually.	
	Check soakaway to ensure emptying is occurring	Annually	

Table 3: Operation and maintenance requirements for soakaways (from the SuDS Manual)



# Appendix A Thames Water Asset Plans



WW EXETER EX3 0LH

Search address supplied Stapleford House

Danes Hill Woking GU22 7HQ

Your reference Stapleford Cottage

Our reference ALS/ALS Standard/2021\_4460032

Search date 2 July 2021

## Knowledge of features below the surface is essential for every development

The benefits of this knowledge not only include ensuring due diligence and avoiding risk, but also being able to ascertain the feasibility of any development.

Did you know that Thames Water Property Searches can also provide a variety of utility searches including a more comprehensive view of utility providers' assets (across up to 35-45 different providers), as well as more focused searches relating to specific major utility companies such as National Grid (gas and electric).

Contact us to find out more.



Thames Water Utilities Ltd Property Searches, PO Box 3189, Slough SL1 4WW DX 151280 Slough 13



searches@thameswater.co.uk www.thameswater-propertysearches.co.uk





Search address supplied: Stapleford House, Danes Hill, Woking, GU22 7HQ

Dear Sir / Madam

An Asset Location Search is recommended when undertaking a site development. It is essential to obtain information on the size and location of clean water and sewerage assets to safeguard against expensive damage and allow cost-effective service design.

The following records were searched in compiling this report: - the map of public sewers & the map of waterworks. Thames Water Utilities Ltd (TWUL) holds all of these.

This searchprovides maps showing the position, size of Thames Water assets close to the proposed development and also manhole cover and invert levels, where available.

Please note that none of the charges made for this report relate to the provision of Ordnance Survey mapping information. The replies contained in this letter are given following inspection of the public service records available to this company. No responsibility can be accepted for any error or omission in the replies.

You should be aware that the information contained on these plans is current only on the day that the plans are issued. The plans should only be used for the duration of the work that is being carried out at the present time. Under no circumstances should this data be copied or transmitted to parties other than those for whom the current work is being carried out.

Thames Water do update these service plans on a regular basis and failure to observe the above conditions could lead to damage arising to new or diverted services at a later date.

#### **Contact Us**

If you have any further queries regarding this enquiry please feel free to contact a member of the team on 0800 009 4540, or use the address below:

Thames Water Utilities Ltd Property Searches PO Box 3189 Slough SL1 4WW

Email: searches@thameswater.co.uk

Web: www.thameswater-propertysearches.co.uk



#### **Waste Water Services**

Please provide a copy extract from the public sewer map.

Enclosed is a map showing the approximate lines of our sewers. Our plans do not show sewer connections from individual properties or any sewers not owned by Thames Water unless specifically annotated otherwise. Records such as "private" pipework are in some cases available from the Building Control Department of the relevant Local Authority.

Where the Local Authority does not hold such plans it might be advisable to consult the property deeds for the site or contact neighbouring landowners.

This report relates only to sewerage apparatus of Thames Water Utilities Ltd, it does not disclose details of cables and or communications equipment that may be running through or around such apparatus.

The sewer level information contained in this response represents all of the level data available in our existing records. Should you require any further Information, please refer to the relevant section within the 'Further Contacts' page found later in this document.

#### For your guidance:

- The Company is not generally responsible for rivers, watercourses, ponds, culverts
  or highway drains. If any of these are shown on the copy extract they are shown for
  information only.
- Any private sewers or lateral drains which are indicated on the extract of the public sewer map as being subject to an agreement under Section 104 of the Water Industry Act 1991 are not an 'as constructed' record. It is recommended these details be checked with the developer.

#### **Clean Water Services**

Please provide a copy extract from the public water main map.

With regard to the fresh water supply, this site falls within the boundary of another water company. For more information, please redirect your enquiry to the following address:

Affinity Water Ltd Tamblin Way Hatfield AL10 9EZ

Tel: 0345 3572401



### For your guidance:

- Assets other than vested water mains may be shown on the plan, for information only.
- If an extract of the public water main record is enclosed, this will show known public
  water mains in the vicinity of the property. It should be possible to estimate the
  likely length and route of any private water supply pipe connecting the property to
  the public water network.

## **Payment for this Search**

A charge will be added to your suppliers account.



#### Further contacts:

#### **Waste Water queries**

Should you require verification of the invert levels of public sewers, by site measurement, you will need to approach the relevant Thames Water Area Network Office for permission to lift the appropriate covers. This permission will usually involve you completing a TWOSA form. For further information please contact our Customer Centre on Tel: 0845 920 0800. Alternatively, a survey can be arranged, for a fee, through our Customer Centre on the above number.

If you have any questions regarding sewer connections, budget estimates, diversions, building over issues or any other questions regarding operational issues please direct them to our service desk. Which can be contacted by writing to:

Developer Services (Waste Water) Thames Water Clearwater Court Vastern Road Reading RG1 8DB

Tel: 0800 009 3921

Email: developer.services@thameswater.co.uk


#### Clean Water queries

Should you require any advice concerning clean water operational issues or clean water connections, please contact:

Developer Services (Clean Water) Thames Water Clearwater Court Vastern Road Reading RG1 8DB

Tel: 0800 009 3921


Email: developer.services@thameswater.co.uk



<u>Thames Water Utilities Ltd</u>, Property Searches, PO Box 3189, Slough SL1 4W, DX 151280 Slough 13 T 0800 009 4540 E <u>searches@thameswater.co.uk</u> I <u>www.thameswater-propertysearches.co.uk</u>

Manhole Reference	Manhole Cover Level	Manhole Invert Level
5101	40.42	38.81
511A	n/a	n/a
5201	40.08	38.93
521A	n/a	n/a
4201	39.45	38.29

The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.



The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of an kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified before any works are undertaken. Crown copyright Reserved

Scale:	1:1790
Width:	500m
Printed By:	Rveldhur
Print Date:	02/07/2021
Map Centre:	501503,15816
Grid Reference:	TQ0158SE

C	٦m	m	۵ı	nt	c

# **ALS/ALS Standard/2021\_4460032**

NB: Level quoted in metres Ordnance Newlyn Datum. The value -9999.00 indicates no Survey information is available.

REFERENCE	COVER LEVEL	INVERT LEVEL
5101	40.42	38.81
3902	25.24	23.8
6001	34.92	33.1
2102	42.51	40.48
2052	39.83	39.18
3952	28.41	26.94
5901	35.72	33.91
2202	42.68	39.42
4952	25.34	
4951	25.15	23.77
6951	31.08	30.38
3959	32.35	29.56
3903	25.77	23.83
3907	25.63	23.9
4901	25.82	23.64
3202	41.52	40.57
3957	24.44	22.78
4353	39.91	38.9
2902	28.01	23.86
4201	39.45	38.29
3901	24.7	23.76
5201	40.08	38.93
2151	42.49	41.42
2251	42.62	40.44
3951	26.48	25.29
3954	25.89	25.08
6202	38.83	36.32
4302	39.25	37.79
2351	41.98	40.63
3053	26.81	25.56
231A		
231B		
321A		
2201	42.64	38.96
491B		
491A		
391H		
4351	39.26	38.12
391B		
391D		
731A		
291A		
291C		
511A		
291G		

REFERENCE	COVER LEVEL	INVERT LEVEL
5001	40.29	38.12
3052		
6952	33.45	32.73
2953		
5301	38.99	37.13
4903	25.76	23.65
5302	37.64	36.45
4902	24.66	23.7
4303	39.8	38.37
3955	25.82	24.53
3201		
3051	38.41	37.39
2051	40.13	39.28
4352	39.28	38.38
3301	40.99	39.46
3351	40.85	39.88
3953	24.69	22.91
2152	40.37	39.49
3905	25.73	23.75
2904	26.12	24
3054	25.84	24.54
4301	39.2	37.56
2203		
6901	32.98	30.56
3908	25.88	23.82
6201	38.59	36.15
391G		
6101	37.84	35.06
3956	24.65	22.87
3906	25.81	23.81
331A		
231C		
321B		
391A		
401A		
621A		
5351	38.94	37.93
6251	38.86	37.36
391C		
2901	24.97	23.85
391J		
291E		
521A		
391K		
631A		




#### Public Sewer Types (Operated & Maintained by Thames Water)

Foul: A sewer designed to convey waste water from domestic and industrial sources to a treatment works.

-- O-- Surface Water: A sewer designed to convey surface water (e.g. rain water from roofs, yards and car parks) to rivers or watercourses.

Combined: A sewer designed to convey both waste water and surface water from domestic and industrial sources to a treatment works.















#### Notes:

- 1) All levels associated with the plans are to Ordnance Datum Newlyn.
- 2) All measurements on the plans are metric.
- 3) Arrows (on gravity fed sewers) or flecks (on rising mains) indicate direction of
- 4) Most private pipes are not shown on our plans, as in the past, this information has not been recorded.
- 5) 'na' or '0' on a manhole level indicates that data is unavailable.

#### Sewer Fittings

A feature in a sewer that does not affect the flow in the pipe. Example: a vent is a fitting as the function of a vent is to release excess gas.

Air Valve

Dam Chase

Meter

Vent Column

#### Operational Controls

A feature in a sewer that changes or diverts the flow in the sewer. Example: A hydrobrake limits the flow passing downstream.

Control Valve

Drop Pipe

Ancillary

Weir

#### End Items

End symbols appear at the start or end of a sewer pipe. Examples: an Undefined End at the start of a sewer indicates that Thames Water has no knowledge of the position of the sewer upstream of that symbol, Outfall on a surface water sewer indicates that the pipe discharges into a stream or river.

Outfall



Undefined End

Inlet

#### Other Symbols

Symbols used on maps which do not fall under other general categories

Public/Private Pumping Station

Change of characteristic indicator (C.O.C.I.)

Summit

#### Areas

Lines denoting areas of underground surveys, etc.

Agreement


Operational Site

Chamber

Tunnel

Conduit Bridge

#### Other Sewer Types (Not Operated or Maintained by Thames Water)



6) The text appearing alongside a sewer line indicates the internal diameter of the pipe in milimetres. Text next to a manhole indicates the manhole reference number and should not be taken as a measurement. If you are unsure about any text or symbology present on the plan, please contact a member of Property Searches on 0800 009 4540.

#### **Terms and Conditions**

All sales are made in accordance with Thames Water Utilities Limited (TWUL) standard terms and conditions unless previously agreed in writing.

- 1. All goods remain in the property of Thames Water Utilities Ltd until full payment is received.
- 2. Provision of service will be in accordance with all legal requirements and published TWUL policies.
- 3. All invoices are strictly due for payment 14 days from due date of the invoice. Any other terms must be accepted/agreed in writing prior to provision of goods or service, or will be held to be invalid.
- 4. Thames Water does not accept post-dated cheques-any cheques received will be processed for payment on date of receipt.
- 5. In case of dispute TWUL's terms and conditions shall apply.
- 6. Penalty interest may be invoked by TWUL in the event of unjustifiable payment delay. Interest charges will be in line with UK Statute Law 'The Late Payment of Commercial Debts (Interest) Act 1998'.
- 7. Interest will be charged in line with current Court Interest Charges, if legal action is taken.
- 8. A charge may be made at the discretion of the company for increased administration costs.

A copy of Thames Water's standard terms and conditions are available from the Commercial Billing Team (cashoperations@thameswater.co.uk).

We publish several Codes of Practice including a guaranteed standards scheme. You can obtain copies of these leaflets by calling us on 0800 316 9800

If you are unhappy with our service you can speak to your original goods or customer service provider. If you are not satisfied with the response, your complaint will be reviewed by the Customer Services Director. You can write to her at: Thames Water Utilities Ltd. PO Box 492, Swindon, SN38 8TU.

If the Goods or Services covered by this invoice falls under the regulation of the 1991 Water Industry Act, and you remain dissatisfied you can refer your complaint to Consumer Council for Water on 0121 345 1000 or write to them at Consumer Council for Water, 1st Floor, Victoria Square House, Victoria Square, Birmingham, B2 4AJ.

#### Ways to pay your bill


Credit Card	BACS Payment	Telephone Banking	Cheque
Call <b>0800 009 4540</b> quoting your invoice number starting CBA or ADS / OSS	Account number 90478703 Sort code 60-00-01 A remittance advice must be sent to: Thames Water Utilities Ltd., PO Box 3189, Slough SL1 4WW. or email ps.billing@thameswater. co.uk	By calling your bank and quoting: Account number 90478703 Sort code 60-00-01 and your invoice number	Made payable to 'Thames Water Utilities Ltd' Write your Thames Water account number on the back. Send to: Thames Water Utilities Ltd., PO Box 3189, Slough SL1 4WW or by DX to 151280 Slough 13

Thames Water Utilities Ltd Registered in England & Wales No. 2366661 Registered Office Clearwater Court, Vastern Rd, Reading, Berks, RG1 8DB.



Appendix B
Proposed Drainage Layout Drawing






THE COPYRIGHT IN THIS DRAWING IS VESTED IN CUBE CONSULTING ENGINEERS LIMITED AND NO LICENCE OR ASSIGNMENT OF ANY KIND HAS BEEN, OR IS, GRANTED TO ANY THIRD PARTY WHETHER BY PROVISION OF COPIES OR

1. DO NOT SCALE FROM THIS DRAWING.

ORIGINALS OR OTHERWISE UNLESS AGREED IN WRITING.

- 2. ALL LEVELS ARE IN METRES ABOVE ORDINANCE DATUM AND ALL DIMENSIONS ARE IN METRES UNLESS NOTED OTHERWISE.
- 3. IN LINE WITH NPPF GUIDANCE THE DRAINAGE DESIGN has been designed with no flooding for a 100YEAR STORM PLUS 40% CLIMATE CHANGE EVENT.
- 4. BELOW GROUND DRAINAGE PIPEWORK SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND IN COMPLIANCE WITH BS EN 12056, BS EN 752 AND THE NATIONAL BUILDING REGULATIONS APPROVED DOCUMENT H.
- THE INFORMATION SHOWN ON THIS DRAWING IS PRELIMINARY AND INDICATIVE ONLY AND IS SUBJECT TO CHANGE THROUGH SITE INVESTIGATIONS, DETAILED DESIGN AND CO-ORDINATION.
- 6. DISCHARGE RATES AND LOCATIONS ARE SUBJECT TO CONFIRMATION THROUGH SURVEY AND DISCUSSIONS WITH THE LLFA AND THAMES WATER.
- DRAINAGE CHANNELS AND GULLIES WILL BE REQUIRED TO SERVE HARDSTANDING AREAS. THESE ARE SHOWN INDICATIVELY AT THIS STAGE BUT AN ALLOWANCE FOR THEM SHOULD BE MADE. ADDITIONAL GULLIES WILL BE REQUIRED, TO BE ADDED AS THE DEIGN DEVELOPS
- 8. INFILTRATION TESTING TO BE UNDERTAKEN TO VERIFY SUITABILITY OF INFILTRATION DEVICES AND
- INFORMATION THEIR DESIGN 9. SOAKAWAY LOCATION AND TYPE SHOWN INDICATIVELY. SOAKAWAY TO BE SUFFICIENTLY DEEP TO ENSURE WATER INFILTRATES TO GROUND BELOW THE EXISTING ONSITE RETAINING STRUCTURES. SOAKAWAY DESIGN TO BE CONFIRMED BASED ON INFILTRATION RESULTS.



# PRELIMINARY ISSUE

91-94 LOWER MARSH

LONDON SE1 7AB, UNITED KINGDOM +44 (0)20 7442 2216 www.whitbywood.com



STAPLEFORD COTTAGE

BELOW GROUND DRAINAGE LAYOUT

JOB NO. 1056	DATE 04	SCA 4/08/2021	1:250
DRN AP	DES AP	CHK	APP AOR
DRAWING NU	MBER		REV
1056-C	-DR-0100		P03



Appendix C Proposed Hydraulic Calculations

Cube Consulting Engineers		Page 1
24 Carronade Court		
London		
N7 8EP		Micro
Date 04/08/2021 11:16	Designed by Cillian Ryan	Drainage
File STAGE 2 MODEL.MDX	Checked by	Dialilade
Innovyze	Network 2020.1.3	

#### STORM SEWER DESIGN by the Modified Rational Method

#### Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

Return Period (years) 100

M5-60 (mm) 20.700

Ratio R 0.439

Maximum Rainfall (mm/hr) 50

Maximum Time of Concentration (mins) 30

Foul Sewage (1/s/ha) 0.000

Volumetric Runoff Coeff. 0.750

Model - England and Wales

PIMP (%) 100

Add Flow / Climate Change (%) 0

Minimum Backdrop Height (m) 0.200

Maximum Backdrop Height (m) 1.500

Min Design Depth for Optimisation (m) 1.200

Min Vel for Auto Design only (m/s) 1.00

Designed with Level Soffits

#### Free Flowing Outfall Details for Storm

Out	fall	Outfall	c.	Level	I.	Level		Min	D,L	W
Pipe	Number	Name		(m)		(m)	I.	Level (m)	(mm)	(mm)
	1.007			30.510	:	29.548		0.000	0	0

Cube Consulting Engineers		Page 2
24 Carronade Court		
London		
N7 8EP		Micro
Date 04/08/2021 11:16	Designed by Cillian Ryan	Drainage
File STAGE 2 MODEL.MDX	Checked by	Dialilade
Innovyze	Network 2020.1.3	

#### Storage Structures for Storm

#### Cellular Storage Manhole: 5, DS/PN: 1.007

Invert Level (m) 27.832 Safety Factor 1.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.03600

Depth	(m)	Area	(m²)	Inf.	Area	(m²)	Depth	(m)	Area	(m²)	Inf.	Area	(m²)
0.	000		25.0			40.0	2.	.001		0.0			90.6
2.	000		25.0			90.6							

Cube Consulting Engineers		Page 3
24 Carronade Court		
London		
N7 8EP		Micro
Date 04/08/2021 11:16	Designed by Cillian Ryan	Drainage
File STAGE 2 MODEL.MDX	Checked by	Dialilade
Innovyze	Network 2020.1.3	

### 1 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

#### Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000 Hot Start (mins) 0 MADD Factor \*  $10m^3$ /ha Storage 2.000 Hot Start Level (mm) 0 Inlet Coefficient 0.800 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (1/per/day) 0.000 Foul Sewage per hectare (1/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 1 Number of Online Controls 1 Number of Time/Area Diagrams 0 Number of Offline Controls 0 Number of Real Time Controls 0

#### Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.350
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 20.000 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0 DVD Status OFF Analysis Timestep Fine Inertia Status OFF DTS Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440
Return Period(s) (years) 1, 30, 100
Climate Change (%) 0, 0, 40

											Water
	US/MH			Return	Climate	First	(X)	First (Y	(Z) First (Z)	Overflow	Level
PN	Name	S	torm	Period	Change	Surch	narge	Flood	Overflow	Act.	(m)
1.000	1	1.5	Winter	1	+0%	100/15	Winter				39.771
1.001	2		Winter	1	+0%		Summer				39.391
1.002	3	15	Winter	1	+0%	100/15	Summer				38.041
2.000	4	15	Winter	1	+0%	100/15	Summer				36.388
1.003	4	15	Winter	1	+0%	100/15	Summer				32.790
1.004	6	15	Winter	1	+0%	100/15	Summer				32.061
1.005	6	15	Winter	1	+0%	100/15	Summer				31.329
1.006	8	15	Winter	1	+0%						30.595
1.007	5	1440	Winter	1	+0%						28.222

PN	US/MH Name	Surcharged Depth (m)			Overflow (1/s)	Half Drain Time (mins)	Flow	Status	Level Exceeded
1.000	1	-0.079	0.000	0.10			0.9	OK	
1.001	2	-0.043	0.000	0.60			3.2	OK	
1.002	3	-0.059	0.000	0.35			3.3	OK	
2.000	4	-0.062	0.000	0.31			2.2	OK	
1.003	4	-0.060	0.000	0.34			5.5	OK	
1.004	6	-0.060	0.000	0.34			5.5	OK	

Cube Consulting Engineers		Page 4
24 Carronade Court		
London		
N7 8EP		Micro
Date 04/08/2021 11:16	Designed by Cillian Ryan	Drainage
File STAGE 2 MODEL.MDX	Checked by	Dialilade
Innovyze	Network 2020.1.3	

# $\frac{1 \text{ year Return Period Summary of Critical Results by Maximum Level (Rank 1)}}{\text{for Storm}}$

		Surcharged	Flooded			Half Drain	Pipe		
	US/MH	Depth	Volume	Flow /	Overflow	Time	Flow		Level
PN	Name	(m)	(m³)	Cap.	(1/s)	(mins)	(1/s)	Status	Exceeded
1.005	6	-0.062	0.000	0.30			5.4	OK	
1.006	8	-0.067	0.000	0.24			5.4	OK	
1.007	5	-1.711	0.000	0.00		1368	0.0	OK	

Cube Consulting Engineers		Page 5
24 Carronade Court		
London		
N7 8EP		Micro
Date 04/08/2021 11:16	Designed by Cillian Ryan	Drainage
File STAGE 2 MODEL.MDX	Checked by	Dialilade
Innovyze	Network 2020.1.3	

## 30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

#### Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000 Hot Start (mins) 0 MADD Factor \*  $10m^3$ /ha Storage 2.000 Hot Start Level (mm) 0 Inlet Coefficient 0.800 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 1 Number of Online Controls 1 Number of Time/Area Diagrams 0 Number of Offline Controls 0 Number of Real Time Controls 0

#### Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.350
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 20.000 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0 DVD Status OFF Analysis Timestep Fine Inertia Status OFF DTS Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440
Return Period(s) (years) 1, 30, 100
Climate Change (%) 0, 0, 40

											Water
	US/MH			Return	Climate	First	t (X)	First (Y)	First (Z)	Overflow	Level
PN	Name	S	torm	Period	Change	Surcl	narge	Flood	Overflow	Act.	(m)
	_										
1.000	1	15	Winter	30	+0%	100/15	Winter				39.783
1.001	2	15	Winter	30	+0%	30/15	Summer				39.508
1.002	3	15	Winter	30	+0%	100/15	Summer				38.085
2.000	4	15	Winter	30	+0%	100/15	Summer				36.416
1.003	4	15	Winter	30	+0%	100/15	Summer				32.825
1.004	6	15	Winter	30	+0%	100/15	Summer				32.097
1.005	6	15	Winter	30	+0%	100/15	Summer				31.361
1.006	8	15	Winter	30	+0%						30.620
1.007	5	1440	Winter	30	+0%						28.613

		Surcharged	Flooded			Half Drain	Pipe		
	US/MH	Depth	Volume	Flow /	Overflow	Time	Flow		Level
PN	Name	(m)	(m³)	Cap.	(1/s)	(mins)	(1/s)	Status	Exceeded
1.000	1	-0.067	0.000	0.24			2.2	OK	
1.001	2	0.074	0.000	1.74			9.3	SURCHARGED	
1.002	3	-0.015	0.000	0.99			9.3	OK	
2.000	4	-0.034	0.000	0.76			5.5	OK	
1.003	4	-0.025	0.000	0.91			14.7	OK	
1.004	6	-0.024	0.000	0.93			14.8	OK	
				∩1 Q Q 2 <b>_</b>	2020 Inr	011170			

Cube Consulting Engineers		Page 6
24 Carronade Court		
London		
N7 8EP		Mirro
Date 04/08/2021 11:16	Designed by Cillian Ryan	Drainage
File STAGE 2 MODEL.MDX	Checked by	Dialilade
Innovyze	Network 2020.1.3	

### 

PN	US/MH Name	Surcharged Depth (m)	Flooded Volume (m³)		Overflow (1/s)	Half Drain Time (mins)	Pipe Flow (1/s)	Status	Level Exceeded
1.005	6	-0.030	0.000	0.83			14.8	OK	
1.006	8	-0.041	0.000	0.65			14.7	OK	
1.007	5	-1.319	0.000	0.00		1368	0.0	OK	

Cube Consulting Engineers		Page 7
24 Carronade Court		
London		
N7 8EP		Micro
Date 04/08/2021 11:16	Designed by Cillian Ryan	Drainage
File STAGE 2 MODEL.MDX	Checked by	praniada
Innovyze	Network 2020.1.3	

## 100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

#### Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000 Hot Start (mins) 0 MADD Factor \*  $10m^3$ /ha Storage 2.000 Hot Start Level (mm) 0 Inlet Coefficient 0.800 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 1 Number of Online Controls 1 Number of Time/Area Diagrams 0 Number of Offline Controls 0 Number of Real Time Controls 0

#### Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.350
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 20.000 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0 DVD Status OFF Analysis Timestep Fine Inertia Status OFF DTS Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440
Return Period(s) (years) 1, 30, 100
Climate Change (%) 0, 0, 40

											Water
	US/MH			Return	Climate	Firs	t (X)	First (Y	) First (Z)	Overflow	Level
PN	Name	S	torm	Period	Change	Surcl	narge	Flood	Overflow	Act.	(m)
	_					/ . =					
1.000	1	15	Winter	100	+40%	100/15	Winter				39.861
1.001	2	15	Winter	100	+40%	30/15	Summer				39.803
1.002	3	15	Summer	100	+40%	100/15	Summer				39.495
2.000	4	15	Winter	100	+40%	100/15	Summer				36.578
1.003	4	15	Winter	100	+40%	100/15	Summer				33.747
1.004	6	15	Winter	100	+40%	100/15	Summer				32.591
1.005	6	15	Winter	100	+40%	100/15	Summer				31.502
1.006	8	15	Winter	100	+40%						30.632
1.007	5	1440	Winter	100	+40%						29.208

	US/MH	Surcharged Depth	Flooded Volume	Flow /	Overflow	Half Drain Time	Pipe Flow		Level		
PN	Name	(m)	(m³)	Cap.	(1/s)	(mins)	(1/s)	Status	Exceeded		
1.000	1	0.011	0.000	0.41			3.8	FLOOD RISK			
1.001	2	0.368	0.000	2.94			15.8	SURCHARGED			
1.002	3	1.395	0.000	1.62			15.2	SURCHARGED			
2.000	4	0.128	0.000	1.36			9.7	SURCHARGED			
1.003	4	0.897	0.000	1.30			21.2	SURCHARGED			
1.004	6	0.471	0.000	1.23			19.6	SURCHARGED			
	©1982-2020 Innovyze										

Cube Consulting Engineers		Page 8
24 Carronade Court		
London		
N7 8EP		Micro
Date 04/08/2021 11:16	Designed by Cillian Ryan	Drainage
File STAGE 2 MODEL.MDX	Checked by	Dialilade
Innovyze	Network 2020.1.3	

# $\frac{100 \text{ year Return Period Summary of Critical Results by Maximum Level (Rank}}{1) \text{ for Storm}}$

		Surcharged	Flooded			Half Drain	Pipe		
	US/MH	Depth	Volume	Flow /	Overflow	Time	Flow		Level
PN	Name	(m)	(m³)	Cap.	(1/s)	(mins)	(1/s)	Status	Exceeded
1.005	6	0.111	0.000	1.07			19.1	SURCHARGED	
1.006	8	-0.029	0.000	0.84			19.1	OK	
1.007	5	-0.725	0.000	0.00		1344	0.0	OK	

Stapleford Cottage



Cube Consulting Engineers Ltd www.consultthecube.co.uk Registered in England and Wales Reg No. 12407198

