



RAIN CHAIN GULLY DETAIL

1. STONE RECEIVER ACTS AS SUMP TO RECEIVE RUN-OFF FROM RAIN CHAIN GULLY, LAID WITH FALL TO OUTLET GULLY.
2. OUTLET GULLY SET IN RECESSED RECEIVER WITH VERTICAL OUTLET AT BASE DROPPING TO COLLECTOR DRAIN BELOW.  
GULLY TO BE 100 MM DIAMETER OUTLET, WADE WB3 SERIES WITH VERTICAL THREADED OUTLET REFERENCE WB 304, OR SIMILAR.
3. RECESSED RECEIVER TO BE INFILLED WITH LOOSE COBBLES TO MASK OUTLET FROM VIEW.

| Revision | Description      | Date     | Checked |
|----------|------------------|----------|---------|
| T2       | MINOR UPDATE     | 09.04.24 | TB      |
| T1       | ISSUE FOR TENDER | 27.03.24 | TB      |

Status **TENDER ISSUE**

Drawing Title  
Rain chain gully at capping beam grid U

Architect  
SIGNUM SPACE

Scale  
1:10

Job  
STAPLEFORD COTTAGE  
WOKING GU22 7HQ

Drawn  
AM 13.03.24

Checked  
TB

**BARNARD & ASSOCIATES Ltd**  
Consulting Engineers  
18 Northfields Prospect  
Northfields, London, SW18 1PE  
Tel No. 0208 874 9005 Fax No. 0208 870 7386  
Email barnard@intonet.co.uk



Drg No.  
23170-715

Revision  
T2

F137 issue02 17.05.09