

Prefix	Tree No	Species	DBH (MM)	Height (M)	Age Class	Condition	Comments	Recommendations	Priority
T	8	Large-leaved Lime	600	10	M	F	Basal view restricted, large fair condition foliage, fair symmetry in crown. Lower west side of crown suppressed by leylandii below.	Crown raise to 3m, remove any deadwood, inspect base and unions from an ariel viewpoint, crown clean	Year 1
T	16	Atlantic Cedar	1200	20	OM	F	Deadwood present, signs consistent with historic failure, heavy overextending limbs, previous collar cuts showing good compartmentalisation.	Removal all deadwood greater than 25mm, reduce in weight overextending heavy limbs to reduce chance of failure, also to reduce wind sale. Reduce up to 3m on overextending lateral pendulous growth up into suitable growth points; only over greenery area and footpath - not upper crown. Inspect unions and overall condition from ariel view- suspend parking; 2 bays outside flats 34-42. MEWP Required	Year 1
T	19	Horse Chestnut	??	20	OM	F	Basal view limited due to epicormics, bifurcating stem at 2m, multiple cavities requiring aerial inspection as well as multiple unions. Deadwood present. Epicormics in tree obscuring views.	Crown clean and thin, inspect previous pruning wounds, cavities and unions. Report findings.	Year 1
G	1	Large-leaved Lime	800	17	M	F	Basal inspection view obscured by epicormic growth. Lapsed pollards at 7m. Deadwood in canopies. 3rd tree in from T5 with swept stem, corrects at 4m, canopy asymmetrical on east side. Secondary most previous pruning points at approx. 10m. Fair condition and foliage size on all trees	Removal epicormic growth to crown break and inspect bases, remove deadwood.	Year 1

TPO Ref: 014 Tree Ref: G3

TPO Ref: 014 Tree Ref: G5

TPO Ref: 014 Tree Ref: G2

TPO Ref: 014 Tree Ref: G3