

# Traditional Standard Range®

## Wall Models



### Features & Benefits

- Extract/intake models in 4 sizes: 6", 7", 9" and 12"
- IPX4 Rated
- White fascia, wall sleeve and black external weather louvre
- Optional shutter available
- Manufactured in weather-resistant polymeric materials
- For the best performance from your fan, use an Ecotronic controller

### Classic Retro-Styled Ventilation

The proven Standard Range Wall models are designed to fit flush into most double brick walls using the rigid wall liner supplied with the unit. Provision is made within the liner for conduit entry. When installed, only the ivory fascia is visible on the internal wall face. The external weather louvre fits flush to the outside. A shutter is available as an accessory which can be easily fitted within the unit.

On new building work the installation and wiring of the wall liner can be completed prior to the final installation of the unit and controller. Fully shrouded connectors on the fascia automatically connect the wiring to the motor when fitted to the wall liner.

### Performance

Model	Extract Performance m <sup>3</sup> /h (l/s) F.I.D.	Watts MAX.	Sound dB(A) @ 3m	Amps @ 240V
S6/WL	340 (94)	32	39	0.16
S7/WL	544 (151)	34	35	0.16
S9/WL	856 (238)	53	43	0.24
S12/WL	1767 (491)	84	46	0.36

### Motor

The motor is purpose-designed. Suitable for running at any angle. Quiet running, enclosed, sealed for life ball bearings.

Supply voltage: 220-240V/1/50Hz.

Suitable for operation in ambient temperatures from -40°C to +50°C.

Fitted with Standard Thermal Overload Protection (S.T.O.P.).

### Shutter

#### Type SD/R

The extract/intake shutter fits inside the Vent-Axia unit and closes against unwanted back draughts. It can be fitted at the same time as the unit or at a later date if required. Airflow operated for extract use, cord operated lock for intake use.

### Controller

The Ecotronic controller is recommended for use with this model to give full function control of the fan including auto mode using an electro-mechanical sensor from Vent-Axia's sensor range. Alternatively, single speed extract is achieved using a normal On/Off switch.

### Models

Size	Stock Ref
S6WL	131510
S7WL	132510
S9WL	133510
S12WL	134510

### Shutters

Size	Stock Ref
S6SD/R	231710
S7SD/R	232710
S9SD/R	233710
S12SD/R	234710

### Dimensions (mm)

Size	6 in	7 in	9 in	12 in
A	279	279	279	279
B	203	279	279	356
C	279	362	362	448
Fixing hole Ø	235	311	311	400
Weight kg	4.1	5.7	6.7	10.1

