

13173w0003a Supporting Letter for Discharge of Conditions

Planning application approval number: F/YR21/0885/F

Site: 1-3 Hostmoor And 1 Martin Avenue, March, Cambridgeshire, PE15 0AX

Date: 29/02/24

Permission for the above planning application for the erection of a retail food store (Class E(a)) and accompanying car park was given subject conditions; this letter has been prepared to assist in the discharge of conditions 2,3 and 4, which relates to existing drainage and surface water drainage.

Responses from Craddys on how each requirement, has or will be achieved, is given below each recommendation.

The requirements of condition 2 are as follows:

Prior to any site works, a drainage survey of the retained existing drainage network should be carried out to confirm its presence and suitability for use within the proposed drainage strategy. This should demonstrate the existing pipe network is of suitable condition to continue accepting flows from the site and has a positive connection to the Anglian Water public sewer. If the flows cannot be accepted, then an alternative scheme shall be submitted to and approved by the LPA and the development shall be implemented in accordance with it.

Please refer to Appendix A for the drainage CCTV survey, which shows existing drainage. The existing pipe network is of suitable condition to continue accepting flows from the site.

Please refer to Appendix B for the Proposed Drainage Design. The proposed surface water manhole, S10, will be installed, to connect into the existing Public Surface Water MH – 1052 via a 150Ø pipe. Existing pipe to be relaid, so that the gradient matches existing. The proposed foul water manhole, Fw04 will be installed, to connect into the existing Foul MH. It will be an indirect connection to the foul sewer via a 100Ø pipe.

The requirements of condition 3 are as follows:

No laying of services, creation of hard surfaces or erection of a building shall commence until a detailed surface water drainage scheme for the site, based on the agreed Sustainable Drainage Strategy, Stirling Maynard Consulting Engineers, 3272 313, November 2021 has been submitted to and approved in writing by the LPA. The scheme shall subsequently be implemented in full accordance with the approved details prior to first occupation.

Please refer to Appendix B for the Proposed Drainage Design. Please refer to Appendix C for the Microdrainage Calculations.

The requirements of condition 4 are as follows:

No development, including preparatory works, shall commence until details of measures indicating how additional surface water run-off from the site will be avoided during the construction works have been submitted to and approved in writing by the Local Planning Authority. The applicant may be required to provide collection, balancing and/or settlement systems for these flows. The approved measures and systems shall be brought into operation before any works to create buildings or hard surfaces commence.


This information will be provided in the contractor's method statement, following planning permission, but prior to start of construction, to discharge this condition.

Appendix A – Drainage CCTV Survey

CCTV Drainage Survey

Craddys
Aldi March
Peterbough, PE15 0BW

CCTV DRAINAGE SURVEY REPORT



Place :



Sewer Surveys UK Ltd
14B Orgreave Close
Sheffield
Tel: 0114 2513481
Fax:
Email: info@sewersurveysuk.co.uk

Project-information

Project name :
ALDI MARCH

Project Number :

Contact :

Date :
02/11/2023


Client: **Craddys**
Contact Name: **Rob Hunt**
Department: **Principal Engineer**
Road: **Suite 8, The Plex, 15 Margaret Street**
Town: **Wakefield**
County: **WF1 2DQ**
Telephone: [REDACTED]
Fax:
Mobile:
E-mail: [REDACTED]

Site: **Aldi March**
Contact Name:
Department:
Road: **Peterborough**
Town: **PE15 0BW**
County:
Telephone:
Fax:
Mobile:
E-mail:


Contractor **Sewer Surveys UK Ltd**
Contact Name: **Andrew Froggatt/Simon Bennett**
Department: **Directors**
Road: **14B Orgreave Close**
Town: **Sheffield**
County: **South Yorkshire, S13 9NP**
Telephone: [REDACTED]
Fax:
Mobile: [REDACTED]
E-mail: [REDACTED]



 WATER FLOW 1

 Tree_Summer

 SOAKAWAY: FOUL WATER

 SURFACE WATER

 PETROL INTERCEPTOR

 RAINWATER PIPE

 RODDING EYE

 SOIL & VENT PIPE

 SOAKAWAY: SURFACE WATER

 W.C.

 FOUL WATER



Tree_Winter



CESS PIT



GNDFLWC



SYPHON INTERCEPTOR



PIPE RUN



ROAD GULLY



SEPTIC TANK



COMBINED



GULLY



PUMP CH



Place :

Fax: [REDACTED]

Inspection report

Date : 02/11/2023	Job number :	Weather : rain	Operator : SB	Section number : 1	PLR SUFFIX: X
Weather rain	Vehicle : YJ65	Camera :	Preset :	Cleaned :	Operator : SB

Place : MARCH, PETERBOROUGH	Location details: Road : HOSTMOOR AVENUE Location Other Pedestrian area Inspection MH1 (D/S) MH2	Catchment: Tape number : Pipe Length 1.60 m	U/S MH : MH1 U/S Depth : D/S MH : MH2 D/S Depth :
Direction Use: Year laid : Purpose : Total length :	Surface water Z Investment planning 30.58 m	Pipe shape : Pipe size : Pipe material : Lining :	Circular 225 mm Vitrified clay
Comment :			

1:252	Position	Code	Observation	Grade	
	0.00	MH	Start node type, manhole, reference number : MH1	0	 <p style="text-align: center;">25.12 m</p>
	0.00	WL	Water level 10 % height/diameter	0	
	4.68	JN	Junction at 09 o'clock dia 150 mm	0	 <p style="text-align: center;">29.2 m</p>
	5.10	JN	Junction at 02 o'clock dia 150 mm	0	
	13.07	JN	Junction at 10 o'clock dia 150 mm	0	
	15.36	JN	Junction at 02 o'clock dia 150 mm	0	
	20.39	JN	Junction at 01 o'clock dia 150 mm	0	
	25.12	RFJ	Fine Roots at joint	2	
	25.12	WL	Water level 20 % height/diameter	0	
	25.30	JN	Junction at 03 o'clock dia 150 mm	0	
	26.66	WL	Water level 30 % height/diameter	0	
	27.46	RFJ	Fine Roots at joint	2	
	29.20	RFJ	Fine Roots at joint	2	

Place :



Sewer Surveys UK Ltd
 14B Orgreave Close
 Street : Sheffield
 Tel: 0114 2313461
 Fax: [REDACTED]
 Email: info@sewersurveys.co.uk

Inspection report

Date : 02/11/2023	Job number :	Weather : rain	Operator : SB	Section number : 2	PLR SUFFIX: X
Weather rain	Vehicle : YJ65	Camera :	Preset :	Cleaned :	Operator : SB

Place : MARCH, PETERBOROUGH	Location details: Catchment: Tape number : Pipe Length 1.60 m	U/S MH : U/S Depth : D/S MH : D/S Depth :	MH3 MH4 MH4
Direction Use: Year laid : Purpose : Total length :	Foul Z Investment planning 6.01 m	Pipe shape : Pipe size : Pipe material : Lining :	Circular 100 mm Vitrified clay

Comment :

1:56	Position	Code	Observation	Grade
		MH	Start node type, manhole, reference number : MH3	0
	0.00	WL	Water level 10 % height/diameter	0
	0.00	DEX	Other settled deposits 10 % cross-sectional area loss	3
	1.00	DEX	Other settled deposits 10 % cross-sectional area loss	3
	2.60	WL	Water level 5 % height/diameter	0
	6.01	MHF	Finish node type, manhole	0

STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	2	2	0.67	4	3

ALDI MARCH

Place :



Sewer Surveys UK Ltd
14B Orgreave Close
Street : Sheffield


Fax:


Inspection report

Date : 02/11/2023	Job number :	Weather : rain	Operator : SB	Section number : 3	PLR SUFFIX: X
Weather rain	Vehicle : YJ65	Camera :	Preset :	Cleaned :	Operator : SB

Place : MARCH, PETERBOROUGH	Location details:	U/S MH : MH4
Road : HOSTMOOR AVENUE	Catchment:	U/S Depth :
Location Difficult access	Tape number :	D/S MH : MH5
Inspection MH4 (D/S) MH5	Pipe Length 1.60 m	D/S Depth :
Direction Use: Foul	Pipe shape : Circular	
Year laid : Z	Pipe size : 100 mm	
Purpose : Investment planning	Pipe material : Vitrified clay	
Total length : 7.66 m	Lining :	

Comment :

1:70	Position	Code	Observation	Grade	
	0.00	MH	Start node type, manhole, reference number : MH4	0	
	0.00	WL	Water level 10 % height/diameter	0	
	0.30	LR	Line of drain/sewer deviates right Remarks: SLIGHT	0	
	1.06	RF	Fine Roots	2	
	1.83	RM	Mass Roots 30 % cross-sectional area loss	5	
	7.66	MHF	Finish node type, manhole	0	



STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	2	10	1.44	11	5

Place :



Sewer Surveys UK Ltd
14B Orgreave Close
Street : Sheffield

Fax:

Inspection report

Date : 02/11/2023	Job number :	Weather : rain	Operator : SB	Section number : 4	PLR SUFFIX: X
Weather rain	Vehicle : YJ65	Camera :	Preset :	Cleaned :	Operator : SB

Place : MARCH, PETERBOROUGH	Location details:	U/S MH : MH5
Road : HOSTMOOR AVENUE	Catchment:	U/S Depth :
Location Difficult access	Tape number :	D/S MH : MAIN
Inspection MH5 (D/S) MAIN	Pipe Length 1.60 m	D/S Depth :
Direction Use: Foul	Pipe shape : Circular	
Year laid : Z	Pipe size : 100 mm	
Purpose : Investment planning	Pipe material : Vitrified clay	
Total length : 7.65 m	Lining :	
Comment :		

1:70	Position	Code	Observation	Grade					
		MH	Start node type, manhole, reference number : MH5	0					
	0.00	WL	Water level 0 % height/diameter	0					
	2.03	DES	Settled deposits fine 10 % cross-sectional area loss	3					
	2.03	CL	Crack Longitudinal at 09 o'clock	2					
	2.03	CL	Crack Longitudinal at 03 o'clock	2					
	3.41	CC	Crack Circumferential from 01 to 05 o'clock	2					
	6.96	LD	Line of drain/sewer deviates down Remarks: SLIGHT	0					
	7.65	OCF	Finish node type, other special chamber	0					
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
3	20	0.04	30	2	1	2	0	2	3

ALDI MARCH

Place :



Sewer Surveys UK Ltd
14B Orgreave Close
Street : Sheffield

Fax:

Inspection report

Date : 02/11/2023	Job number :	Weather : rain	Operator : SB	Section number : 5	PLR SUFFIX: X
Weather rain	Vehicle : YJ65	Camera :	Preset :	Cleaned :	Operator : SB

Place : MARCH, PETERBOROUGH	Location details:	U/S MH : GY1
Road : HOSTMOOR AVENUE	Catchment:	U/S Depth :
Location Road	Tape number :	D/S MH : MAIN
Inspection GY1 (D/S) MAIN	Pipe Length 1.60 m	D/S Depth :
Direction Use: Surface water	Pipe shape : Circular	
Year laid : Z	Pipe size : 150 mm	
Purpose : Investment planning	Pipe material : Vitrified clay	
Total length : 2.16 m	Lining :	

Comment :

1:50	Position	Code	Observation	Grade
	0.00	GY	Start node type, gully, reference number : GY1	0
	0.00	WL	Water level 0 % height/diameter	0
	0.62	LD	Line of drain/sewer deviates down Remarks: CRITICAL	0
	1.62	LD	Line of drain/sewer deviates down Remarks: CRITICAL	0
	1.72	JN	Junction at 09 o'clock dia 150 mm	0
	2.16	OCF	Finish node type, other special chamber	0

1.72 m

STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1

ALDI MARCH

Place :



Sewer Surveys UK Ltd
14B Orgreave Close
Street : Sheffield

Fax:

Inspection report

Date : 02/11/2023	Job number :	Weather : rain	Operator : SB	Section number : 6	PLR SUFFIX: X
Weather rain	Vehicle : YJ65	Camera :	Preset :	Cleaned :	Operator : SB

Place : MARCH, PETERBOROUGH	Location details:	U/S MH : GY2
Road : HOSTMOOR AVENUE	Catchment:	U/S Depth :
Location Road	Tape number :	D/S MH : MAIN
Inspection GY2 (D/S) MAIN	Pipe Length 1.60 m	D/S Depth :
Direction Use: Surface water	Pipe shape : Circular	
Year laid : Z	Pipe size : 150 mm	
Purpose : Investment planning	Pipe material : Vitrified clay	
Total length : 2.82 m	Lining :	

Comment :

1:50	Position	Code	Observation	Grade	
	0.00	OC	Start node type, other special chamber, reference number : GY2		
	0.00	WL	Water level 5 % height/diameter	0	1.72 m
	1.06	WL	Water level 15 % height/diameter	0	
	1.72	DES	Settled deposits fine 20 % cross-sectional area loss	3	
	2.38	LL	Line of drain/sewer deviates left Remarks: MARGINAL	0	
	2.82	DES	Settled deposits fine 70 % cross-sectional area loss	4	
	2.82	SA	Survey abandoned Remarks: DUE TO DES	0	

STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	2	8	3.55	10	4

Place :



Sewer Surveys UK Ltd
14B Orgreave Close
Street : Sheffield

Fax: [REDACTED]

Inspection report

Date : 02/11/2023	Job number :	Weather : rain	Operator : SB	Section number : 7	PLR SUFFIX: X
Weather rain	Vehicle : YJ65	Camera :	Preset :	Cleaned :	Operator : SB

Place : MARCH, PETERBOROUGH	Location details:	U/S MH : GY4
Road : HOSTMOOR AVENUE	Catchment:	U/S Depth :
Location Road	Tape number :	D/S MH : MAIN
Inspection GY4 (D/S) MAIN	Pipe Length 1.60 m	D/S Depth :
Direction Use: Surface water	Pipe shape : Circular	
Year laid : Z	Pipe size : 150 mm	
Purpose : Investment planning	Pipe material : Vitrified clay	
Total length : 3.37 m	Lining :	

Comment :

1:50	Position	Code	Observation	Grade					
		MH	Start node type, manhole, reference number : GY4	0					
		WL	Water level 5 % height/diameter	0					
		LD	Line of drain/sewer deviates down Remarks: SLIGHT	0					
		OCF	Finish node type, other special chamber	0					
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1

ALDI MARCH

Place :



Sewer Surveys UK Ltd
14B Orgreave Close
Street : Sheffield

Fax:

Inspection report

Date : 02/11/2023	Job number :	Weather : rain	Operator : SB	Section number : 8	PLR SUFFIX: X
Weather rain	Vehicle : YJ65	Camera :	Preset :	Cleaned :	Operator : SB

Place : MARCH, PETERBOROUGH	Location details:	U/S MH : GY5
Road : HOSTMOOR AVENUE	Catchment:	U/S Depth :
Location Road	Tape number :	D/S MH : MAIN
Inspection GY5 (D/S) MAIN	Pipe Length 1.60 m	D/S Depth :
Direction Use: Surface water	Pipe shape : Circular	
Year laid : Z	Pipe size : 150 mm	
Purpose : Investment planning	Pipe material : Vitrified clay	
Total length : 2.49 m	Lining :	

Comment :

1:50	Position	Code	Observation	Grade
		OC	Start node type, other special chamber, reference number : GY5	
		WL	Water level 0 % height/diameter	0
		OCF	Finish node type, other special chamber	0

STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1

ALDI MARCH

Place :



Sewer Surveys UK Ltd
14B Orgreave Close
Street : Sheffield

Fax:

Inspection report

Date : 02/11/2023	Job number :	Weather : rain	Operator : SB	Section number : 9	PLR SUFFIX: X
Weather rain	Vehicle : YJ65	Camera :	Preset :	Cleaned :	Operator : SB

Place : MARCH, PETERBOROUGH	Location details:	U/S MH : GY6
Road : HOSTMOOR AVENUE	Catchment:	U/S Depth :
Location Road	Tape number :	D/S MH : MAIN
Inspection GY6 (D/S) MAIN	Pipe Length 1.60 m	D/S Depth :
Direction Use: Surface water	Pipe shape : Circular	
Year laid : Z	Pipe size : 150 mm	
Purpose : Investment planning	Pipe material : Vitrified clay	
Total length : 2.60 m	Lining :	

Comment :

1:50	Position	Code	Observation	Grade					
		OC	Start node type, other special chamber, reference number : GY6						
		WL	Water level 0 % height/diameter	0					
		OCF	Finish node type, other special chamber	0					
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1

ALDI MARCH

Place :



Sewer Surveys UK Ltd
14B Orgreave Close
Street : Sheffield

Fax:

Inspection report

Date : 02/11/2023	Job number :	Weather : rain	Operator : SB	Section number : 10	PLR SUFFIX: X
Weather rain	Vehicle : YJ65	Camera :	Preset :	Cleaned :	Operator : SB

Place : MARCH, PETERBOROUGH	Location details:	U/S MH : GY7
Road : HOSTMOOR AVENUE	Catchment:	U/S Depth :
Location Road	Tape number :	D/S MH : MAIN
Inspection GY7 (D/S) MAIN	Pipe Length 1.60 m	D/S Depth :
Direction Use: Surface water	Pipe shape : Circular	
Year laid : Z	Pipe size : 150 mm	
Purpose : Investment planning	Pipe material : Vitrified clay	
Total length : 6.67 m	Lining :	

Comment :

1:56	Position	Code	Observation	Grade
		OC	Start node type, other special chamber, reference number : GY7	
	0.00	WL	Water level 5 % height/diameter	0
	6.01	LD	Line of drain/sewer deviates down Remarks: MARGINAL	
	6.67	OCF	Finish node type, other special chamber	0

STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1

ALDI MARCH




Place :

Fax: [REDACTED]

Inspection report

Date : 02/11/2023	Job number :	Weather : rain	Operator : SB	Section number : 11	PLR SUFFIX: X
Weather rain	Vehicle : YJ65	Camera :	Preset :	Cleaned :	Operator : SB

Place : MARCH, PETERBOROUGH	Location details: Road : HOSTMOOR AVENUE	Catchment: Tape number :	U/S MH : MH7/1051
Location Road	Inspection MH6/1052 (U/S) MH7/1051	Pipe Length 1.60 m	D/S MH : MH6/1052
Direction Use: Surface water	Year laid : Z	Pipe shape : Circular	D/S Depth :
Purpose : Investment planning	Total length : 58.15 m	Pipe size : 225 mm	Pipe material : Concrete
Lining :		Comment :	

1:432	Position	Code	Observation	Grade	
	0.00	MH	Start node type, manhole, reference number : MH6/10520		
	0.00	WL	Water level 10 % height/diameter	0	0.4 m
	0.40	CM	Multiple Cracks from 07 to 05 o'clock	3	
	1.00	B	Broken pipe from 03 to 05 o'clock	4	
	1.60	CN	Connection at 02 o'clock, dia 150 mm	0	
	2.15	CN	Connection at 10 o'clock, dia 150 mm	0	1 m
	12.82	CN	Connection at 10 o'clock, dia 150 mm	0	
	14.53	CN	Connection at 02 o'clock, dia 150 mm	0	
	15.01	DES	Settled deposits fine 10 % cross-sectional area loss	3	
	15.88	DEX	Other settled deposits 20 % cross-sectional area loss	4	15.88 m
	47.46	CN	Connection at 10 o'clock, dia 150 mm	0	
	48.72	CN	Connection at 02 o'clock, dia 150 mm	0	
	49.08	DES	Settled deposits fine 10 % cross-sectional area loss	2	
	52.36	DES	Settled deposits fine 10 % cross-sectional area loss	3	

Place :



Sewer Surveys UK Ltd
14B Orgreave Close
Street : Sheffield

Fax:

Inspection report

Date : 02/11/2023	Job number :	Weather : rain	Operator : SB	Section number : 12	PLR SUFFIX: X
Weather rain	Vehicle : YJ65	Camera :	Preset :	Cleaned :	Operator : SB

Place : MARCH, PETERBOROUGH	Location details:	U/S MH : 1053
Road : HOSTMOOR AVENUE	Catchment:	U/S Depth :
Location Road	Tape number :	D/S MH : 1052
Inspection 1052 (U/S) 1053	Pipe Length 1.60 m	D/S Depth :
Direction Use: Surface water	Pipe shape : Circular	
Year laid : Z	Pipe size : 300 mm	
Purpose : Investment planning	Pipe material : Concrete	
Total length : 31.67 m	Lining :	

Comment :

1:266	Position	Code	Observation	Grade					
		MH	Start node type, manhole, reference number : 1052	0					
	0.00	WL	Water level 5 % height/diameter	0					
	31.67	MHF	Finish node type, manhole	0					
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	0	0	0	0	1

ALDI MARCH






Place :

Fax: [REDACTED]

Inspection report

Date : 02/11/2023	Job number :	Weather : rain	Operator : SB	Section number : 13	PLR SUFFIX: X
Weather rain	Vehicle : YJ65	Camera :	Preset :	Cleaned :	Operator : SB

Place : MARCH, PETERBOROUGH	Location details:	U/S MH : MH2
Road : HOSTMOOR AVENUE	Catchment:	U/S Depth :
Location Road	Tape number :	D/S MH : 1052
Inspection 1052 (U/S) MH2	Pipe Length 1.60 m	D/S Depth :
Direction Use: Surface water	Pipe shape : Circular	
Year laid : Z	Pipe size : 225 mm	
Purpose : Investment planning	Pipe material : Vitrified clay	
Total length : 6.86 m	Lining :	
Comment :		

1:70	Position	Code	Observation	Grade					
									
	0.00	MH	Start node type, manhole, reference number : 1052	0					
	0.00	WL	Water level 10 % height/diameter	0	1 m				
	1.00	HJ	Hole in sewer at joint from 04 to 08 o'clock	5					
	1.20	WL	Water level 20 % height/diameter	0					
	2.65	S1 RM	Mass Roots 10 % cross-sectional area loss, Start	5	2.65 m				
	4.97	C1 RM	Mass Roots 20 % cross-sectional area loss, Changed	5	4.97 m				
	6.40	F1 RM	Mass Roots 20 % cross-sectional area loss, Finish	5					
	6.86	MHF	Finish node type, manhole	0					
									
STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
1	103.12	15.03	103.12	4	2	10	5.54	38	5

ALDI MARCH

Place :


Fax:


Inspection report

Date : 02/11/2023	Job number :	Weather : rain	Operator : SB	Section number : 14	PLR SUFFIX: X
Weather rain	Vehicle : YJ65	Camera :	Preset :	Cleaned :	Operator : SB

Place : MARCH, PETERBOROUGH	Location details:	U/S MH : 2051
Road : HOSTMOOR AVENUE	Catchment:	U/S Depth :
Location Road	Tape number :	D/S MH : 1052
Inspection 1052 (U/S) 2051	Pipe Length 2.50 m	D/S Depth :
Direction Use: Surface water	Pipe shape : Circular	
Year laid : Z	Pipe size : 900 mm	
Purpose : Investment planning	Pipe material : Concrete	
Total length : 77.48 m	Lining :	
Comment :		

1:644	Position	Code	Observation	Grade
	1052			
	0.00	MH	Start node type, manhole, reference number : 1052	0
	0.00	WL	Water level 10 % height/diameter	0
	9.82	CN	Connection at 02 o'clock, dia 150 mm	0
	11.08	CN	Connection at 10 o'clock, dia 150 mm	0
	43.59	CN	Connection at 02 o'clock, dia 150 mm	0
	44.35	CN	Connection at 10 o'clock, dia 150 mm	0
	44.35	DER	Settled deposits coarse 10 % cross-sectional area loss	3
	57.22	CN	Connection at 12 o'clock, dia 150 mm	0
	61.07	CN	Connection at 02 o'clock, dia 150 mm	0
	62.52	CN	Connection at 10 o'clock, dia 150 mm	0
	62.52	DEC	Settled deposits hard or compacted 10 % cross-sectional area loss	3
	77.48	MHF	Finish node type, manhole	0
	2051			





STR no def	STR peak	STR mean	STR total	STR grade	SER no def	SER peak	SER mean	SER total	SER grade
0	0	0	0	1	2	2	0.05	4	3

Place :



Sewer Surveys UK Ltd
14B Orgreave Close
Sheffield

Fax:

ΣØ / Main sections

Project name :
ALDI MARCH

Project number :

Contact :

Date :
02/11/2023

Nr.	US MH	DS MH	Date	Road	Tape No.	Material	m	(m)
2	MH3	MH4	02/11/2023	HOSTMOOR AVENUE		Vitrified clay	6.01	6.01
3	MH4	MH5	02/11/2023	HOSTMOOR AVENUE		Vitrified clay	7.66	7.66
4	MH5	MAIN	02/11/2023	HOSTMOOR AVENUE		Vitrified clay	7.65	7.65

Pipe size: CIRCULAR 100 = 21.32 m (21.32 m)

Nr.	US MH	DS MH	Date	Road	Tape No.	Material	m	(m)
5	GY1	MAIN	02/11/2023	HOSTMOOR AVENUE		Vitrified clay	2.16	2.16
6	GY2	MAIN	02/11/2023	HOSTMOOR AVENUE		Vitrified clay	2.82	2.82
7	GY4	MAIN	02/11/2023	HOSTMOOR AVENUE		Vitrified clay	3.37	3.37
8	GY5	MAIN	02/11/2023	HOSTMOOR AVENUE		Vitrified clay	2.49	2.49
9	GY6	MAIN	02/11/2023	HOSTMOOR AVENUE		Vitrified clay	2.60	2.60
10	GY7	MAIN	02/11/2023	HOSTMOOR AVENUE		Vitrified clay	6.67	6.67

Pipe size: CIRCULAR 150 = 20.11 m (20.11 m)

Nr.	US MH	DS MH	Date	Road	Tape No.	Material	m	(m)
1	MH1	MH2	02/11/2023	HOSTMOOR AVENUE		Vitrified clay	30.58	30.58
11	MH7/1051	MH6/1052	02/11/2023	HOSTMOOR AVENUE		Concrete	58.15	58.15
13	MH2	1052	02/11/2023	HOSTMOOR AVENUE		Vitrified clay	6.86	6.86

Pipe size: CIRCULAR 225 = 95.59 m (95.59 m)

Nr.	US MH	DS MH	Date	Road	Tape No.	Material	m	(m)
12	1053	1052	02/11/2023	HOSTMOOR AVENUE		Concrete	31.67	31.67

Pipe size: CIRCULAR 300 = 31.67 m (31.67 m)

Nr.	US MH	DS MH	Date	Road	Tape No.	Material	m	(m)
14	2051	1052	02/11/2023	HOSTMOOR AVENUE		Concrete	77.48	77.48

Pipe size: CIRCULAR 900 = 77.48 m (77.48 m)

All sections = 246.17 m (246.17 m)

Place :



Sewer Surveys UK Ltd
14B Orgreave Close
Sheffield

Fax: [REDACTED]

Service / Operational Defects (SRM 4)

Project name :
ALDI MARCH

Project Number :

Contact :

Date :
02/11/2023

No.	PLR	Dir.	Use	Shape / Size	Date	Mat.	Total Length	Insp. Length	Peak HWG	Peak Score	Grade	Mean Score	Total Score
1	MH1X	D	S	C 225	02/11/2023	VC	30.58	30.58	5	4	3	0.19	5.88
2	MH3X	D	F	C 100	02/11/2023	VC	6.01	6.01	-	2	3	0.67	4
3	MH4X	D	F	C 100	02/11/2023	VC	7.66	7.66	5	10	5	1.44	11
4	MH5X	D	F	C 100	02/11/2023	VC	7.65	7.65	3	2	3	0	2
5	GY1X	D	S	C 150	02/11/2023	VC	2.16	2.16	-	0	1	0	0
6	GY2X	D	S	C 150	02/11/2023	VC	2.82	2.82	3	8	4	3.55	10
7	GY4X	D	S	C 150	02/11/2023	VC	3.37	3.37	-	0	1	0	0
8	GY5X	D	S	C 150	02/11/2023	VC	2.49	2.49	-	0	1	0	0
9	GY6X	D	S	C 150	02/11/2023	VC	2.60	2.60	-	0	1	0	0
10	GY7X	D	S	C 150	02/11/2023	VC	6.67	6.67	-	0	1	0	0
11	MH7/1051X	U	S	C 225	02/11/2023	CO	58.15	58.15	3	5	4	0.21	12
12	1053X	U	S	C 300	02/11/2023	CO	31.67	31.67	-	0	1	0	0
13	MH2X	U	S	C 225	02/11/2023	VC	6.86	6.86	5	10	5	5.54	38
14	2051X	U	S	C 900	02/11/2023	CO	77.48	77.48	3	2	3	0.05	4

ALDI MARCH

Place :



Sewer Surveys UK Ltd
14B Orgreave Close
Sheffield

Fax:

Structural Defects (SRM 4)

Project name :
ALDI MARCH

Project Number :

Contact :

Date :
02/11/2023

No.	PLR	Dir.	Use	Shape / Size	Date	Mat.	Total Length	Insp. Length	Peak HWG	Peak Score	Grade	Mean Score	Total Score
1	MH1X	D	S	C 225	02/11/2023	VC	30.58	30.58	-	0	1	0	0
2	MH3X	D	F	C 100	02/11/2023	VC	6.01	6.01	-	0	1	0	0
3	MH4X	D	F	C 100	02/11/2023	VC	7.66	7.66	-	0	1	0	0
4	MH5X	D	F	C 100	02/11/2023	VC	7.65	7.65	2	20	2	0.04	30
5	GY1X	D	S	C 150	02/11/2023	VC	2.16	2.16	-	0	1	0	0
6	GY2X	D	S	C 150	02/11/2023	VC	2.82	2.82	-	0	1	0	0
7	GY4X	D	S	C 150	02/11/2023	VC	3.37	3.37	-	0	1	0	0
8	GY5X	D	S	C 150	02/11/2023	VC	2.49	2.49	-	0	1	0	0
9	GY6X	D	S	C 150	02/11/2023	VC	2.60	2.60	-	0	1	0	0
10	GY7X	D	S	C 150	02/11/2023	VC	6.67	6.67	-	0	1	0	0
11	MH7/1051X	U	S	C 225	02/11/2023	CO	58.15	58.15	4	80	4	2.06	120
12	1053X	U	S	C 300	02/11/2023	CO	31.67	31.67	-	0	1	0	0
13	MH2X	U	S	C 225	02/11/2023	VC	6.86	6.86	4	103.12	4	15.03	103.12
14	2051X	U	S	C 900	02/11/2023	CO	77.48	77.48	-	0	1	0	0

ALDI MARCH

Job Number:	Survey By: SB
-------------	---------------

Grid Ref:	Node Number: 1051	Cover Level:
-----------	-------------------	--------------

Location: HOSTMOOR AVENUE

Year Laid: Z	Status: PU	Function: SW	Node Type: MH	Survey Date:
--------------	------------	--------------	---------------	--------------

Manufacturer:	Grating:
---------------	----------

COVER	Shape: DT	Hinged:	Lockable:	Duty: H	Size:660/660	Toxic atmos:
-------	-----------	---------	-----------	---------	--------------	--------------

SHAFT	Side Entry:	Regulating Courses:3	Depth:600	Size:600/600	Vermin:
-------	-------------	----------------------	-----------	--------------	---------

CHAMBER	Soffit Type:S	No. of Step Irons: 2	No. of Ladders:	No. of Landings:
---------	---------------	----------------------	-----------------	------------------


Size:1050/1050	Const'n Code: PC	Depth of Flow:	Depth of Silt:	H of S:
----------------	------------------	----------------	----------------	---------

	Pipe	U/S D/S node Reference	Shape	Pipe Size		Backdrop Diameter	Pipe Material	Lining Material	Depth from Cover (M)	Invert Level (M)
INCOMING PIPES	A	GY	C	150	150		VC		1.62	
	B	GY	C	150	150		VC		1.53	
	C									
	D									
	E									
	F									
OUTGOING PIPES	X	1052	C	225	225		VC		1.64	
	Y									

CONDITION INFORMATION Enter Y if attention required. Use Remarks to clarify

Cover	Irons/Ladders	Shaft	Chamber	Benching	Other
-------	---------------	-------	---------	----------	-------

Remarks:



Job Number:	Survey By: SB
-------------	---------------

Grid Ref:	Node Number: 1052	Cover Level:
-----------	-------------------	--------------

Location: HOSTMOOR AVENUE

Year Laid: Z	Status: PU	Function: SW	Node Type: MH	Survey Date:
--------------	------------	--------------	---------------	--------------

Manufacturer:	Grating:
---------------	----------

COVER	Shape: DT	Hinged:	Lockable:	Duty: H	Size:660/660	Toxic atmos:
-------	-----------	---------	-----------	---------	--------------	--------------

SHAFT	Side Entry:	Regulating Courses:2	Depth:450	Size:620/620	Vermin:
-------	-------------	----------------------	-----------	--------------	---------

CHAMBER	Soffit Type:S	No. of Step Irons: 5	No. of Ladders:	No. of Landings:
---------	---------------	----------------------	-----------------	------------------


Size:1500/1500	Const'n Code: PC	Depth of Flow: 20MM	Depth of Silt:	H of S:
----------------	------------------	---------------------	----------------	---------

	Pipe	U/S D/S node Reference	Shape	Pipe Size		Backdrop Diameter	Pipe Material	Lining Material	Depth from Cover (M)	Invert Level (M)
INCOMING PIPES	A	1051	C	225	225		CO		1.83	
	B	1053	C	300	300		CO		2.00	
	C	MH2	C	225	225		VC		1.85	
	D	2051	C	900	900		CO		2.38	
	E									
	F									
OUTGOING PIPES	X	OUTLET	C	900	900		CO		2.41	
	Y									

CONDITION INFORMATION Enter Y if attention required. Use Remarks to clarify

Cover	Irons/Ladders	Shaft	Chamber	Benching	Other
-------	---------------	-------	---------	----------	-------

Remarks:



Job Number:	Survey By: SB
-------------	---------------

Grid Ref:	Node Number: 2051	Cover Level:
-----------	-------------------	--------------

Location: HOSTMOOR AVENUE

Year Laid: Z	Status: PU	Function: SW	Node Type: MH	Survey Date:
--------------	------------	--------------	---------------	--------------

Manufacturer:	Grating:
---------------	----------

COVER	Shape: DT	Hinged:	Lockable:	Duty: H	Size:600/600	Toxic atmos:
-------	-----------	---------	-----------	---------	--------------	--------------

SHAFT	Side Entry:	Regulating Courses:4	Depth:680	Size:600/600	Vermin:
-------	-------------	----------------------	-----------	--------------	---------

CHAMBER	Soffit Type:S	No. of Step Irons: 5	No. of Ladders:	No. of Landings:
---------	---------------	----------------------	-----------------	------------------


Size:1500/1500	Const'n Code: PC	Depth of Flow: 10MM	Depth of Silt:	H of S:
----------------	------------------	---------------------	----------------	---------

	Pipe	U/S D/S node Reference	Shape	Pipe Size		Backdrop Diameter	Pipe Material	Lining Material	Depth from Cover (M)	Invert Level (M)
INCOMING PIPES	A		C	900	900		CO		2.54	
	B		C	225	225		VC		1.98	
	C		C	300	300		CO		2.05	
	D									
	E									
	F									
OUTGOING PIPES	X	1052	C	900	900		CO		2.57	
	Y									

CONDITION INFORMATION Enter Y if attention required. Use Remarks to clarify

Cover	Irons/Ladders	Shaft	Chamber	Benching	Other
-------	---------------	-------	---------	----------	-------

Remarks:



Job Number:	Survey By: SB
-------------	---------------

Grid Ref:	Node Number: MH1	Cover Level:
-----------	------------------	--------------

Location: HOSTMOOR AVENUE

Year Laid: Z	Status: PU	Function: SW	Node Type: MH	Survey Date:
--------------	------------	--------------	---------------	--------------

Manufacturer:	Grating:
---------------	----------

COVER	Shape: DT	Hinged:	Lockable:	Duty: H	Size:600/600	Toxic atmos:
-------	-----------	---------	-----------	---------	--------------	--------------

SHAFT	Side Entry:	Regulating Courses:	Depth: 320	Size:600/450	Vermin:
-------	-------------	---------------------	------------	--------------	---------

CHAMBER	Soffit Type:S	No. of Step Irons:	No. of Ladders:	No. of Landings:
---------	---------------	--------------------	-----------------	------------------


Size:920/600	Const'n Code: BR	Depth of Flow: 10MM	Depth of Silt:	H of S:
--------------	------------------	---------------------	----------------	---------

	Pipe	U/S D/S node Reference	Shape	Pipe Size		Backdrop Diameter	Pipe Material	Lining Material	Depth from Cover (M)	Invert Level (M)
INCOMING PIPES	A	?	C	150	150		VC		0.67	
	B	?	C	150	150		VC		0.84	
	C									
	D									
	E									
	F									
OUTGOING PIPES	X	MH2	C	225	225		VC		0.86	
	Y									

CONDITION INFORMATION Enter Y if attention required. Use Remarks to clarify

Cover	Irons/Ladders	Shaft	Chamber	Benching	Other
-------	---------------	-------	---------	----------	-------

Remarks:



Job Number:	Survey By: SB
-------------	---------------

Grid Ref:	Node Number: MH2	Cover Level:
-----------	------------------	--------------

Location: HOSTMOOR AVENUE

Year Laid: Z	Status: PU	Function: SW	Node Type: MH	Survey Date:
--------------	------------	--------------	---------------	--------------

Manufacturer:	Grating:
---------------	----------

COVER	Shape:	Hinged:	Lockable:	Duty:	Size:	Toxic atmos:
-------	--------	---------	-----------	-------	-------	--------------

SHAFT	Side Entry:	Regulating Courses:	Depth:	Size:	Vermin:
-------	-------------	---------------------	--------	-------	---------

CHAMBER	Soffit Type:	No. of Step Irons:	No. of Ladders:	No. of Landings:
---------	--------------	--------------------	-----------------	------------------

Size:	Const'n Code: PC	Depth of Flow:	Depth of Silt:	H of S:
-------	------------------	----------------	----------------	---------

	Pipe	U/S D/S node Reference	Shape	Pipe Size	Backdrop Diameter	Pipe Material	Lining Material	Depth from Cover (M)	Invert Level (M)
INCOMING PIPES	A								
	B								
	C								
	D								
	E								
	F								
OUTGOING PIPES	X								
	Y								

CONDITION INFORMATION Enter Y if attention required. Use Remarks to clarify

Cover	Irons/Ladders	Shaft	Chamber	Benching	Other
-------	---------------	-------	---------	----------	-------

Remarks: U.T.R REQUIRES DIGGING UP (TREE ROUTES)



Job Number:	Survey By: SB
-------------	---------------

Grid Ref:	Node Number: MH3	Cover Level:
-----------	------------------	--------------

Location: HOSTMOOR AVENUE

Year Laid: Z	Status: PU	Function: FW	Node Type: MH	Survey Date:
--------------	------------	--------------	---------------	--------------

Manufacturer:	Grating:
---------------	----------

COVER	Shape: C	Hinged:	Lockable:	Duty: H	Size:660/660	Toxic atmos:
-------	----------	---------	-----------	---------	--------------	--------------

SHAFT	Side Entry:	Regulating Courses: 1	Depth: 360	Size:600/600	Vermin:
-------	-------------	-----------------------	------------	--------------	---------

CHAMBER	Soffit Type:S	No. of Step Irons: 5	No. of Ladders:	No. of Landings:
---------	---------------	----------------------	-----------------	------------------

Size:1200/1200	Const'n Code: PC	Depth of Flow:	Depth of Silt:	H of S:
----------------	------------------	----------------	----------------	---------

	Pipe	U/S D/S node Reference	Shape	Pipe Size		Backdrop Diameter	Pipe Material	Lining Material	Depth from Cover (M)	Invert Level (M)
INCOMING PIPES	A	?	C	100	100		VC		1.78	
	B	?	C	100	100		VC		1.72	
	C	?	C	100	100		VC		1.73	
	D	?	C	100	100		VC		1.73	
	E									
	F									
OUTGOING PIPES	X	MH4	C	100	100		VC		1.82	
	Y									

CONDITION INFORMATION Enter Y if attention required. Use Remarks to clarify

Cover	Irons/Ladders	Shaft	Chamber	Benching	Other
-------	---------------	-------	---------	----------	-------

Remarks:



Job Number:	Survey By: SB
-------------	---------------

Grid Ref:	Node Number: MH4	Cover Level:
-----------	------------------	--------------

Location: HOSTMOOR AVENUE

Year Laid: Z	Status: PU	Function: FW	Node Type: MH	Survey Date:
--------------	------------	--------------	---------------	--------------

Manufacturer:	Grating:
---------------	----------

COVER	Shape: C	Hinged:	Lockable:	Duty: H	Size:660/660	Toxic atmos:
-------	----------	---------	-----------	---------	--------------	--------------

SHAFT	Side Entry:	Regulating Courses:2	Depth:440	Size:600/600	Vermin:
-------	-------------	----------------------	-----------	--------------	---------

CHAMBER	Soffit Type:S	No. of Step Irons: 5	No. of Ladders:	No. of Landings:
---------	---------------	----------------------	-----------------	------------------


Size:1200/1200	Const'n Code: PC	Depth of Flow:	Depth of Silt:	H of S:
----------------	------------------	----------------	----------------	---------

	Pipe	U/S D/S node Reference	Shape	Pipe Size		Backdrop Diameter	Pipe Material	Lining Material	Depth from Cover (M)	Invert Level (M)
INCOMING PIPES	A	MH3	C	100	100		VC		1.83	
	B									
	C									
	D									
	E									
	F									
OUTGOING PIPES	X	MH5	C	100	100		VC		1.85	
	Y									

CONDITION INFORMATION Enter Y if attention required. Use Remarks to clarify

Cover	Irons/Ladders	Shaft	Chamber	Benching	Other
-------	---------------	-------	---------	----------	-------

Remarks:



Job Number:	Survey By: SB
-------------	---------------

Grid Ref:	Node Number: MH5	Cover Level:
-----------	------------------	--------------

Location: HOSTMOOR AVENUE

Year Laid: Z	Status: PU	Function: FW	Node Type: MH	Survey Date:
--------------	------------	--------------	---------------	--------------

Manufacturer:	Grating:
---------------	----------

COVER	Shape: C	Hinged:	Lockable:	Duty: H	Size:660/660	Toxic atmos:
-------	----------	---------	-----------	---------	--------------	--------------

SHAFT	Side Entry:	Regulating Courses:3	Depth:510	Size:600/600	Vermin:
-------	-------------	----------------------	-----------	--------------	---------

CHAMBER	Soffit Type:S	No. of Step Irons: 5	No. of Ladders:	No. of Landings:
---------	---------------	----------------------	-----------------	------------------

Size:1200/1200	Const'n Code: PC	Depth of Flow:	Depth of Silt:	H of S:
----------------	------------------	----------------	----------------	---------

	Pipe	U/S D/S node Reference	Shape	Pipe Size		Backdrop Diameter	Pipe Material	Lining Material	Depth from Cover (M)	Invert Level (M)
INCOMING PIPES	A	MH4	C	100	100		VC		1.87	
	B									
	C									
	D									
	E									
	F									
OUTGOING PIPES	X	MAIN	C	100	100		VC		1.90	
	Y									

CONDITION INFORMATION Enter Y if attention required. Use Remarks to clarify

Cover	Irons/Ladders	Shaft	Chamber	Benching	Other
-------	---------------	-------	---------	----------	-------

Remarks:



Sewer Surveys UK LTD



CONTRACTORS HEALTH & SAFETY ASSESSMENT SCHEME
Accredited Contractor
www.chas.co.uk












Constructionline
A UK GOVERNMENT CERTIFICATION SERVICE





Unit 14b, Orgreave Close, Sheffield, S13 9NP.


Appendix B – Proposed Drainage Design



GENERAL NOTES
 CONSULT AND OBSERVATIONS: This drawing is to be used in conjunction with all relevant Accidents, Engineers and Specialist drawings together with the specification.
 BUILDING REGULATIONS AND SAFETY: PROVISION APPROVALS: Please note that it is the responsibility of the Client/Contractor to ensure the Building Regulations and safety provisions (e.g. MIBOC approval of all design and construction details) is achieved prior to construction of this.
DRAINAGE NOTES
 Refer to general arrangement drawings for drainage notes.
CD - SPECIFIC NOTES
 THE FOLLOWING NOTES ARE TO BE OBSERVED BY THE CONTRACTOR IN CONNECTION WITH THE WORKS:
 REFER TO GENERAL ARRANGEMENT DRAWINGS
OPERATIONAL APPROVED: NONE
 • None general arrangement drawings
NOT TO SCALE: DIMENSIONS/COORDINATES/VERTICAL/TERRAIN
 • None in general arrangement drawings
 IF IT IS ASSUMED THAT ALL WORK WILL BE COMPLETED BY CONTRACTOR & CONTRACTOR'S SUBCONTRACTORS TO THE FULL AND COMPLETE SATISFACTION OF THE CLIENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY APPROVALS AND PERMITS PRIOR TO COMMENCEMENT OF WORK.
ALDI - A&S Shows Ltd.
ALDI STORE
 102/104 AVENUE
 MARCH
PROPOSED DRAINAGE DETAILS SHEET 1
 Issue Description: CDY XX XX DR C
 Issue No: Ss_50_35_00_0040 A4 C02
 Issue Date: 18.12.23
 Issue By: AS SHOWN
CRADDYS
 Consulting Civil and Structural Engineers
 www.craddys.co.uk



- Notes for class 2:**
1. Bedding beneath and at sides of pipe to be well compacted.
 2. Concrete may be cast where directed or approved by the engineer to contain bedding material in certain conditions.
 3. In very wet conditions, where directed or approved by the engineer a temporary bed may be laid under the granular bed.
 4. Where joint pipes with flexible joints are used, the concrete protection to be interrupted over the full cross section, extended not exceeding 50mm or as indicated by the engineer by a shaped former of bitumen impregnated compressible block. These interruptions shall coincide with pipe joints.
 5. Concrete to be G60 concrete.
 6. Where flexible pipes are used care must be taken to prevent the pipes from floating.




- Notes for class 3:**
1. Bedding beneath and at sides of pipe to be well compacted.
 2. The first 50mm of the cover of the pipe is to be kept temporary level. Mechanical compaction may be used only above this bed.
 3. Concrete may be cast where directed or approved by the engineer to contain bedding material in certain conditions.
 4. In very wet conditions, where directed or approved by the engineer a temporary bed may be laid under the granular bed.
 5. + 150mm for 150mm diameter pipes or less.
 6. + 100mm for pipe diameters over 150mm.
 7. + 150mm for 150mm diameter pipes or less.
 8. + 100mm for pipe diameters over 150mm.
 9. + 100mm for pipe diameters or less.

CLASS 2 BEDDING WHERE COVER TO SOFFIT IS LESS THAN 600mm (1200mm IN TRAFFICKED AREAS) OR WHERE PIPE CLEARANCE BETWEEN PIPES IS LESS THAN 300mm

Not to scale.


CLASS 3 BEDDING FOR DRAINS (WHERE COVER TO SOFFIT IS MORE THAN 1200mm IN TRAFFICKED AREAS OR 600mm ELSEWHERE)

Scale: 1:20




TANKED (NO INFILTRATION) PERMEABLE PAVEMENT (BLOCK PAVING)

Scale: 1:20




TYPICAL RODDING EYE DETAIL




CAR PARK DRAINAGE CHANNEL

Scale: 1:10



HAIRATON 'TRASH BOX' OUTFALL DETAIL

Scale: 1:10



LOADING BAY RAMP DRAINAGE CHANNEL

Scale: 1:10

GENERAL NOTES

Consulting and Specifications: The drawings to be used in conjunction with all relevant contracts, Engineers and Specialist drawings together with the specifications.

BUILDING REGULATIONS AND SAFETY PREVENTION APPROVALS: Please note that it is the responsibility of the Client/Contractor to ensure that Building Regulations and safety provisions (as applicable) are approved by the relevant authorities in advance prior to construction or installation.

DRAINAGE NOTES

Refer to general arrangement drawings for drainage notes.

CDM (CONSTRUCTION DESIGN AND MANAGEMENT) REGULATIONS

THE FOLLOWING INFORMATION IS PROVIDED FOR THE DESIGNER'S INFORMATION AND MANAGEMENT REGULATIONS:

- 1. Name of project/contract
- 2. Name of project/contract

OPERATIONAL APPROVALS/REVISE

- 1. Refer to general arrangement drawings

IF IT IS ASSUMED THAT ALL WORK WILL BE COMPLETED BY CONTRACTOR'S SUBCONTRACTORS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN OF ANY SUBCONTRACTORS' WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN OF ANY SUBCONTRACTORS' WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN OF ANY SUBCONTRACTORS' WORK.

ALDI - ASD Stores Ltd.

ALDI STORE

ROSEMOOR AVENUE

MARSH

PROPOSED DRAINAGE DETAILS SHEET 2

13173 CDY XX XX DR C

Scale: 1:10

Sheet No: S5_50_35_00 0061 A4 C01

Rev: 1

18.12.23 AS SHOWN A1

CRADDYS

Consulting Civil and Structural Engineers

www.craddys.co.uk

Appendix C – Microdrainage Calculations

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Sw

Pipe Sizes STANDARD Manhole Sizes STANDARD

Return Period (years)	100	Maximum Rainfall (mm/hr)	50	FSR Rainfall Model - England and Wales		Minimum Backdrop Height (m)	0.200	Min Vel for Auto Design only (m/s)	1.00
MS-60 (mm)	19,000	Maximum Time of Concentration (mins)	30	Volumetric Runoff Coeff.	0.750	Maximum Backdrop Height (m)	1.500	Min Slope for Optimisation (1:X)	500
Ratio R	0.436	Foul Sewage (l/s/ha)	0.000	Add Flow / Climate Change (%)	0	Min Design Depth for Optimisation (m)	1.200		

Designed with Level Soffits

Time Area Diagram for Sw

Time (mins)	Area (ha)	Time (mins)	Area (ha)	Time (mins)	Area (ha)
0-4	0.001	4-8	0.394	8-12	0.196

Total Area Contributing (ha) = 0.592

Total Pipe Volume (m³) = 15.677

Network Design Table for Sw

- Indicates pipe length does not match coordinates
« - Indicates pipe capacity < flow

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.000	24.851	0.249	99.8	0.019	5.00	0.0	0.600	o	150	Pipe/Conduit	●
1.001	11.006	0.055	200.1	0.026	0.00	0.0	0.600	o	225	Pipe/Conduit	●
2.000	25.698	1.400	18.4	0.015	5.00	0.0	0.600	o	150	Pipe/Conduit	●
1.002	47.611	0.159	299.4	0.057	0.00	0.0	0.600	o	300	Pipe/Conduit	●
3.000	15.492	1.000	15.5	0.028	5.00	0.0	0.600	o	225	Pipe/Conduit	●
4.000	5.700	0.057	100.0	0.050	5.00	0.0	0.600	o	150	Pipe/Conduit	●
4.001	5.700	0.200	28.5	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	●

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	I.Area (ha)	E Base Flow (l/s)	Foul Flow (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	50.00	5.41	1.600	0.019	0.0	0.0	0.0	1.01	17.8	2.6
1.001	50.00	5.61	1.276	0.045	0.0	0.0	0.0	0.92	36.6	6.1
2.000	50.00	5.18	2.700	0.015	0.0	0.0	0.0	2.36	41.7	2.0
1.002	50.00	6.49	1.146	0.117	0.0	0.0	0.0	0.90	63.9	15.8
3.000	50.00	5.08	2.064	0.028	0.0	0.0	0.0	3.34	132.9	3.8
4.000	50.00	5.09	2.257	0.050	0.0	0.0	0.0	1.00	17.8	6.8
4.001	50.00	5.14	2.200	0.050	0.0	0.0	0.0	1.89	33.5	6.8



Craddys
 Eden Office Park
 Ham Green
 Bristol BS20 0DD
 Date 19/12/2023 15:35
 File 13173 Civils 3D Drainage - Copy2.mdx
 XP Solutions

Designed by purcella
 Checked by
 Network 2020.1.3

Network Design Table for Sw












PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT (mm)	DIA (mm)	Section Type	Auto Design
1.003	5.000	0.037	135.1	0.050	0.00	0.0	0.600	o	300	Pipe/Conduit	●
1.004	2.643	0.010	264.3	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	●
5.000	69.798	0.345	202.3	0.200	5.00	0.0	0.600	o	300	Pipe/Conduit	●
5.001	8.200#	0.045	182.2	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	●
5.002	21.000#	0.021	1000.0	0.012	0.00	0.0	0.600	o	300	Pipe/Conduit	●
5.003	12.830	0.490	26.2	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	●
5.004	12.137	0.460	26.4	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	●
6.000	3.800	0.038	100.0	0.053	5.00	0.0	0.600	o	150	Pipe/Conduit	●
6.001	3.800	0.255	14.9	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	●
7.000	3.800	0.038	100.0	0.082	5.00	0.0	0.600	o	150	Pipe/Conduit	●
7.001	3.800	0.500	7.6	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	●
1.005	20.471	-1.260	-16.2	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	●
1.006	9.347	0.100	93.5	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	●
1.007	8.286	1.100	7.5	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	●

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.003	50.00	6.55	0.987	0.245	0.0	0.0	0.0	1.35	95.5	33.2
1.004	50.00	6.60	0.850	0.245	0.0	0.0	0.0	0.96	68.0	33.2
5.000	50.00	6.06	2.499	0.200	0.0	0.0	0.0	1.10	77.9	27.1
5.001	50.00	6.17	2.154	0.200	0.0	0.0	0.0	1.16	82.1	27.1
5.002	50.00	6.89	2.109	0.212	0.0	0.0	0.0	0.49	34.6	28.7
5.003	50.00	6.96	1.790	0.212	0.0	0.0	0.0	3.08	218.1	28.7
5.004	50.00	7.02	1.300	0.212	0.0	0.0	0.0	3.07	217.2	28.7
6.000	50.00	5.06	2.263	0.053	0.0	0.0	0.0	1.00	17.8	7.2
6.001	50.00	5.09	2.255	0.053	0.0	0.0	0.0	2.62	46.4	7.2
7.000	50.00	5.06	2.538	0.082	0.0	0.0	0.0	1.00	17.8	11.1
7.001	50.00	5.08	2.500	0.082	0.0	0.0	0.0	3.68	65.0	11.1
1.005	50.00	10.71	0.840	0.592	0.0	0.0	0.0	0.09	1.66	80.2
1.006	50.00	10.86	2.100	0.592	0.0	0.0	0.0	1.04	18.46	80.2
1.007	50.00	10.90	2.000	0.592	0.0	0.0	0.0	2.83	22.36	80.2

Manhole Schedules for Sw

MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam.,L*W (mm)	PN	Pipe Out Invert Level (m)	Diameter (mm)	Pipes In Invert Level (m)	Diameter (mm)	Backdrop (mm)	MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam.,L*W (mm)	PN	Pipe Out Invert Level (m)	Diameter (mm)	Pipes In Invert Level (m)	Diameter (mm)	Backdrop (mm)	
Structure - (514)	2.220	0.620	Open Manhole	1200	1.000	1.600	150				S07a+Swale	3.400	1.291	Open Manhole	600	5.002	2.109	300	5.001	2.109	300	
S01	3.344	2.068	Open Manhole	1200	1.001	1.276	225	1.000	1.351	150	Swale End	3.400	1.610	Open Manhole	1200	5.003	1.790	300	5.002	2.088	300	298
Structure - (515)	3.400	0.700	Open Manhole	1200	2.000	2.700	150				S08	3.420	2.120	Open Manhole	1350	5.004	1.300	300	5.003	1.300	300	
S02	3.400	2.254	Open Manhole	1200	1.002	1.146	300	1.001	1.221	225	13	3.700	1.437	Open Manhole	1200	6.000	2.263	150				
								2.000	1.300	150	14	3.700	1.475	Open Manhole	1200	6.001	2.255	150	6.000	2.225	150	
Structure - (506)	2.950	0.886	Open Manhole	1200	3.000	2.964	225				14	3.540	1.002	Open Manhole	1200	7.000	2.536	150				
6	3.400	1.143	Open Manhole	1200	4.000	2.257	150	4.000	2.200	150	16	3.540	1.040	Open Manhole	1200	7.001	2.500	150	7.000	2.500	150	
7	3.400	1.200	Open Manhole	1200	4.001	2.200	150	1.002	0.987	300	S05	3.400	2.560	Open Manhole	1350	1.005	0.840	150	1.004	0.840	300	
S03	3.400	2.413	Open Manhole	1350	1.003	0.987	300	3.000	1.064	225							5.004	0.840	300			
								4.001	2.000	150	2						6.001	2.000	150	1160		
TANK S04	3.400	2.550	Open Manhole	1350	1.004	0.850	300	4.001	2.000	150	863						7.001	2.000	150	1160		
S06	3.513	1.014	Open Manhole	1350	5.000	2.499	300	1.003	0.950	300	100	S09	3.200	1.100	Open Manhole	1350	1.006	2.100	150	1.005	2.100	150
S07	3.400	1.246	Open Manhole	600	5.001	2.154	300	5.000	2.154	300		S10	3.200	1.200	Open Manhole	1350	1.007	2.000	100	1.006	2.000	150
												16	2.700	1.800	Open Manhole	1200		OUTFALL	1.007	0.900	100	

MH Name	Manhole Easting (m)	Manhole Northing (m)	Intersection Easting (m)	Intersection Northing (m)	Manhole Access	Layout (North)
Structure - (514)	540212.701	298141.813	540212.701	298141.813	Required	
S01	540187.910	298140.084	540187.910	298140.084	Required	
Structure - (515)	540156.885	298141.752	540156.885	298141.752	Required	
S02	540180.601	298131.855	540180.601	298131.855	Required	
Structure - (506)	540185.081	298068.913	540185.081	298068.913	Required	
S03	540183.818	298084.353	540183.818	298084.353	Required	
TANK S04	540178.830	298084.008	540178.830	298084.008	Required	
S06	540222.405	298144.855	540222.405	298144.855	Required	
S07	540227.187	298075.221	540227.187	298075.221	Required	
Swale End	540196.868	298071.212	540196.868	298071.212	Required	
S08	540184.068	298070.341	540184.068	298070.341	Required	



Craddys
 Eden Office Park
 Ham Green
 Bristol BS20 0DD
 Date 19/12/2023 15:35
 File 13173 Civils 3D Drainage - Copy2.mdx
 XP Solutions

Designed by purcella
 Checked by
 Network 2020.1.3

Manhole Schedules for Sw

MH Name	Manhole Easting (m)	Manhole Northing (m)	Intersection Easting (m)	Intersection Northing (m)	Manhole Access	Layout (North)
S05	540179.003	298081.371	540179.003	298081.371	Required	
S09	540175.513	298061.200	540175.513	298061.200	Required	
S10	540168.921	298054.574	540168.921	298054.574	Required	
16	540169.524	298046.310			No Entry	



Craddys
 Eden Office Park
 Ham Green
 Bristol BS20 0DD
 Date 19/12/2023 15:35
 File 13173 Civils 3D Drainage - Copy2.mdx
 XP Solutions

Designed by purcella
 Checked by
 Network 2020.1.3

PIPELINE SCHEDULES for Sw

Upstream Manhole

- Indicates pipe length does not match coordinates

PN	Hyd Diam Sect (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.000	o 150	Structure - (514)	2.220	1.600	0.470	Open Manhole	1200
1.001	o 225	S01	3.344	1.276	1.843	Open Manhole	1200
2.000	o 150	Structure - (515)	3.400	2.700	0.550	Open Manhole	1200
1.002	o 300	S02	3.400	1.146	1.954	Open Manhole	1200
3.000	o 225	Structure - (506)	2.950	2.064	0.661	Open Manhole	1200
4.000	o 150	6	3.400	2.257	0.993	Open Manhole	1200
4.001	o 150	7	3.400	2.200	1.050	Open Manhole	1200
1.003	o 300	S03	3.400	0.997	2.113	Open Manhole	1350
1.004	o 300	TANK S04	3.400	0.850	2.250	Open Manhole	1350
5.000	o 300	S06	3.513	2.499	0.714	Open Manhole	1350
5.001	o 300	S07	3.400	2.154	0.946	Open Manhole	600
5.002	o 300	S07a+Swale	3.400	2.109	0.991	Open Manhole	600
5.003	o 300	Swale End	3.400	1.790	1.310	Open Manhole	1200
5.004	o 300	S08	3.420	1.300	1.820	Open Manhole	1350
6.000	o 150	13	3.700	2.263	1.287	Open Manhole	1200
6.001	o 150	14	3.700	2.255	1.295	Open Manhole	1200
7.000	o 150	14	3.540	2.538	0.852	Open Manhole	1200

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.000	24.851	99.8	S01	3.344	1.351	1.843	Open Manhole	1200
1.001	11.006	200.1	S02	3.400	1.221	1.954	Open Manhole	1200
2.000	25.698	18.4	S02	3.400	1.300	1.950	Open Manhole	1200
1.002	47.611	299.4	S03	3.400	0.987	2.113	Open Manhole	1350
3.000	15.492	15.5	S03	3.400	1.064	2.111	Open Manhole	1350
4.000	5.700	100.0	7	3.400	2.200	1.050	Open Manhole	1200
4.001	5.700	28.5	S03	3.400	2.000	1.250	Open Manhole	1350
1.003	5.000	135.1	TANK S04	3.400	0.950	2.150	Open Manhole	1350
1.004	2.643	264.3	S05	3.400	0.840	2.260	Open Manhole	1350
5.000	69.798	202.3	S07	3.400	2.154	0.946	Open Manhole	600
5.001	8.200#	182.2	S07a+Swale	3.400	2.109	0.991	Open Manhole	600
5.002	21.000#	1000.0	Swale End	3.400	2.088	1.012	Open Manhole	1200
5.003	12.830	26.2	S08	3.420	1.300	1.820	Open Manhole	1350
5.004	12.137	26.4	S05	3.400	0.840	2.260	Open Manhole	1350
6.000	3.800	100.0	14	3.700	2.225	1.325	Open Manhole	1200
6.001	3.800	14.9	S05	3.400	2.000	1.250	Open Manhole	1350
7.000	3.800	100.0	16	3.540	2.500	0.890	Open Manhole	1200



Craddys
 Eden Office Park
 Ham Green
 Bristol BS20 0DD
 Date 19/12/2023 15:35
 File 13173 Civils 3D Drainage - Copy2.mdx
 XP Solutions

Designed by purcella
 Checked by
 Network 2020.1.3

PIPELINE SCHEDULES for Sw

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
7.001	o 150	16	S05	3.540	2.500	0.890	Open Manhole	1200
1.005	o 150	S05	3.400	0.840	2.410	Open Manhole	1350	
1.006	o 150	S09	3.200	2.100	0.950	Open Manhole	1350	
1.007	o 100	S10	3.200	2.000	1.100	Open Manhole	1350	

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
7.001	3.800	7.6	S05	3.400	2.000	1.250	Open Manhole	1350
1.005	20.471	-16.2	S09	3.200	2.100	0.950	Open Manhole	1350
1.006	9.347	93.5	S10	3.200	2.000	1.050	Open Manhole	1350
1.007	8.286	7.5	16	2.700	0.900	1.700	Open Manhole	1200

Free Flowing Outfall Details for Sw

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (mm)	D, L (mm)	W (mm)
1.007	16	2.700	0.900	0.000	1200	0

Simulation Criteria for Sw

Volumetric Runoff Coeff 0.750 Hot Start Level (mm) 0 Additional Flow - % of Total Flow 0.000 Flow per Person per Day (l/per/day) 0.000
 Areal Reduction Factor 1.000 Manhole Headloss Coeff (Global) 0.500 MADD Factor * 10m³/ha Storage 2.200 Run Time (mins) 60
 Hot Start (mins) 0 Foul Sewage per hectare (l/s) 0.000 Inlet Coefficient 0.800 Output Interval (mins) 1

Number of Input Hydrographs 0 Number of Online Controls 5 Number of Offline Controls 0 Number of Storage Structures 6 Number of Time/Area Diagrams 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR Region England and Wales Ratio R 0.436 Cv (Summer) 0.750 Storm Duration (mins) 30
 Return Period (years) 100 MS-60 (mm) 13.800 Profile Type Summer Cv (Winter) 0.840



Craddys
 Eden Office Park
 Ham Green
 Bristol BS20 0DD
 Date 19/12/2023 15:35
 File 13173 Civils 3D Drainage - Copy2.mdx
 XP Solutions

Designed by purcella
 Checked by
 Network 2020.1.3

Online Controls for Sw

Orifice Manhole: 7, DS/PN: 4.001, Volume (m³): 1.4

Diameter (m) 0.030 Discharge Coefficient 0.600 Invert Level (m) 2.200

Orifice Manhole: S08, DS/PN: 5.004, Volume (m³): 3.9

Diameter (m) 0.140 Discharge Coefficient 0.600 Invert Level (m) 1.300

Orifice Manhole: 14, DS/PN: 6.001, Volume (m³): 1.7

Diameter (m) 0.020 Discharge Coefficient 0.600 Invert Level (m) 2.255

Orifice Manhole: 16, DS/PN: 7.001, Volume (m³): 1.2

Diameter (m) 0.040 Discharge Coefficient 0.600 Invert Level (m) 2.500

Pump Manhole: S05, DS/PN: 1.005, Volume (m³): 4.6

Invert Level (m) 0.840

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.200	5.0000	0.800	5.0000	1.400	5.0000	2.000	5.0000	2.600	5.0000	3.200	5.0000	3.800	5.0000	4.400	5.0000	5.000	5.0000	5.600	5.0000
0.400	5.0000	1.000	5.0000	1.600	5.0000	2.200	5.0000	2.800	5.0000	3.400	5.0000	4.000	5.0000	4.600	5.0000	5.200	5.0000	5.800	5.0000
0.600	5.0000	1.200	5.0000	1.800	5.0000	2.400	5.0000	3.000	5.0000	3.600	5.0000	4.200	5.0000	4.800	5.0000	5.400	5.0000	6.000	5.0000

Storage Structures for Sw

Porous Car Park Manhole: 6, DS/PN: 4.000

Infiltration Coefficient Base (m/hr) 0.00000 Safety Factor 2.0 Width (m) 5.0 Depression Storage (mm) 5
 Membrane Percolation (mm/hr) 1000 Porosity 0.30 Length (m) 55.0 Evaporation (mm/day) 3
 Max Percolation (1/s) 76.4 Invert Level (m) 2.700 Slope (1:X) 0.0 Cap Volume Depth (m) 0.350

Cellular Storage Manhole: S06, DS/PN: 5.000

Invert Level (m) 2.499 Infiltration Coefficient Base (m/hr) 0.00000 Infiltration Coefficient Side (m/hr) 0.00000 Safety Factor 2.0 Porosity 0.30

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	42.0	0.0	1.000	42.0	0.0	1.001	0.0	0.0

Complex Manhole: Swale End, DS/PN: 5.003

Cellular Storage

Invert Level (m) 1.790 Infiltration Coefficient Base (m/hr) 0.00000 Infiltration Coefficient Side (m/hr) 0.00000 Safety Factor 2.0 Porosity 0.30

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	20.0	0.0	1.100	20.0	0.0	1.101	0.0	0.0

Tank or Pond

Invert Level (m) 3.060

Depth (m)	Area (m ²)	Depth (m)	Area (m ²)
0.000	20.0	0.331	60.0

Porous Car Park Manhole: 13, DS/PN: 6.000

Infiltration Coefficient Base (m/hr) 0.00000 Safety Factor 2.0 Width (m) 5.0 Depression Storage (mm) 5
 Membrane Percolation (mm/hr) 1000 Porosity 0.30 Length (m) 80.0 Evaporation (mm/day) 3
 Max Percolation (1/s) 111.1 Invert Level (m) 2.900 Slope (1:X) 0.0 Cap Volume Depth (m) 0.350


Porous Car Park Manhole: 14, DS/PN: 7.000

Infiltration Coefficient Base (m/hr) 0.00000 Safety Factor 2.0 Width (m) 5.0 Depression Storage (mm) 5
 Membrane Percolation (mm/hr) 1000 Porosity 0.30 Length (m) 87.4 Evaporation (mm/day) 3
 Max Percolation (1/s) 121.4 Invert Level (m) 2.900 Slope (1:X) 0.0 Cap Volume Depth (m) 0.350

Cellular Storage Manhole: S05, DS/PN: 1.005

Invert Level (m) 1.500 Infiltration Coefficient Base (m/hr) 0.00000 Infiltration Coefficient Side (m/hr) 0.00000 Safety Factor 2.0 Porosity 0.95

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	792.0	0.0	0.500	792.0	0.0	0.510	0.0	0.0

Craddys		Page 0
Eden Office Park		
Ham Green		
Bristol BS20 0DD		
Date 19/12/2023 15:36		
File 13173 Civils 3D Drainage - Copy2.mdx		Designed by purcella
XP Solutions		Checked by
		Network 2020.1.3


2 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Sw

Simulation Criteria
Areal Reduction Factor 1.000 Hot Start Level (mm) 0 Foul Sewage per hectare (l/s) 0.000 MADD Factor * 10m³/ha Storage 2.200 Flow per Person per Day (l/per/day) 0.000
Hot Start (mins) 0 Manhole Headloss Coeff (Global) 0.500 Additional Flow - % of Total Flow 0.000 Inlet Coefficient 0.800
Number of Input Hydrographs 0 Number of Online Controls 5 Number of Offline Controls 0 Number of Storage Structures 6 Number of Time/Area Diagrams 0 Number of Real Time Controls 0

Synthetic Rainfall Details
Rainfall Model FEH Site Location GB 540254 298056 TL 40254 98056 Cv (Summer) 0.750
FEH Rainfall Version 2013 Data Type Point Cv (Winter) 0.840
Margin for Flood Risk Warning (mm) 300.0 DTS Status ON Inertia Status ON
Analysis Timestep 2.5 Second Increment (Extended) DVD Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 120, 240, 360, 480, 960, 1440, 2880, 7200, 10080
Return Period(s) (years) 2, 30, 100
Climate Change (%) 0, 25, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Surcharged			Flooded		Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
									Level (m)	Depth (m)	Volume (m ³)	Flow / Overflow Cap. (l/s)	Flow (l/s)				
1.000	Structure - (514)	120 Summer	2	+0%	30/120 Summer	100/360 Winter			1.629	-0.121	0.000	0.08		1.4	OK	3	
1.001	S01 240	Winter	2	+0%	2/120 Summer				1.563	0.062	0.000	0.06		1.7	SURCHARGED		
2.000	Structure - (515)	120 Summer	2	+0%	2/120 Summer				2.717	-0.133	0.000	0.03		1.1	OK		
1.002	S02 240	Winter	2	+0%	2/120 Summer				1.562	0.116	0.000	0.07		4.1	SURCHARGED		
3.000	Structure - (506)	120 Summer	2	+0%	100/360 Winter				2.083	-0.206	0.000	0.02		2.1	OK		
4.000	S 6 120	Winter	2	+0%	2/120 Summer				2.712	0.305	0.000	0.12	25	1.8	SURCHARGED		
4.001	S 7 120	Winter	2	+0%	2/120 Summer				2.709	0.359	0.000	0.05		1.3	SURCHARGED		
1.003	S03 240	Winter	2	+0%	2/120 Summer				1.561	0.274	0.000	0.13		8.1	SURCHARGED		
1.004	TANK S04 240	Winter	2	+0%	2/120 Summer				1.561	0.411	0.000	0.16		8.1	SURCHARGED		
5.000	S06 120	Summer	2	+0%	100/120 Summer				2.589	-0.210	0.000	0.19	20	14.5	OK		
5.001	S07 120	Summer	2	+0%	30/120 Summer				2.311	-0.140	0.000	0.23		14.2	OK		
5.002	S07a+Swale 120	Summer	2	+0%	30/120 Summer				2.306	-0.103	0.000	0.76		15.0	OK		
5.003	Swale End 120	Summer	2	+0%	30/120 Summer				1.849	-0.241	0.000	0.09	22	15.0	OK		
5.004	S08 120	Summer	2	+0%	2/120 Summer				1.652	0.052	0.000	0.09		14.8	SURCHARGED		
6.000	S 13 240	Winter	2	+0%	2/120 Summer				2.919	0.506	0.000	0.09	76	1.1	SURCHARGED		
6.001	S 14 120	Winter	2	+0%	2/120 Summer				2.931	0.526	0.000	0.02		0.7	SURCHARGED		
7.000	S 14 120	Winter	2	+0%	2/120 Summer				2.520	0.232	0.000	0.21	29	2.5	SURCHARGED		
7.001	S 16 120	Winter	2	+0%	2/120 Summer				2.933	0.283	0.000	0.05		2.1	SURCHARGED		
1.005	S05 240	Winter	2	+0%	2/120 Summer				1.560	0.570	0.000	1.21	122	5.0	SURCHARGED		
1.006	S09 360	Winter	2	+0%					2.157	-0.093	0.000	0.31		5.0	OK		
1.007	S10 240	Winter	2	+0%					2.033	-0.067	0.000	0.24		5.0	OK		

Craddys		Page 1
Eden Office Park Ham Green Bristol BS20 0DD		
Date 19/12/2023 15:36	Designed by purcella	
File 13173 Civils 3D Drainage - Copy2.mdx	Checked by	
XP Solutions	Network 2020.1.3	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Sw

Simulation Criteria
Areal Reduction Factor 1.000 Hot Start Level (mm) 0 Foul Sewage per hectare (l/s) 0.000 MADD Factor * 10m²/ha Storage 2.200 Flow per Person per Day (l/per/day) 0.000
Hot Start (mins) 0 Manhole Headloss Coeff (Global) 0.500 Additional Flow - % of Total Flow 0.000 Inlet Coefficient 0.800
Number of Input Hydrographs 0 Number of Online Controls 5 Number of Offline Controls 0 Number of Storage Structures 6 Number of Time/Area Diagrams 0 Number of Real Time Controls 0

Synthetic Rainfall Details
Rainfall Model FEH Site Location GB 540254 298056 TL 40254 98056 Cv (Summer) 0.750
FEH Rainfall Version 2013 Data Type Point Cv (Winter) 0.840
Margin for Flood Risk Warning (mm) 300.0 DTS Status ON Inertia Status ON
Analysis Timestep 2.5 Second Increment (Extended) DVD Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 120, 240, 360, 480, 960, 1440, 2880, 7200, 10080
Return Period(s) (years) 2, 30, 100
Climate Change (%) 0, 25, 40

WARNING: Half Drain Time has not been calculated as the structure is too full.

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m ³)	Flow / Overflow Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
1.000	Structure - (514)	120 Summer	30	+25%	30/120 Summer	100/360 Winter			1.848	0.098	0.000	0.26		4.4	SURCHARGED	3
1.001	S01	120 Winter	30	+25%	2/120 Summer				1.829	0.328	0.000	0.25		7.7	SURCHARGED	
2.000	Structure - (515)	120 Summer	30	+25%					2.730	-0.120	0.000	0.09		3.5	OK	
1.002	S02	120 Winter	30	+25%	2/120 Summer				1.821	0.375	0.000	0.34		20.2	SURCHARGED	
3.000	Structure - (506)	120 Summer	30	+25%	100/360 Winter				2.098	-0.191	0.000	0.06		6.5	OK	
4.000	S06	120 Winter	30	+25%	2/120 Summer				2.870	0.463	0.000	0.14	95	2.0	SURCHARGED	
4.001	S07	120 Winter	30	+25%	2/120 Summer				2.867	0.517	0.000	0.05		1.5	SURCHARGED	
1.003	S03	480 Winter	30	+25%	2/120 Summer				1.817	0.530	0.000	0.22		13.4	SURCHARGED	
1.004	TANK S04	480 Winter	30	+25%	2/120 Summer				1.816	0.666	0.000	0.26		13.3	SURCHARGED	
5.000	S06	120 Summer	30	+25%	100/120 Summer				2.671	-0.128	0.000	0.62	18	45.9	OK	
5.001	S07	120 Summer	30	+25%	30/120 Summer				2.590	0.136	0.000	0.74		45.6	SURCHARGED	
5.002	S07a+Swale	120 Summer	30	+25%	30/120 Summer				2.511	0.102	0.000	2.45		48.2	SURCHARGED	
5.003	Swale End	120 Summer	30	+25%	30/120 Summer				2.473	0.383	0.000	0.21	13	36.4	SURCHARGED	
5.004	S08	120 Summer	30	+25%	2/120 Summer				2.401	0.801	0.000	0.21		36.1	SURCHARGED	
6.000	S09	240 Winter	30	+25%	2/120 Summer				3.070	0.657	0.000	0.10		1.2	SURCHARGED	
6.001	S10	240 Winter	30	+25%	2/120 Summer				3.072	0.667	0.000	0.02		0.7	SURCHARGED	
7.000	S11	120 Winter	30	+25%	2/120 Summer				3.083	0.395	0.000	0.24	96	2.9	SURCHARGED	
7.001	S12	120 Winter	30	+25%	2/120 Summer				3.091	0.441	0.000	0.06		2.5	SURCHARGED	
1.005	S05	480 Winter	30	+25%	2/120 Summer				1.816	0.826	0.000	1.21		5.0	SURCHARGED	
1.006	S09	360 Winter	30	+25%					2.157	-0.093	0.000	0.31		5.0	OK	
1.007	S10	360 Winter	30	+25%					2.033	-0.067	0.000	0.24		5.0	OK	



Craddys
 Eden Office Park
 Ham Green
 Bristol BS20 0DD
 Date 19/12/2023 15:36
 File 13173 Civils 3D Drainage - Copy2.mdx
 XP Solutions

Designed by purcella
 Checked by
 Network 2020.1.3

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for SW


Simulation Criteria
 Areal Reduction Factor 1.000 Hot Start Level (mm) 0 Foul Sewage per hectare (l/s) 0.000 MADD Factor * 10m²/ha Storage 2.200 Flow per Person per Day (l/per/day) 0.000
 Hot Start (mins) 0 Manhole Headloss Coeff (Global) 0.500 Additional Flow - % of Total Flow 0.000 Inlet Coefficient 0.800
 Number of Input Hydrographs 0 Number of Online Controls 5 Number of Offline Controls 0 Number of Storage Structures 6 Number of Time/Area Diagrams 0 Number of Real Time Controls 0

Synthetic Rainfall Details
 Rainfall Model FEH Site Location GB 540254 298056 TL 40254 98056 Cv (Summer) 0.750
 FEH Rainfall Version 2013 Data Type Point Cv (Winter) 0.840
 Margin for Flood Risk Warning (mm) 300.0 DTS Status ON Inertia Status ON
 Analysis Timestep 2.5 Second Increment (Extended) DVD Status ON

Profile(s) Summer and Winter
 Duration(s) (mins) 120, 240, 360, 480, 960, 1440, 2880, 7200, 10080
 Return Period(s) (years) 2, 30, 100
 Climate Change (%) 0, 25, 40

WARNING: Half Drain Time has not been calculated as the structure is too full.

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m ³)	Flow / Overflow Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
1.000	Structure - (514)	480 Winter	100	+40%	30/120 Summer	100/360 Winter			2.248	0.498	28,094	0.24		4.1	FLOOD	3
1.001	S01	480 Winter	100	+40%	2/120 Summer				2.305	0.804	0.000	0.14		4.3	SURCHARGED	
2.000	Structure - (515)	120 Summer	100	+40%					2.737	-0.113	0.000	0.14		5.4	OK	
1.002	S02	480 Winter	100	+40%	2/120 Summer				2.322	0.876	0.000	0.19		11.3	SURCHARGED	
3.000	Structure - (506)	480 Winter	100	+40%	100/360 Winter				2.336	0.047	0.000	0.02		2.8	SURCHARGED	
4.000	S 6	240 Winter	100	+40%	2/120 Summer				3.023	0.616	0.000	0.12	188	1.7	SURCHARGED	
4.001	S 7	240 Winter	100	+40%	2/120 Summer				3.019	0.669	0.000	0.06		1.7	SURCHARGED	
1.003	S03	480 Winter	100	+40%	2/120 Summer				2.335	1.048	0.000	0.33		20.3	SURCHARGED	
1.004	TANK S04	480 Winter	100	+40%	2/120 Summer				2.337	1.187	0.000	0.39		20.2	SURCHARGED	
5.000	S06	120 Summer	100	+40%	100/120 Summer				3.256	0.457	0.000	0.73	13	54.4	FLOOD RISK	
5.001	S07	120 Summer	100	+40%	30/120 Summer				3.155	0.701	0.000	0.82		50.3	FLOOD RISK	
5.002	S07a+Swale	120 Summer	100	+40%	30/120 Summer				3.075	0.666	0.000	2.69		52.8	SURCHARGED	
5.003	Swale End	120 Summer	100	+40%	30/120 Summer				3.028	0.930	0.000	0.26	25	45.9	SURCHARGED	
5.004	S08	120 Summer	100	+40%	2/120 Summer				2.921	1.321	0.000	0.26		44.8	SURCHARGED	
6.000	S 13	360 Winter	100	+40%	2/120 Summer				3.216	0.803	0.000	0.08		1.0	SURCHARGED	
6.001	S 14	360 Winter	100	+40%	2/120 Summer				3.217	0.812	0.000	0.03		0.8	SURCHARGED	
7.000	S 14	240 Winter	100	+40%	2/120 Summer				3.240	0.552	0.000	0.26	188	3.1	FLOOD RISK	
7.001	S 16	240 Winter	100	+40%	2/120 Summer				3.252	0.602	0.000	0.06		2.8	FLOOD RISK	
1.005	S05	480 Winter	100	+40%	2/120 Summer				2.339	1.349	0.000	1.21		5.0	SURCHARGED	
1.006	S09	960 Winter	100	+40%					2.157	-0.093	0.000	0.31		5.0	OK	
1.007	S10	960 Winter	100	+40%					2.033	-0.067	0.000	0.24		5.0	OK	

Craddys		Page 0
Eden Office Park		
Ham Green		
Bristol BS20 0DD		
Date 19/12/2023 15:38		
File 13173 Civils 3D Drainage - Copy2.mdx		Designed by purcella
XP Solutions		Checked by
		Network 2020.1.3

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Sw

Simulation Criteria

Areal Reduction Factor 1.000 Hot Start Level (mm) 0 Foul Sewage per hectare (l/s) 0.000 MADD Factor * 10m³/ha Storage 2.200 Flow per Person per Day (l/per/day) 0.000
Hot Start (mins) 0 Manhole Headloss Coeff (Global) 0.500 Additional Flow - % of Total Flow 0.000 Inlet Coefficient 0.800

Number of Input Hydrographs 0 Number of Online Controls 5 Number of Offline Controls 0 Number of Storage Structures 6 Number of Time/Area Diagrams 0 Number of Real Time Controls 0

Synthetic Rainfall Details


Rainfall Model FSR Region England and Wales MS-60 (mm) 19.000 Ratio R 0.437 Cv (Summer) 0.750 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0 DTS Status ON Inertis Status ON
Analysis Timestep 2.5 Second Increment (Extended) DVD Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60
Return Period(s) (years) 2, 30, 100
Climate Change (%) 0, 25, 40

WARNING: Half Drain Time has not been calculated as the structure is too full.

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m ³)	Flow / Overflow Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
1.000	Structure - (514)	15 Winter	2	+0%	30/15 Summer	100/15 Winter			1.645	-0.105	0.000	0.19		3.3	OK	
1.001	S01	30 Winter	2	+0%	2/15 Summer				1.604	-0.103	0.000	0.17		5.2	SURCHARGED	1
2.000	Structure - (515)	15 Winter	2	+0%	2/15 Summer				2.725	-0.125	0.000	0.07		2.6	OK	
1.002	S02	30 Winter	2	+0%	2/15 Summer				1.597	-0.151	0.000	0.20		12.2	SURCHARGED	
3.000	Structure - (506)	15 Winter	2	+0%	2/15 Summer				2.094	-0.195	0.000	0.04		4.9	OK	
4.000	S	60 Winter	2	+0%	2/15 Summer				2.714	-0.307	0.000	0.15	22	2.3	SURCHARGED	
4.001	S	60 Winter	2	+0%	2/15 Summer				2.711	-0.361	0.000	0.05		1.3	SURCHARGED	
1.003	S03	30 Winter	2	+0%	2/15 Summer				1.578	-0.291	0.000	0.35		21.6	SURCHARGED	
1.004	TANK S04	60 Winter	2	+0%	2/15 Summer				1.546	-0.396	0.000	0.34		17.5	SURCHARGED	
5.000	S06	15 Winter	2	+0%	30/15 Summer				2.641	-0.158	0.000	0.43	7	32.2	OK	
5.001	S07	15 Winter	2	+0%	2/15 Summer				2.489	-0.035	0.000	0.44		26.8	SURCHARGED	
5.002	S07a+Swale	15 Summer	2	+0%	30/15 Summer				2.409	0.000	0.000	1.27		25.0	OK	
5.003	Swale End	15 Winter	2	+0%	30/15 Summer				1.900	-0.190	0.000	0.15	6	26.6	OK	
5.004	S09	15 Winter	2	+0%	2/15 Summer				1.880	-0.250	0.000	0.14		24.5	SURCHARGED	
6.000	S	13 60 Winter	2	+0%	2/15 Summer				2.912	-0.499	0.000	0.21	32	2.5	SURCHARGED	
6.001	S	14 60 Winter	2	+0%	2/15 Summer				2.914	-0.509	0.000	0.02		0.7	SURCHARGED	
7.000	S	14 60 Winter	2	+0%	2/15 Summer				2.922	-0.234	0.000	0.26	25	3.2	SURCHARGED	
7.001	S	16 60 Winter	2	+0%	2/15 Summer				2.919	-0.269	0.000	0.05		2.1	SURCHARGED	
1.005	S05	60 Winter	2	+0%	2/15 Summer				1.546	-0.556	0.000	1.21		5.0	SURCHARGED	
1.006	S09	30 Summer	2	+0%					2.157	-0.093	0.000	0.31		5.0	OK	
1.007	S10	60 Winter	2	+0%					2.033	-0.067	0.000	0.24		5.0	OK	

Craddys		Page 1
Eden Office Park		
Ham Green		
Bristol BS20 ODD		
Date 19/12/2023 15:38		
File 13173 Civils 3D Drainage - Copy2.mxd		Designed by purcella
XP Solutions		Checked by
		Network 2020.1.3

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Sw

Simulation Criteria
Areal Reduction Factor 1.000 Hot Start Level (mm) 0 Foul Sewage per hectare (l/s) 0.000 MADD Factor * 10m²/ha Storage 2.200 Flow per Person per Day (l/per/day) 0.000
Hot Start (mins) 0 Manhole Headloss Coeff (Global) 0.500 Additional Flow - % of Total Flow 0.000 Inlet Coefficient 0.800

Number of Input Hydrographs 0 Number of Online Controls 5 Number of Offline Controls 0 Number of Storage Structures 6 Number of Time/Area Diagrams 0 Number of Real Time Controls 0

Synthetic Rainfall Details
Rainfall Model FSR Region England and Wales MS-60 (mm) 19.000 Ratio R 0.437 Cv (Summer) 0.750 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0 DTS Status ON Inertis Status ON
Analysis Timestep 2.5 Second Increment (Extended) DVD Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60
Return Period(s) (years) 2, 30, 100
Climate Change (%) 0, 25, 40

WARNING: Half Drain Time has not been calculated as the structure is too full.

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m ³)	Flow / Overflow Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
1.000	Structure - (514)	15 Winter	30	+25%	30/15 Summer	100/15 Winter			1.898	0.148	0.000	0.49			8.3 SURCHARGED	
1.001	S01	15 Summer	30	+25%	2/15 Summer			1.859	0.358	0.000	0.59				18.1 SURCHARGED	1
2.000	Structure - (515)	15 Winter	30	+25%	2/15 Summer			2.740	-0.110	0.000	0.16				6.2 OK	
1.002	S02	15 Summer	30	+25%	2/15 Summer			1.833	0.387	0.000	0.71				42.5 SURCHARGED	
3.000	Structure - (506)	15 Winter	30	+25%	2/15 Summer			2.112	-0.177	0.000	0.10				11.7 OK	
4.000	S	60 Winter	30	+25%	2/15 Summer			2.803	0.396	0.000	0.19		59		2.8 SURCHARGED	
4.001	S	60 Winter	30	+25%	2/15 Summer			2.800	0.450	0.000	0.05				1.4 SURCHARGED	
1.003	S03	60 Winter	30	+25%	2/15 Summer			1.730	0.443	0.000	0.67				41.1 SURCHARGED	
1.004	TANK S04	60 Winter	30	+25%	2/15 Summer			1.652	0.502	0.000	0.79				41.0 SURCHARGED	
5.000	S06	15 Winter	30	+25%	30/15 Summer			2.852	0.053	0.000	0.89		8		66.6 SURCHARGED	
5.001	S07	15 Winter	30	+25%	2/15 Summer			2.737	0.283	0.000	1.05				64.2 SURCHARGED	
5.002	S07a+Swale	15 Winter	30	+25%	30/15 Summer			2.665	0.256	0.000	3.39				66.6 SURCHARGED	
5.003	Swale End	15 Winter	30	+25%	30/15 Summer			2.630	0.540	0.000	0.24		10		41.6 SURCHARGED	
5.004	S08	15 Winter	30	+25%	2/15 Summer			2.542	0.542	0.000	0.24				40.3 SURCHARGED	
6.000	S	13 60 Winter	30	+25%	2/15 Summer			2.985	0.572	0.000	0.23				2.8 SURCHARGED	
6.001	S	14 60 Winter	30	+25%	2/15 Summer			2.985	0.580	0.000	0.02				0.7 SURCHARGED	
7.000	S	14 60 Winter	30	+25%	2/15 Summer			3.014	0.326	0.000	0.27		62		2.3 SURCHARGED	
7.001	S	16 60 Summer	30	+25%	2/15 Summer			3.023	0.373	0.000	0.05				3.3 SURCHARGED	
1.005	S05	60 Winter	30	+25%	2/15 Summer			1.642	0.652	0.000	1.21				5.0 SURCHARGED	
1.006	S09	60 Summer	30	+25%				2.157	-0.093	0.000	0.31				5.0 OK	
1.007	S10	30 Summer	30	+25%				2.035	-0.067	0.000	0.24				5.0 OK	



Craddys	
Eden Office Park	
Ham Green	
Bristol BS20 0DD	
Date 19/12/2023 15:38	Designed by purcella
File 13173 Civils 3D Drainage - Copy2.mxd	Checked by
XP Solutions	Network 2020.1.3

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for SW

Simulation Criteria
 Areal Reduction Factor 1.000 Hot Start Level (mm) 0 Foul Sewage per hectare (l/s) 0.000 MADD Factor * 10m²/ha Storage 2.200 Flow per Person per Day (l/per/day) 0.000
 Hot Start (mins) 0 Manhole Headloss Coeff (Global) 0.500 Additional Flow - % of Total Flow 0.000 Inlet Coefficient 0.800

Number of Input Hydrographs 0 Number of Online Controls 5 Number of Offline Controls 0 Number of Storage Structures 6 Number of Time/Area Diagrams 0 Number of Real Time Controls 0

Synthetic Rainfall Details
 Rainfall Model FSR Region England and Wales MS-60 (mm) 19.000 Ratio R 0.437 Cv (Summer) 0.750 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0 DTS Status ON Inertia Status ON
 Analysis Timestep 2.5 Second Increment (Extended) DVD Status ON

Profile(s) Summer and Winter
 Duration(s) (mins) 15, 30, 60
 Return Period(s) (years) 2, 30, 100
 Climate Change (%) 0, 25, 40

WARNING: Half Drain Time has not been calculated as the structure is too full.

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m ³)	Flow / Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
1.000	Structure - (514)	15 Winter	100	+40%	30/15 Summer	100/15 Winter			2.220	0.470	0.066	0.73		12.1	FLOOD	1
1.001	S01	15 Winter	100	+40%	2/15 Summer				2.147	0.646	0.000	0.78		24.0	SURCHARGED	
2.000	Structure - (515)	15 Winter	100	+40%					2.749	-0.101	0.000	0.23		9.1	OK	
1.002	S02	15 Winter	100	+40%	2/15 Summer				2.088	0.642	0.000	1.03		61.6	SURCHARGED	
3.000	Structure - (506)	15 Winter	100	+40%					2.121	-0.168	0.000	0.14		17.0	OK	
4.000	S	60 Winter	100	+40%	2/15 Summer				2.801	0.474	0.000	0.17		2.6	SURCHARGED	
4.001	S	60 Winter	100	+40%	2/15 Summer				2.878	0.528	0.000	0.06		1.5	SURCHARGED	
1.003	S03	15 Winter	100	+40%	2/15 Summer				1.899	0.612	0.000	1.75		107.2	SURCHARGED	
1.004	TANK S04	60 Winter	100	+40%	2/15 Summer				1.721	0.571	0.000	1.16		60.1	SURCHARGED	
5.000	S06	15 Winter	100	+40%	30/15 Summer				3.305	0.506	0.000	1.13	7	84.6	FLOOD RISK	
5.001	S07	15 Winter	100	+40%	2/15 Summer				3.221	0.767	0.000	1.21		74.3	FLOOD RISK	
5.002	S07a+Swale	15 Winter	100	+40%	30/15 Summer				3.145	0.736	0.000	3.93		77.2	FLOOD RISK	
5.003	Swale End	15 Winter	100	+40%	30/15 Summer				3.096	1.006	0.000	0.29	15	51.1	SURCHARGED	
5.004	S09	15 Winter	100	+40%	2/15 Summer				2.973	1.373	0.000	0.23		46.0	SURCHARGED	
6.000	S	13 60 Winter	100	+40%	2/15 Summer				3.045	0.632	0.000	0.24		3.0	SURCHARGED	
6.001	S	14 60 Winter	100	+40%	2/15 Summer				3.044	0.639	0.000	0.02		0.7	SURCHARGED	
7.000	S	14 60 Winter	100	+40%	2/15 Summer				3.096	0.408	0.000	0.26		3.1	SURCHARGED	
7.001	S	16 60 Winter	100	+40%	2/15 Summer				3.092	0.442	0.000	0.06		2.5	SURCHARGED	
1.005	S05	60 Winter	100	+40%	2/15 Summer				1.721	0.731	0.000	1.21		5.0	SURCHARGED	
1.006	S09	60 Winter	100	+40%					2.157	-0.093	0.000	0.31		5.0	OK	
1.007	S10	30 Summer	100	+40%					2.035	-0.067	0.000	0.24		5.0	OK	