



Internal view

External view

NOTES:  
Door and frame material to be prime European Oak

Finish TBC (Manufacture to sanded finish 240)

20mm T&G boards for bottom panel

Oak cill section with Galvanised water bar 25mm x 6mm

44mm thick door

Rebated frame with aquamac 21 weather seal

Traditional Mortice & Tenon construction

Rebated glazing bars with streamlined chamfer detail to suit black weather boarded barn

4mm toughened float glass, 4no panes

102mm hinges

Letter box

Handles not included (TBC by customer as to style required)

Espagnolette multipoint locking system

Door hung on left hand side from outside, to open inwards

00	Issued for approval	12.04.2024
Rev	Changes	Date

This drawing is prepared solely for the use of Nightingale Joinery Limited in preparation of their work and must not be used for any other purpose. If dimensions are critical for other trades it shall be their responsibility to check them on site.

Client  
Nightingale Joinery Ltd

Site Address  
Hall Barn  
Little Waldingfield  
Sudbury, Suffolk  
CO10 0SY

Drawing Title  
Mr & Mrs Mason  
Solid Oak Front Door

Scale  
1:10 @ A3

Drawn By BH	Date Drawn 12.04.2024	Checked By -
----------------	--------------------------	-----------------

**Nightingale Joinery Ltd**  
Nightingale Hall Farm,  
Nightingale Hall Road,  
Earls Colne,  
Colchester,  
Essex,  
CO6 2NR  
Tel:01787 224332  
Fax:01787 221328  
E-mail: info@nightingalejoinery.co.uk

Drawing Status  
**PLANNING APPROVAL  
DRAWING**

Job No 3482	Drawing Number 3482-DRG-001	Revision 00
----------------	--------------------------------	----------------