

Rose Barn, Cemetery Lane, Bourton on the Water, GL54 2HB

External stair specification

Treated softwood with 32 x 32 mm simple balusters and handrail between 900 and 1100mm measure vertically above pitch line. 245mm goings and approximate 210mm equal risers with no aperture to permit the passage of a 100mm di sphere.

David Hicks

20/3/24