



EXISTING



PROPOSED

SCOPE OF WORKS

1. Remove existing shop frontage, shutter and door.
2. Remove existing upvc windows from upper floors.
3. Remove existing rainwater goods and replace with cast iron
4. Repair brickwork as required. Re-point in lime mortar. Clean brick facade.
5. Repair and re-decorate bay window.
6. Install new timber sliding sash windows to upper floors including bay.
7. Install new shop front as detailed.




SCALE 1:50 @ A3

| LETTER | REVISION  | DATE     |
|--------|---|----------|
| B      | Reference to shutter omitted. Issued for Planning | 10/04/24 |
| A      | Updated to reflect comments.                      | 27/03/24 |
| Ⓢ      | First issue                                       |          |

| LETTER    | REVISION | DATE |
|-----------|----------|------|
| Revisions |          |      |

|   |   |               |
|---|---|---------------|
|  <p><b>JOMAST</b><br/>DEVELOPMENTS</p> | <p>Top Floor, Old House<br/>Edgop Street<br/>STOCKTON-ON-TEES<br/>TS18 1SW</p> <p>T: 01642 674203<br/>F: 01642 618153<br/>E: enquiries@jomast.co.uk</p> |               |
| <p>PROJECT<br/>STOCKTON – 11 HIGH STREET</p>  |   |               |
| <p>DRAWING TITLE<br/>EXISTING AND PROPOSED FRONT ELEVATION</p>  |   |               |
| DRAWN<br>IS   | PAPER SIZE<br>A3  | SCALE<br>1:50 |
| JOB NUMBER<br>96006   | DRAWING NUMBER + REVISION<br>20-01 B  | STATUS        |