



Rainwater Soakaway Calculation as per clause 3.6.5 of building regs
 0.214 x 997 (roof area) x 0.3 = 65m³ volume required
 Soakaway 1.25m x 2.5m x 1.25m deep provides 48.75m³ capacity
 Soakaway to be located min. 5m off building and boundaries
 Crushed hardcore filled trench with geotextile membrane surround

-  CONCRETE
-  HARDCORE

New building sited in closest
 position available to existing
 Daftmill Farm distillery
 buildings.
 Although the land is currently
 agricultural field,
 the proposal has been
 strategically located
 within the field corner
 adjoining the holding
 and is not disruptive
 to the rest of the field.

PROPOSED SITE PLAN

Scale 1:500



Data provider copyright : © Crown Copyright 2024. All rights reserved. Licence Number 100047514

Notes

All dimensions are in millimeters unless noted otherwise
 No responsibility can be taken for any errors found by measuring
 off this drawing or ordering of materials via drawing dimensions
 All dimensions contained within this drawings to be double
 checked on site by project manager / contractor and if any issues
 please consult with Project Management Forfar Ltd
 This drawing is to be read in conjunction with latest revisions of
 all relevant architectural and engineer drawings
 Please refer to structural engineer drawings for all structural
 information relating to this project

REV	DESCRIPTION

PROJECT MANAGEMENT FORFAR LTD
 11 OSPREY CRESCENT, FORFAR,
 ANGUS, DD8 2ES
 TELE: 07722299558
 E-MAIL: phil@pm-scot.com
 WEBSITE: www.pm-scot.com

CLIENT:
ANGLEPARK FARMING COMPANY

PROJECT ADDRESS:
DAFTMILL DISTILLERY
DAFTMILL FARM
BY CUPAR, FIFE
KY15 5RF

DRAWN: **P. Bine** CHECKED: DATE: **MARCH 24** REVISION:

PROJECT NAME:
ERECTION OF WHISKY MATURATION WAREHOUSES

DRAWING TITLE:
PROPOSED SITE PLAN

SCALE: **1:500** SHEET SIZE: **A1** SHEET NO:

PROJECT NO: **2545** STATUS: **PLANNING**

DRAWING NO: **PMF 2545 - 200 PL**