

27th March 2024

Job No. 24/A/371

THE TALISMAN THEATRE AND ARTS CENTRE
BARROW ROAD
KENILWORTH
WARWICKSHIRE
CV8 1EG

SPECIFICATION FOR EXTERNAL SIGNAGE

Halo Illumination

1 No. set of TALISMAN THEATRE letters.

3542mm wide x 341mm cap height.

Font to be Cartogothic standard font.

Face and returns constructed from brushed stainless steel returns 50mm deep.

5mm opal polycarbonate back trays, light to emit from rear internal 6500K white LED lighting modules.

Illuminance levels – 95 cd/m².

Lettering affixed to powder coated rails (RAL 9015 traffic white – matt finish).

12V transformer mounted remotely inside building.

Fused spur to be provided by Client.

All quotations to allow for the following:-

Site survey

Delivery to site and installation.

Artwork set up and technical plans.

Cherry picker to be allowed for, for installation.

Work to be completed by the end of June 2024/July 2024. Initial mark up to be provided by artwork.