

NOTES

This drawing pack is design intent only. It has been produced to show how the SEAT/CUPRA dealership can be upgraded to comply with the new CUPRA Garage with SEAT Corporate Identity. It must not be used for construction. It is the responsibility of the Retailer and their design team to prepare construction information, and obtain all relevant statutory approvals (planning, advertising consent, building control, equality act etc).

The setting out of all corporate elements (furniture, POS, Finishes etc.) must be installed as indicated unless otherwise agreed and approved by SEAT prior to commencement of work.

All signage, furniture and interior elements are supplied by SEAT / CUPRA approved suppliers. Interior finishes and specifications are to comply with SEAT/CUPRA CI Specifications.

The retailer appointed design team must ensure that the design is developed to be fit for purpose. Appropriate care should be taken to ensure correct provision of power and data to relevant items. This includes detailed setting out and coordination of services.

The survey information used to prepare this pack may not correctly represent the current 'as built' facilities. As a result this drawing must only be used for reference purposes. Do not scale off the drawing. The Retailer's design team appointed to complete works are responsible for checking all dimensions and resolving any discrepancies. No works should be undertaken before all statutory or brand consents and approvals are in place. All works should comply with and work within current Health and Safety guidelines and the CDM Regulations. All further necessary survey work (spatial, structural, asbestos etc.) should be directed by the Retailer.

Any changes to these layouts should be approved by SEAT / CUPRA UK in writing.

SPECIFICATIONS (when ordering quote "SEAT")

ENTRANCE MATTING

'Barricade One' anthracite colour ref 4118002 by Interface Europe Ltd.

CERAMIC TILES - MAIN SHOWROOM AREA

CEMENTO RASATO GRIGIO 1200x600
Contact Chris Dennis
T: 0121 753 0777
M: 07562 603 869
E: chrisdennis@solusceramics.com

CERAMIC TILES - CORE ISLAND

NEOWOOD BEIGE 1200X200
Contact Chris Dennis
T: 0121 753 0777
M: 07562 603 869
E: chrisdennis@solusceramics.com

Expansion joints to be allowed for as recommended by Solus Ceramics. Ensure where these are installed that they do not conflict with the stainless steel edge trims mentioned below.

CARPET TILES - OFFICES

Interface Polichrome Solid, Colour Ref: Cloudburst 4266003 500 x 500 tiles

STEEL EDGE TRIM

2-4mm wide brushed aluminium or stainless steel edge trim to be used where different floor finishes meet.

WALLS - EMULSION PAINT

Walls	Chalk	Vintro Concrete Effect Paint, code: VPCE001
Columns	Chalk	Vintro Concrete Effect Paint, code: VPCE001

Concrete effect paint to be applied according to manufacturer's guidance, lightly brush for added texture.

Architraves	Jet Black	RAL 9005 Eggshell
Skirting	Jet Black	RAL 9005 Eggshell
Exposed steelwork	Anthracite	RAL 7016 Satin

GLAZED OFFICE PARTITIONS

Frames	Jet Black	RAL 9005 Satin
--------	-----------	----------------

DOORS

Doors	Telegrey 1	RAL 7045 Satin
Door Frames	Jet Black	RAL 9005 Eggshell
Ironmongery	Jet Black	RAL 9005 Satin

(Existing brushed Stainless Steel ironmongery can be retained)

SHOWROOM GENERAL WORK

Where possible re-run exposed pipes/ductwork above suspended ceiling. Showroom walls made good (re-plastered where necessary) before final decoration. External roofs checked for water tightness before installing suspended ceilings. Bare brick or blockwork walls to be dry lined or plastered before decorating (bare walls not permitted). Mirror walls - mirrors to be removed or panelled over.

EXTERIOR FINISHES

Existing brickwork may remain natural. Profiled steel cladding painted / coated RAL 7016. Rendered walls painted RAL 7016 - Anthracite Grey. Aluminium windows / curtain walling / door frames to be carefully prepared and painted / coated in RAL 7016.

FURNITURE, POINT OF SALE, SIGNAGE

Contact James Burnett at Volkswagen Group UK Ltd.
Tel: 01908 601263

EXPOSED CEILINGS

Spray existing exposed ceiling, steelwork, and services to match RAL 7016 Anthracite.

SUSPENDED CEILINGS

Showroom: If suspended ceiling is >3m, the ceiling should be finished to match RAL 7016 Anthracite. If <3m, the ceiling should be finished to match RAL 7005 Mouse Grey.

Customer facing offices and handover:

If suspended ceiling is >2.5m, the ceiling should be finished to match RAL 7016 Anthracite, unless the showroom is RAL 7005 Mouse Grey, in which case it should match RAL 7005 Mouse Grey. If <2.5m, the ceiling should be finished to match RAL 7005 Mouse Grey.

Back of house areas and customer toilets to have a white ceiling finish.

LIGHTING

Showroom lighting to be set out to suit new showroom layout and to comply with performance specification:

Car exhibition: 1000 lux
Core Island: 500 lux
Operational spots: 500 lux
Handover area: 1000 lux
Offices: 500 lux
Toilets: 200 lux

The light should have a minimum colour rendering index (CRI) of 80 and a colour temperature of 4000K (neutral). A colour temperature of 3000K (warm) can be used at operational spots, offices and lower ceiling areas.

Existing light fittings can be retained subject to CUPRA SA approval. Where retained, they should be painted to match the ceiling finish. 600 x 600 modular fittings are not acceptable and should be replaced.

APPROVED LIGHTING SUPPLIERS:

Ansorg Lighting

Simon Parry - Account Manager
07305 165660, ansorg@mcgregorparry.co.uk

CASTAN Architectural Lighting

David Boya - Sales Manager
+34 639 640 515, dboya@castanweb.com

iGuzzini david.griffiths@iguzzini.com

DDD lighting design sean@dddlightingdesign.co.uk

Linealight ruben.melenchon@linealight.com

Zumtobel Harald.Schwarzer@zumtobelgroup.com

NOTE: MARSET SOHO & MARSET DJEMBE PENDANT FITTINGS TO BE SOURCED BY DEALER DIRECT.

	plan	elevation	picture	description
General				Suspended light iGuzzini Easy QU52_ES 4000K
				Recessed double downlighter black RAL 9005 4000K
				Recessed single downlighter black RAL 9005 4000K / 3000K
				Recessed single downlighter white RAL 9003 4000K / 3000K
Accent				Track mounted spot light black RAL 9005 4000K
Decoration				Suspended light Marset Soho 112 black 3000K
				Ceiling attached light Marset Soho C112 black 3000K
				Suspended light operational spots Marset Djembé 65.35 white 3000K

CI CONCEPT CGI RENDERS



	John Clark Aberdeen Specification/ Furniture		Status Issue 2.0	
	Scale NTS @ A3	Date 14/02/24	Drawn EA/GG	Checked GG
Drawing SE002_303		013	---	
		+44 (0) 20 3093 0611 info@brandtwentytwo.com www.brandtwentytwo.com 5 St John's Lane, London, EC1M 4BH		BRAND TWENTY TWO