



Q37 Details

- Water reduction layer (installed by others)
- Drainage Layer
 - Material: Recycled PE rigid load tolerant drainage and retention board.
 - Depth: 20mm
- Filter Fleece
 - Material: 1.5mm (nominal) non woven geotextile

- Growing Medium
 - Material: low nutrient, free draining root zone
 - Depth: 100mm
- Wildflower Blanket
 - Planting Mix: 30-40 species regional wildflower and grass mix.
 - Depth: 25mm - may grow to over 1mtr
 - Vegetation coverage at installation: Min. 90%
- Dry Weight – 97 kg/m²
- Saturated Weight – 146 kg/m²

System Name:
SGT 02 – Wildflower Mat

Drawn By:	Scale:
	Do not scale

Contact:
[Redacted]

