



DG01  
Replacement timber entrance door  
Hardwood panel door and frame  
Finish colour - Black

DG02  
New slimline aluminium double glazed doors and side screens  
Toughened glass  
Finished colour - RAL 9005 Jet Black

**Proposed External Door Elevations**  
1:20

- Notes:
1. This schedule to be read in conjunction with floor plans, elevations, schedules and details.
  2. All units viewed externally.
  3. Dimensions indicated are overall Structural
  4. Opening arrows point to hinge style
  5. Final unit sizes to be confirmed by unit manufacturer
  6. Fitting tolerances to be advised by respective manufacturer / installer
  7. All dimensions to be checked on site prior to manufacturing
  8. Contractors Programme to allow for openings to be formed, measured and units ordered from site measurements. Existing openings to be finished externally before being site measured.
  9. All associated flashings, cills, brackets, restraints, ironmongery and fixings required to allow installation and normal operation are deemed to have been included in the tender return unless specifically excluded.
  10. Finish - primed and painted to manufacturers specification ready for installation.  
Colour - As indicated.
  11. Replacement doors to be fitted into same position as existing.

**External Door Schedule**

Ref.	Type	Level	Room	Width (S/O)	Height (S/O)	Glazing	Egress	Obscured	Threshold	Trickle Vent	Comments
DG01		Ground Floor	L0-01 Living Room	As existing	As existing	None, Timber Entrance door	Yes	N/A	Timber	0	Main Entrance Door
DG02 / W02		Ground Floor	L0-04 Kitchen / Dining	2372.5 - TBC	2100 - TBC	Double Glazed, toughened glass	Yes	No	Flush	4nr	Double doors with side window panets

