Tree Planting Schedule										
Herbaceous										
Nr	Code	Plant Name	Height/Spread/Grade	Girth	Age	Root	Container	Habit	Form	Density/m2
13	Ah HJ	Anemone hybrida 'Honorine Jobert'	30-40cm			C	3L			
16	Am	Alchemilla mollis	30-40cm			C	3L			4.00
6	CaKF	Calamagrostis arundinacea 'Karl Foerster'	30-40cm			C	3L			4.00
20	DrEr	Dryopteris erythrosora	30-40cm			C	3L			4.00
7	Eph ch	Euphorbia characias ssp wulfenii	30-40cm(D)			C	3L			4.00
9	Hchr M	Heuchera 'Marmalade'	30-40cm			C	3L			4.00
5	MsF	Miscanthus sinensis 'Flamingo'	30-40cm(D)			C	3L			4.00
17	Nxf	Nepeta x faassenii	30-40cm			C	3L			4.00
6	RTG	Rudbeckia fulgida 'Goldsturm'	30-40cm			C	3L			
4	Ss	Salvia superba	30-40cm			C	3L			
9	St	Stipa tenuissima	30-40cm			C	4L			3.00
13	Vb	Verbena bonariensis	30-40cm			C	3L			
Tree										
Nr	Code	Plant Name	Height/Spread/Grade	Girth	Age	Root	Container	Habit	Form	Density/m2
2	Acr cm	Acer campestre	350-400cm	14-16cm	3x	RB			Standard (extra-heavy)	
13	Aln gl	Alnus glutinosa	350-400cm	14-16cm	3x	RB			Standard (extra-heavy)	
27	Bp	Betula pendula	350-400cm	14-16cm	3x	RB			Standard (extra-heavy)	
9	Fs	Fagus sylvatica	350-400cm	14-16cm	3x	RB			Standard (extra-heavy)	
4	Pns sy	Pinus sylvestris	350-400cm	14-16cm	3x	RB			Standard (extra-heavy)	
14	Qr ro	Quercus robur	350-400cm	14-16cm	3x	RB			Extra-heavy Standard	
12	Sau	Sorbus aucuparia	350-400cm	14-16cm	3x	RB			Standard (extra-heavy)	
14	Slx al	Salix alba	350-400cm	14-16cm	2x	RB			Standard (Extra heavy)	
19	Tl cr	Tilia cordata	350-400cm	14-16cm	3x	RB			Standard (extra-heavy)	

NOTES ON PLANTING

1 Topsoil / Subsoil: Topsoil shall be spread to min 450mm depth over planting beds. Topsoil should be in accordance with BS3882:2015 and where subsoil is required, to be in line with BS8601:2013. It is recommended that samples are tested with Certification and Analysis Reports with a concise analysis. To be provided to the Landscape Architect / Client for approval. If the soil doesn't meet the BS standard specialist advise should be received to see if the soil can be improved.

NO IMPORTED TOPSOIL TO BE USED WITHIN MILTON VALLEY FLOOD PLAIN

2 Herbicide and Cultivation: Topsoil to be treated with an application of herbicide prior to planting, where necessary, strictly in accordance with the Control of Pesticides Regulations 1986 (or otherwise updated / superceded legislation), and following manufacturers instructions and undertaken by qualified staff. The topsoil shall then be cultivated to 150mm depth) **No herbicides to be used in close proximity to Wince Brook.**

3 Whips: All whips to be protected by a spiral bound shrub guard secured into place with a timber cane. When in public locations it may be necessary to have caps to the canes.

4 No herbicides are explicitly proposed other than those that might be used in the removal of invasive species (under matters to agree under Condition 27)

5 Position of Plants: Final position of trees subject to confirmation of service location and approval of statutory undertakers.

6 On excavation of the tree pit a bucket test should be undertaken to review the water infiltration. Certain species of trees will decline if the ground drainage is poor. Monitor the water egress. If water sits for long periods or doesn't drain the pit may require further works to break up the ground. A clean stone drainage layer may assist to ensure that the root ball isn't sat within standing water.

TREES - EXTRA HEAVY STANDARDS Tree pits for extra heavy standards to be 750 x 750 x 750mm backfilled with sub soil and 300mm topsoil (from site). Stakes to be 65mm diameter treated softwood driven firmly into the ground. Stakes to be 600mm above ground level and fixed to tree with suitable rubber tree tie.

7 Watering: Plant only into moist soil and water thoroughly to the full depth of soil immediately after planting. Water regularly through the establishment period (minimum 3 months) to prevent dehydration. The trees should be watered through the irrigation pipe to ensure that the water gets down to the rootball. These trees should be watered regularly throughout spring-summer during the first 2 years to ensure that the tree root system establish well.

PLAY AREA PLANTING EXTRACT

Planting Schedule (Mix)											
Mix A											
Nr	Code	Plant Name	Mix%	Height/Spread/Grade	Girth	Age	Root	Container	Habit	Form	Density/m2
15	CmE	Carex morrowii 'Evergold'	50.00 %	30-40cm			C	3L			5.00
15	HmPP	Heuchera micrantha 'Palace Purple'	50.00 %	30-40cm			C	3L			5.00
Mix B											
Nr	Code	Plant Name	Mix%	Height/Spread/Grade	Girth	Age	Root	Container	Habit	Form	Density/m2
16	LaH	Lavandula angustifolia 'Hidcote'	50.00 %	30-40cm			C	3L	Bushy		5.00
16	St	Stipa tenuissima	50.00 %	30-40cm			C	4L			5.00
Mix C											
Nr	Code	Plant Name	Mix%	Height/Spread/Grade	Girth	Age	Root	Container	Habit	Form	Density/m2
3	AhHJ	Anemone hybrida 'Honorine Jobert'	50.00 %	30-40cm			C	3L			2.00
8	HaRE	Hebe albicans 'Red Edge'	50.00 %	30-40cm			C	3L			5.00
Riparian Mix											
Nr	Code	Plant Name	Mix%	Height/Spread/Grade	Girth	Age	Root	Container	Habit	Form	Density/m2
183	Aln gl	Alnus glutinosa	20.00 %	60-80cm			BR			Whip	1.00
183	Ppl Tr	Populus Tremula	20.00 %	60-80cm			BR			Whip	1.00
183	Slx al	Salix alba	20.00 %	60-80cm			BR			Whip	1.00
183	Slx cp	Salix caprea	20.00 %	60-80cm			BR			Whip	1.00
183	Vb op	Viburnum opulus	20.00 %	60-80cm			BR			Whip	1.00
Scrub Mix											
Nr	Code	Plant Name	Mix%	Height/Spread/Grade	Girth	Age	Root	Container	Habit	Form	Density/m2
558	Ca	Corylus avellana	25.00 %	60-80cm			BR			Whip	1.00
558	Crtg mn	Crataegus monogyna	25.00 %	60-80cm			BR			Whip	1.00
558	Prns sp	Prunus spinosa	25.00 %	60-80cm			BR			Whip	1.00
558	Slx cin	Salix cinerea	25.00 %	60-80cm			BR			Whip	1.00

LEGEND

Existing Trees Retained

Proposed tree (Spine Road)
20-25cm girth, Semi-Mature, to be secured with tree stakes and underground guys, in soft landscaping

Proposed whip tree planting (Spine Road)
To be planted as 80-100cm bare root plants to be installed with tree and shrub shelter guards. Planted on embankments.

Proposed Hedge planting (Spine Road)
To be planted as 5L pots at 300mm centres. Hedge to be max. 900mm high

Proposed Native Woodland Understorey Mix (Spine Road)
Plants to be inserted at 40-80cm height in groups of 3 or 5 protected by tubex or spiral guards. Approx 1:3 embankment to edge of footway. Native woodland planting to be incorporated on the slope, using a pinned Covamat system.

Proposed Native Trees
Extra Heavy Standard, 14-16cm girth, 3.5-4.0m height. To be fixed with double stakes and rubber ties.

Proposed Wildflower Seed Mix
EM2 Proposed Wildflower Seed Mix

Proposed Wildflower Seed Mix (Wetland)
EM8 Meadow Mixture for Wetlands

Proposed Wetland Planting
EP1 Pond Edge Mixture

Proposed Riparian Planting
To be planted with a mix of riparian planting species such as Salix alba, Alnus glutinosa. To be protected with spiral guards

Proposed Scrub Mix
To be protected with spiral guards

Phasing Lines

All other areas to be retained where possible and made good in areas that have been damaged as a result of works. New areas of rough grassland to be seeded due to formation of new contours/levels.

REVISION NOTES

Rev	By	Description	Date
N	FZ	Updated in line with 101V landscape masterplan	17.04.24
M	DC	Wildflower seed mix spec amended	16.11.23
L	DC	Play area relocated and planting amended	13.11.23
K	EO	Updated in line with 101Q landscape masterplan	20.09.23
J	EO	Updated in line with 101P landscape masterplan	19.09.23
I	JL	Minor amend to tree species	30.05.23
H	DC	Phasing lines added	08.09.22
G	KD	Updated for landscape management purposes	01.12.21
F	MC	Updated in line with GMEU comments	26.05.21

GENERAL NOTES

1. This drawing is the copyright of tpm landscape Ltd and cannot be reproduced in any form without the consent of the company.
2. This drawing is to be read in conjunction with detail landscape drawings, details and specification.
3. This drawing is to be read in conjunction with all relevant Architects', Engineer's, Specialists, Bills of Quantities and Specifications.
4. The insertion of any firm or proprietary brand on this drawing is an indication of the class or quality required and does not exclude the use of alternative materials that are equal in performance, quality and appearance, provided that they have been approved in writing by the Landscape Architect.
5. The Contractor is responsible for accurately ascertaining the position of underground services and responding to all relevant service easement requirements.
6. All dimensions are in millimetres unless stated otherwise, for the purposes of construction this drawing must not be scaled and only written dimensions used. Written and scaled dimensions to be checked on site, any discrepancies reported prior to work commencing. IF IN DOUBT PLEASE ASK.
7. All work and materials are to be in accordance with the relevant British Standards and Code of Practice.
8. All Proprietary products are to be used strictly in accordance with the manufacturer's instructions and details.

Client
FO Developments LLP

Project
Broadway Green, Oldham - Linear Park

Description
Planting Strategy

Status
For Approval

N

Scale @ A1	Drawn	Checked	Date
1:1000	SH	DC	16.03.20
Job number	Drawing number		Revision
1994	201		N

tpm landscape
chartered landscape architects
address: 4th Floor Studio 10 Little Lever St Manchester M1 1HR
tel: 0161 235 0600 fax 0601 email info@tpmlandscape.co.uk