



IDE FARM PHASE 3		
om	Existing column installed on pervious phase to be retained	
PT RB	Proposed column installation, complete with new lantern Lantern: RB_ISARO PRO 12 LED -WW - 350mA - WSC - 13W Mounting: Post Top Column: 6 metre nominal height steel post top column Lanterns to be controlled via CMS System	
PT Co	Proposed column installation, complete with new lantern Lantern: RG_ISARO PRO 12 LED - WW - 150mA - EWR - 6W Mounting: Post Top Column: 6 metre nominal height steel post top column Lanterns to be controlled via CMS System	
PT	Proposed column installation, complete with new lantern Lantern: RO_ISARO PRO 24 LED - WW - 350mA - ES - 26W Mounting: Post Top Column: 6 metre nominal height steel post top column Lanterns to be controlled via CMS System	