

Details of repair & restoration works to Kitchen floor

This information has been supplied to discharge condition 3 of Listed Building Consent DC/22/05516.



These photographs highlight the typical condition of existing kitchen pammments that would be considered for replacement (with red line boundary). The random placement of flagstones (partly visible in the left-hand photo) will be rationalised and focused to an area in front of the range. Areas of cement flooring (to the left-hand side of the range) will be removed, and replaced with reclaimed pammments.



The proposed replacement pammments will be reclaimed – samples in photo above. These will be sourced from Mongers of Hingham, a Norfolk-based reclamation specialist. Light terracotta, pink and buff tones will be sourced to match the existing floor as best as possible. The existing pammments being retained, will be gently cleaned.