



Eastbound (Westerly) Visibility splay
MfS Values
 85%ile - 35.8mph
 Reaction time - 1.5s
 Deceleration Rate - 4.41m/s
 Gradient - 0%
 Bonnet Adjusted SSD - 55.4m

Westbound (Easterly) Visibility splay
MfS Values
 85%ile - 35.5mph
 Reaction time - 1.5s
 Deceleration Rate - 4.41m/s
 Gradient - 0%
 Bonnet Adjusted SSD - 54.8m

Footway/ Verge Crossover
 Width - 5m
 Bound Surface for 7.5m
 Gates set back - 7.5m

Based upon the ORDNANCE SURVEY MAPS with the permission of THE CONTROLLER OF HER MAJESTY'S STATIONERY OFFICE, © Crown Copyright AL 100030412

© David Tucker Associates

REV	DESCRIPTION	DRAWN	INITIALS	DATE



Forester House, Doctors Lane,
 Henley -in-Arden
 Warwickshire B95 5AW
 Tel: +44(0)1564 793598
 Fax: +44(0)1564 793983
 www.dtatransportation.co.uk

JOB TITLE		Blithbury Road		CLIENT		CT Planning	
DRAWING TITLE							
Proposed Site Access with Visibility Splays							
SCALE	DRAWN BY	DATE	DRAWING No	REVISION			
1:500@A4	DN	Apr 24	25383-01	D			