



**HARD LANDSCAPE KEY**

<b>P1 - Carriageway PERMEABLE Paving</b> Tobmore Fusion Pave Colour: Silver	
<b>P1A - Carriageway IMPERMEABLE Paving</b> Tobmore Fusion Pave Colour: Silver	
<b>P2 - Footpath PERMEABLE Paving</b> Tobmore Fusion Pave Colour: Silver	
<b>P2A - Energy Centre IMPERMEABLE</b> Tobmore Fusion Pave Colour: Silver	
<b>P3 - Footpaths IMPERMEABLE</b> Tobmore Fusion Pave Colour: Silver	
<b>P3A - Footpaths IMPERMEABLE</b> Tobmore Fusion Pave Colour: Silver	
<b>P4 - Permeable Asphalt</b> Tobmore Fusion Pave Colour: Silver	
<b>P5 - Self-Binding Gravel</b> Tobmore Fusion Pave Colour: Silver	
<b>P6 - Permeable Wet-Pour Safety Surface</b> Tobmore Fusion Pave Colour: Silver	
<b>P7 - Rubber MARCH Play Safety Surface</b> Tobmore Fusion Pave Colour: Silver	
<b>P8 - Permeable Asphalt Surface</b> Tobmore Fusion Pave Colour: Silver	
<b>P9 - Carriageway Rumble Strip - Tibermore</b> Tobmore Fusion Pave Colour: Silver	
<b>P10 - Permeable Asphalt Court Surface</b> Tobmore Fusion Pave Colour: Silver	
<b>P11 - Bosh Bound Gravel</b> Tobmore Fusion Pave Colour: Silver	
<b>P12 - Tactile Paving</b> Tobmore Fusion Pave Colour: Silver	
<b>P13 - Concrete Flag Paving to Private Terraces</b> Tobmore Fusion Pave Colour: Silver	
<b>P14 - Concrete Flag Paving to rear of Energy Centre</b> Tobmore Fusion Pave Colour: Silver	
<b>P15 - Slipping Stones - 300mm spacing</b> Tobmore Braemar Ground 600 x 400 x 50mm colour: Alto Silver	
<b>KERBS AND EDGINGS</b>	
Aluminum edge: 150mm Flexible Edging, Lad Flush	
Aluminum edge: 150mm Flexible Edging, 50mm upstand	
Tobmore Fusion Kerb 'Silver' 255 x 145 x 95mm laid with 125mm upstand	
Tobmore Fusion Kerb 'Silver' 255 x 145 x 95mm laid flush, 145mm wide	
Tobmore Fusion Kerb 'Silver' 255 x 145 x 95mm staggered kerb section	
<b>FURNITURE</b>	
Flamingo BENCH BT1 40718 Steel framed bench with slatted seat and backrest Colour: Mattblack RAL 7016 Anthracite Grey	
Timber Seating Cube - F14 400 x 400 x 400mm timber cube, mattblack colour RAL 7016 Anthracite Grey, steel fixed to manufacturer's specification	
Cycle racks - F20 Supplier: Marbath or equal approved Standard: BS EN 15194:2010 Colour: Mattblack RAL 7016 Anthracite Grey Flang: Steel fixed to concrete footings to engineer's specification and details	
Removable Bollard - F4b DN: 100mm diameter, 1.5m high, 100mm diameter Colour: Mattblack RAL 7016 Anthracite Grey	
Timber Bollard - F4 100mm diameter, 1.5m high, 100mm diameter Colour: Mattblack RAL 7016 Anthracite Grey	
Litter Bin - LB - OMS S45 TA - 200 litre, 1000mm high, 400mm diameter Colour: Mattblack RAL 7016 Anthracite Grey	
Communal picnic table - 240 2400 x 1200mm table plus seating benches Colour: Mattblack RAL 7016 Anthracite Grey	
Revised Planting Beds for flowers and cabbie crops Coloured timber, 100mm high, 100mm wide, 100mm deep Filled with General Purpose Topsoil to BS3882	
<b>INCIDENTAL PLAY ITEMS</b>	
Timber Stepping Logs - Pressure treated softwood 300mm high and 300mm diameter, 400mm apart and 750mm from hard edges	
Play Boulders 400 x 400 x 400mm, 450mm separation and 750mm from hard edges	
Timber Sleeper Path - Pressure treated softwood sleepers 2400mm long x 250mm x 125mm inset level and flush with soil surface	
Tree Trunk - debarked and smoothed and prepared for play use, 1.5m separation from other features or hard surfaces	
Willow Tunnel - Natural Live Woven Willow Tunnel 9m long x 2m wide x 2m high	

- REVISIONS**
- Rev P01 30/09/22 First Issue
  - Rev P02 30/09/22 4m wide hard surface cable route added
  - Rev P03 10/10/22 Sub-Station amended
  - Rev P04 19/10/22 Phase 1 Link road detailed and interface amended
  - Rev P05 19/10/22 Phase 1 - 2 interface detailed following discussion with MCA
  - Rev P06 21/10/22 UPRN cable route restored to agreed route
  - Rev P07 11/11/22 UPRN & RPO construction items arrangement
  - Rev P08 25/10/22 Link road location amended to avoid site construction compound and allow completion of Phase 2. Additional soft landscape areas identified to compensate for lost link road
  - Rev P09 09/11/22 Link road deleted and central green redesigned to accommodate fire access to Phase 1 Block B
  - Rev P10 08/12/22 Fire Access to Phase 1 Block B deleted following acquisition of fire access and play layout restored
  - Rev P11 11/12/22 Key added
  - Rev P12 15/01/24 Coordinated with Phase 1 and 2 Plans

**mca**  
**DURKAN**

**Kidbrooke Park Road  
LB Greenwich**

**Phase 1 and 2  
General Arrangement  
Masterplan**

1:250/A0    30/09/22    MC

KPR-MCA-SW-00-DR-L-0007    P12

Phase 1 and 2 SCALE 1:250/A0