

Heating

Product Information

PUHZ-(H)W50-140VHA(2)/YHA2(-BS)
Ecodan Monobloc Air Source Heat Pumps

Making a
World of
Difference



Designed to meet
the demands of
today's heating
needs



Certificate Number: MCS 187002
Product Type: Heat Pumps
Product Reference: PUHZ-W50VHA2(-BS), PUHZ-W85VHA2(-BS)
PUHZ-W112VHA(-BS), PUHZ-H81-40VHA2/YHA2(-BS)

Our range of Ecodan monobloc air source heat pumps includes **5, 8.5, 11.2 and 14kW sizes**. Now with the ability to cascade up to six units of the same output, Ecodan monobloc systems offer a capacity range from 5 through to 84kW. Designed to suit a wide number of applications, these models offer a viable solution for the varying requirements that domestic and small commercial applications demand.

Key Features

- Self-contained unit, only requiring water and electric connections
- No need for gas supply, flues or ventilation
- Single phase power supply with a low starting current (3 phase available for 14kW)
- Low maintenance and quiet operation
- Operates with outside temperatures as low as -25°C
- Multiple unit connection
- Hybrid function, for use with conventional boilers
- 2-zone energy efficient space heating control
- Available as a standalone, packaged or semi packaged system
- Energy monitoring as standard
- Coastal protection models available (-BS)

Application Examples

- The vast majority of UK homes
- Small Retail Outlets
- Dental / Doctor's Surgeries
- Public Sector / Commercial Buildings



Air Conditioning | Heating
Ventilation | Controls



ecodan[®]
Renewable Heating Technology

OUTDOOR UNIT		PUHZ-W50VHA2(-BS)	PUHZ-W85VHA2(-BS)	PUHZ-W112VHA(-BS)	PUHZ-HW140VHA2(-BS)	PUHZ-HW140YHA2(-BS)
HEAT PUMP SPACE HEATER - 55°C	ErP Rating	A++	A++	A++	A++	A++
	η_s	127%	128%	125%	126%	126%
	SCOP	3.25	3.27	3.20	3.22	3.22
HEAT PUMP SPACE HEATER - 35°C	ErP Rating	A++	A++	A++	A++	A++
	η_s	162%	162%	164%	157%	157%
	SCOP	4.12	4.12	4.18	3.99	3.99
HEAT PUMP COMBINATION HEATER - Large Profile ¹	ErP Rating	A	A	A	A	A
	η_{wh}	99%	97%	100%	96%	96%
HEATING ² (A-3/W35)	Capacity (kW)	4.8	8.3	11.0	14.0	14.0
	Power Input (kW)	1.63	2.96	3.65	4.81	4.81
	COP	2.95	2.80	3.01	2.91	2.91
OPERATING AMBIENT TEMPERATURE (°C DB)		-15 ~ +35°C	-20 ~ +35°C	-20 ~ +35°C	-25 ~ +35°C	-25 ~ +35°C
SOUND PRESSURE LEVEL AT 1M (dBA) ^{3,4}		45	48	53	53	53
LOW NOISE MODE (dBA) ³		40	42	46	46	46
WATER DATA	Pipework Size (mm)	22	22	28	28	28
	Flow Rate (l/min)	14.3	25.8	32.1	40.1	40.1
	Water Pressure Drop (kPa)	12	13.5	6.3	9	9
	Height	950	950	1020	1020	1020
DIMENSIONS (mm) ⁷	Width	330+30 ⁵	330+30 ⁵	330+30 ⁵	330+30 ⁵	330+30 ⁵
	Depth	740	943	1350	1350	1350
	Height	64	77	133	134	148
WEIGHT (kg)		64	77	133	134	148
ELECTRICAL DATA	Electrical Supply	220-240v, 50Hz	220-240v, 50Hz	220-240v, 50Hz	220-240v, 50Hz	380-415v, 50Hz
	Phase	Single	Single	Single	Single	3
	Nominal Running Current [MAX] (A)	5.4 [13]	10.3 [23]	11.2 [29.5]	14.9 [35]	5.1 [13]
	Fuse Rating - MCB Sizes (A) ⁶	16	25	32	40	16

¹ Combination with EHPT20X-MHCW Cylinder

² Under normal heating conditions at outdoor temp: -3°CDB / -4°CWB, outlet water temp 35°C, inlet water temp 30°C.

³ Under normal heating conditions at outdoor temp: 7°CDB / 6°CWB, outlet water temp 35°C, inlet water temp 30°C as tested to BS EN14511.

⁴ Sound power level of the PUHZ-W50VHA2 is 61 dBA, PUHZ-W85VHA2 is 62.5 dBA, PUHZ-W112VHA is 65 dBA, PUHZ-HW140VHA2 is 65.5 dBA, PUHZ-HW140YHA2 is 67.5 dBA. Tested to BS EN12102.

⁵ Grille.

⁶ MCB Sizes BS EN60898-2 & BS EN60947-2.


⁷ Flow Temperature Controller (FTC) for standalone systems PAC-IF062B-E Dimensions WxDxH (mm) - 520x150x450

η_s is the seasonal space heating energy efficiency (SSHEE) η_{wh} is the water heating energy efficiency


DIMENSIONS

PUHZ-W50VHA2(-BS)

Upper View




Front View




PUHZ-W85VHA2(-BS)

Upper View




Front View




PUHZ-(H)W112-140VHA(2) / YHA2(-BS)

Upper View



Front View



Telephone: 01707 282880

email: heating@meuk.mee.com web: heating.mitsubishielectric.co.uk

UNITED KINGDOM Mitsubishi Electric Europe Living Environmental Systems Division
Travellers Lane, Hatfield, Hertfordshire, AL10 8XB, England General Enquiries Telephone: 01707 282880 Fax: 01707 278881

IRELAND Mitsubishi Electric Europe Westgate Business Park, Ballymount, Dublin 24, Ireland
Telephone: Dublin (01) 419 8800 Fax: Dublin (01) 419 8890 International code: (003531)

Country of origin: United Kingdom - Japan - Thailand - Malaysia. ©Mitsubishi Electric Europe 2015. Mitsubishi and Mitsubishi Electric are trademarks of Mitsubishi Electric Europe B.V. The company reserves the right to make any variation in technical specification to the equipment described, or to withdraw or replace products without prior notification or public announcement. Mitsubishi Electric is constantly developing and improving its products. All descriptions, illustrations, drawings and specifications in this publication present only general particulars and shall not form part of any contract. All goods are supplied subject to the Company's General Conditions of Sale, a copy of which is available on request. Third-party product and brand names may be trademarks or registered trademarks of their respective owners.



www.greengateway.mitsubishielectric.co.uk

Mitsubishi Electric UK's commitment to the environment

Follow us @meuk_les
Follow us @green_gateway

Mitsubishi Electric
Living Environmental Systems UK

youtube.com/mitsubishielectric2

