

Heritage Statement for proposed alterations to the listed building at Halifax, 84 North Street, Sudbury CO10 1RF , to remove external signage and an external ATM.



Front elevation

The description from the Listed Building Register is:

Heritage Category: Listed Building

Grade: II

List Entry Number: 1351394

List Entry Name: 84, NORTH STREET

Statutory Address 1: 84,NORTH STREET

Location

Statutory Address: 84, NORTH STREET

The building or site itself may lie within the boundary of more than one authority.

County: Suffolk

District: Babergh (District Authority)

Parish: Sudbury

National Grid Reference: TL 87391 41497

Details

1. NORTH STREET 1692 (East Side) N0 84 TL 8741 3/214

II GV

2. With early C19 rebuilding. 2 storey. 3 windows including first floor canted splay bay, sashes without glazing bars. Stucco, lined and painted. Ground floor shop with wood case. Included for Group Value.

Nos 83 to 88 (consec) form a group.

Listing NGR: TL8739141497

Legacy

The contents of this record have been generated from a legacy data system

Legacy System number: 276122

Legacy System: LBS

The branch is to close and therefore an external ATM and the bank signage are to be removed.

On the front elevation, the hanging projecting sign is to be removed, but the bracket is to remain for possible future use and to minimise disturbance to the heritage asset. The security camera is to be removed and the redundant wiring and fixing holes in the timber fascia are to be filled with wood filler. The fasci sign is to be removed and the redundant fixing holes in the timber fascia are to be filled with wood filler. The fascia and shopfront framing are to be repainted, white. The engraved text and logo on the letterbox face are to be carefully ground out. The through-the-window external ATM is to be removed and the aperture infilled with clear glazing. The over-ATM tablet sign and the under-ATM slip bin are to be removed. The blue film about the ATM is to be removed.

These proposed alterations are not considered to detract from the listed building appearance, character, and quality.

Lime mortar will be natural hydraulic lime (3.5) with a fine-sieved, crushed natural-stone aggregate to match the stone to be filled, and mixed in the ratio of 1 part lime : 3 parts aggregate, when filling redundant holes.