

**RICHARD PARR
ASSOCIATES**

Date West Bradley House
04.10.23 Building: Main House, link and Apple Barn
Job Number Proposed Element
315

Schedule no 002

| | |
|-----------------|--|
| Floors | |
| Floor type 1 | <ol style="list-style-type: none"> 1.Extg 200mm joists strengthened with sistered joists 2.100mm 60kg/m3 density rockwool between joists 3.Heavy pugging on plywood shelf on noggins fixed to side of joists 4.Pre-routed foil board with wet fed UFH pipes between the joists. 5.New Ply 6.Uncoupling Membrane - Schluter DITRA 25 or similar 6.Limestone Stone slabs on adhesive. |
| Floor type 2 | <ol style="list-style-type: none"> 1.Extg 200mm joists strengthened with sistered joists 2.100mm 60kg/m3 density rockwool between joists 3.Heavy pugging on plywood shelf on noggins fixed to side of joists 4.Pre-routed foil board with wet fed UFH pipes between the joists. 5.Impact joist strips adhered to joists 6.Existing timber boards/ New like for like replacement boards if required due to condition. |
| Floor type 3 | <ol style="list-style-type: none"> 1.Compacted sand binding on compacted Type 1 2.New poured re-inforced concrete slab 3.Damp proof membrane 4.140mm PIR insulation 5.50mm screed inlaid with wet fed UFH 6.Extg flagstones re-instated. Where nessiary flags to be reduced to 60mm and laid on 50mm sand/motor bedding. |
| Floor type 4 | <ol style="list-style-type: none"> 1.Concrete binding on compacted Type 1 2.New poured re-inforced concrete slab 3.Damp proof membrane 4.140mm PIR insulation 5.100 mm concrete screed inlaid with wet fed UFH |
| Floor type 5 | <ol style="list-style-type: none"> 1.Extg 200mm joists strengthened with sistered joists 2.100mm 60kg/m3 density rockwool between joists 3.Heavy pugging on plywood shelf on noggins fixed to side of joists 4.Ply 5.Uncoupling Membrane with electric underfloor heating- Schluter DITRA heat or similar 6.Tiles |
| Floor type 6 | <ol style="list-style-type: none"> 1.Extg oak joists timbers to be retained on existing steel posts 2.New timber joists mechanically hung between extg beams at 400mm ctrs flush to top of extg beams 3.100mm 60kg/m3 rockwool between joists 4.Pre-routed foil board with wet fed UFH pipes on new plywood shelf sitting on noggins fixed to joists 5.Impact joist strips adhered to joists 6.New 25mm plywood subfloor screwed at 150mm ctrs 7.Carpet |
| Floor type 7 | <ol style="list-style-type: none"> 1.Extg oak joists timbers to be retained on existing steel posts 2.New timber joists mechanically hung between extg beams at 400mm ctrs flush to top of extg beams 3.100mm 60kg/m3 rockwool between joists 4.Pre-routed foil board with wet fed UFH pipes on new plywood shelf sitting on noggins fixed to joists 5.Impact joist strips adhered to joists 6.New Solid timber floor boards |
| Floor type 8 | <ol style="list-style-type: none"> 1.Extg 200mm joists strengthened with sistered joists 2.100mm 60kg/m3 density rockwool between joists 3.Heavy pugging on plywood shelf on noggins fixed to side of joists 4.Pre-routed foil board with wet fed UFH pipes between the joists. 5.Impact joist strips adhered to joists 6.New Ply Sub floor 6.Carpet |
| Floor type 9 | <ol style="list-style-type: none"> 2.New steel structure with 200mm joists spanning in-between web of steels at 400mm ctrs 3.100mm 60kg/m3 rockwool between joists 4.Pre-routed foil board with wet fed UFH pipes on new plywood shelf sitting on noggins fixed to joists 5.Impact joist strips adhered to joists 6.New 25mm plywood subfloor screwed at 150mm ctrs 7.New stone floor |
| Cornices | |
| Cornice Type A | Stevensons of norwich - BERRINGTON HALL ESTATE OFFICE CORNICE NC04 |
| Cornice Type B | Stevensons of norwich - SALTRAM RED STAIR CORNICE MG03 |
| Skirtings | |
| Skirting Type A | Ogee profile 175 x 20mm painted timber skirting |
| Skirting Type B | 100mm Stone skirting |
| Skirting Type C | Recessed square profile 125 x 20mm painted timber skirting |
| Skirting Type D | Bespoke, See staircase drawing. |
| Skirting Type E | Square profile 125 x 20mm painted timber skirting |