

6 Montague Park, Winkfield, SL4 4BD

No. on Plan	Species	Proposed Works	Reason
T1	Ash	Crown reduce by 1.5m Remove deadwood.	To maintain size for garden.
T2	Ash	Crown reduce by 1.5m. Remove deadwood.	
T3	Ash	Fell in sections to near ground level. Grind out stump to 15-20cm below ground level. Level wood chips and soil over hole, remove remainder from site.	Customers request due to being a poor specimen and the canopy is weighted towards the house due to its proximity.