


Specification

New 20mm diameter black painted steel rail and 10 x 40mm supports with curved top, welded to anchor plates below surface finish, bolted with resin anchors to concrete pad footings.


Footings to existing stone balustrade is to be protected with an EPS isolator where new pad footings are close to the existing.

Railing fabricator is to ensure that member sizes shown, anchor plates, anchors and footings are fit for purpose.


Specification for decoration of the new steel railings is to be suitable for an extreme marine environment.



Proposed Plan



Proposed Elevation



Proposed Section

Note:
Do not scale this drawing.
All levels and dimensions are to be checked on site.
This drawing is to be read in conjunction with all relevant consultants' requirements, drawings and specifications.
Any discrepancies between consultants' drawings to be reported to the Contract Administrator before any relevant work commences.

Copyright: 2021 Miller Bourne ©

Rev	Date	Description	Drawn	Checked	Status
P-01	30.05.22	First Issue	AGO	AI G	

Roedean School
3No. Minor Projects

Balustrade Railings - Proposed Details

Scale: 1:10 @ A3

Ref Number: 4830-MBA-02-G-DR-A-1012-S1-P01

PLANNING

MILLERBOURNE
ARCHITECTS

332, K. Ingvery
Hove East Sussex
BN3 4QVY
T: 01273 411399
design@miller-bourne.co.uk