

Manufacturer: Jacksons Fencing

Web: www.jacksons-security.co.uk

Tel: +44 (0)1233 750393 | 0800 953 3699

Product Reference: JAKOUSTIC® ABSORPTIVE

Service Life of Fencing

Timber and Steel fencing and gates designed and manufactured to be fit for purpose and providing a minimum 25 year guarantee, delivering the lowest whole life cost and significantly reduced carbon footprint.

Fencing & Posts:

2000mm High, Post Length 2900mm (2410mm Post Centres)

2500mm High, Post Length 3400mm with 2000mm Spur Post (2410mm Post Centres)

3000mm High, Post Length 3900mm with 2500mm Spur Post (2410mm Post Centres)

** Delete above as required*

For heights above 3000mm please see Jakoustic® Commercial and Highway

Construction:

Jakoustic® Absorptive takes the proven Jakoustic® Reflective design of heavy section planed timber boards with deep interlocking 'V' tongue and groove joint, coupled to tuning fork posts and adds an absorptive layer of a mineral Rockwool fibre and protective membrane to one side of the barrier. Offering up to 32dB* reduction in noise, it has been designed for faster installation times on site and can accommodate changes in site levels or profile.

Boards:

On one side, Jakcure pressure treated 34mm x 143mm x 4.8m (planed) boards with unique deep interlocking "V" tongue and groove joint

Posts:

Overlength timber tuning fork posts for setting in concrete as standard

Fixings:

Special fixings clamp the acoustic boards between posts

Finish / Colour:

Absorptive face clad in black membrane with vertical timber battens as standard

Planed timber finish

Installation

In accordance to manufacturers instructions

NOTES:

For more information please contact Jacksons Fencing. We reserve the right to alter specification within this document at any time.