

Specification

Construction:-

All windows and doors are manufactured from Smarts Alitherm Heritage thermally broken aluminium profiles including all necessary ancillary profiles including a head add on profile a 150mm sub cill and coupling mullions. (refer to elevations for cill sizes)

Finish:-

All aluminium profiles are Polyester Powder Coated (Minimum 40 microns thick) - Anthracite Grey KL005 (RAL 7016 matt)

Glazing:- Hermetically sealed double glazed units comprising:

G1 - (28)

4mm Superior soft coat low-e clear low iron float glass (int)
20mm argon gas filled cavity with black warm edge spacer
4mm clear low iron float glass (ext)

G2 - (28)

4mm Superior soft coat low-e clear low iron toughened safety glass (int)
20mm argon gas filled cavity with black warm edge spacer
4mm clear low iron toughened safety glass (ext)

Side hung window fittings:-

- Stainless steel friction stay's (Egress where noted)
- A single key locking handle operating a multi point locking system
- Slimline TTF through frame colour matched adjustable trickle vents (see elevations for locations and quantities)

Door fittings:-

- 3 No system butt hinges per door leaf
- Back to back colourmatched ACSM060 lever handles operating an enhanced security multi point locking system

Sealant:-

External perimeter seal - Arbosil low modulus silicone sealant from the standard range

NOTES

For Approval

02 detail number
03 drawing number

REVISIONS

CLIENT

Mr Brightey

CONTRACT

Corner House
Shapway Lane
Stoney Stratton
Shepton Mallet
BA4 6DZ

DRAWING TITLE

Aluminium window
& door specification

SCALES @ A3

na

DATE

April '24

DRAWN BY

pmc

DRAWING NO.

JXXXX - SP01

REV.


Techniglaze

Techniglaze Limited
Units 1-6 Fourth Avenue
Westfield Industrial Estate
Midsomer Norton
Radstock BA3 4XE

Tel: 01761 417654
Fax: 01761 417207