

Move existing pitch west to allow new 3G pitch
Watchpoints - closer to road and removal of vegetation required

Install retaining structure in stone gabions sized to structural engineers recommendations to allow level platform for new 3G pitch

Remove existing skate park and replace with 5v5 mini soccer 3G pitch:


- 3G FTP surface of 40mm pile on shockpad layer with infill of silica sand/rubberised pellets to manufacturers recommendations - all to FA Standards/European standard EN 15330-1 2013/EN14877:2013
- Perimeter fencing 4.5m height - twin bar super-rebound panels or rolls supported by box section posts in plastic coated galvanised steel. Colour: Green
- floodlights to each corner of min 120lux to specialist lighting designers details
- Min 300m tarmaced 'mowing strip' around perimeter of fencing

Existing football pitch - add 6 No floodlight posts to artificially light pitch

New pathways around clubhouse and to 3G pitch in simple 600x600 concrete paving slabs laid on sand/cement base

Remove MUGA and construct new Clubhouse

Remove existing changing facility and replace with additional car parking



C	06.11.23	3G pitch amended, further spec added	AC
B	16.08.23	Post Meeting Amends	LC
A	03.08.23	Post Meeting Amends	LC



2 Hearsall Lane, Coventry, CV5 6QR, tel: 024 7671 3872
also at 1 Chapel Street, Warwick, CV34 4HL,
t: 01926 405595 - f: 01926 405522
e: architect@callingham-associates.co.uk
www.callingham.co

PROPOSED WORKS
CHARLIE WAYMAN FIELDS AND
MINERS WELFARE SITES
CHILTON WAY
FERRYHILL
DL17 0HJ

PROPOSED CHARLIE WAYMAN SITE
scale: 1:1250 @ A1 date: 09.08.23 drawn by: LC
drg: **1329.05C** checked by: xx