

		GENERAL NOTES
		All dimensions are in millimetres unless otherwise noted.
hitects specification		Contractor to be responsible for checking all dimensions on site prior to work commencing.
ction/thickness. ction A-A)		All work to be carried out in accordance with British Standards and Codes of Practice.
	-	Contractor to be responsible for all necessary temporary support and bracing to ensure stability of the building during the
		RETAINING WALL Concrete to be grade C35 having a crushing strength of 35N/mm <sup>2</sup> at 28 days.
		Cement content to be $300 \text{kg/m}^3$ .
it res RETAINED		Aggregate to be 20mm maximum size. Max. free water/cement ratio to be 0.60. High yield reinforcement 'T' bars to be type 2 bond bars as described in BS8110 with a characteristic tensile strength of 460N/mm <sup>2</sup> .
		Test cubes to be taken as directed by the Engineer.
		All concrete to be compacted to the specification or by the means approved by the Engineer.
EARTH		Concrete cover to be 50mm. Filling behind wall to be lightly compacted free draining hardcore/clean stone. Minimum bar reinforcement lap lengths : TIO = 350mm TI2 = 450mm TI6 = 550mm T2O = 650mm
Drainage System	3500 Max. retained height	Mınımum fabrıc reinforcement lap lengths : A393 = 400mm
rs = T20 bars at centres. (Inner face) ND ANY RY DRAINAGE D BE DESIGNED LLED BY		
irs=T20 50mm her Face)		THIS DRAWING TO BE READ IN CONJUNCTION WITH LATEST BUILDING REGULATION DRAWINGS AND DETAILS
us Drain		SAFE GROUND BEARING PRESSURE = 130KN/M <sup>2</sup> FOR RETAINING WALL BASE – SEE MURRAY RIX REPORT.
-	-	Client Mr. and Mrs. W. Mallard
-	350	<sup>Job</sup> Proposed New Dwelling at Gerrards Hollow, Gee Cross. Sk14 5DT.
bution steel - T12's top pottom at 150mm c/c		Drg Proposed Foundation and Reinforced Concrete Retaining Wall Details. Drawn Date Scale
		S.King Dec. 2023 As Shown Job No. Drg No.
		C23.07.32 Sketch02 Gamble King and Noone Ltd
		Consulting Structural Engineers & Building Surveyors. 5 Queen Street Oldham OL1 1RD Tel 0161 652 1183 Mobile: 07756 902 604
		07725 145 369