


Key

1. Church building
2. Paving
3. Car Park
4. Raised External Platforms
5. Childrens' External Play
6. Planting Bed
7. Grass
8. Banking
9. Permeable paving
10. Covered cycle racks
11. Landscape Buffer
12. Bin Store
13. Overspill parking

| Station | Easting | Northing | Level |
|---|---|---|---|
| S1 | 455637.082 | 296401.009 | 68.787 |
| S2 | 455671.031 | 296369.169 | 68.579 |
| S5 | 455657.798 | 296394.284 | 68.639 |

Overflow parking

Tarmac Roadway

Permeable Paved Car Parking spaces.

Paved walkways and paths

150mm Gravel perimeter around the building.

(Refer to drawing 13457-230 for details)

Boundary Treatment

Boundary treatments to remain as existing as shown. Retractable Bollards to be constructed at Vehicle entance .

Existing Hedge Boundary

Existing Fence Boundary

New Telescopic Bollards

| AMENDMENTS | DWN | DATED |
|---|---|---|

DRAWING TITLE
**Site Plan Master REDUCTIONS**

JOB TITLE
Proposed New Baptist Church
Dog & Gun Lane, Whetstone, Leicestershire
For WBC Design Co Ltd

| AMENDMENTS | DATED |
|---|---|
| A-C1 Construction Issue | 12.04.24 |
| C1 Construction Issue | 25.10.20 |
| | 25.05.17 |

**13038-400**

| | | |
|---|---|---|
| DRAWN | DATE | 10.05.17 |

DRAWN **Hard Landscaping**

JOB TITLE
Whetstone Baptist Church
Dog & Gun Lane, Whetstone, Leicestershire
For WBC Design Co Ltd

DRAWING NUMBER
**13038-404A-C2**

KPW ARCHITECTS
Kingsway House
t: 0116 255 2279
e: admin@kpw-architects.co.uk
www.kpw-architects.co.uk

| SCALE (A0) | DATE |
|---|---|
| 1:200 | 10.05.17 |

Figured dimensions must be taken in preference to scaled dimensions and any discrepancies or errors are to be referred to the Architect. Contractors, sub-contractors and suppliers must verify all dimensions on site before commencing work or producing any workshop drawings. Copyright Reserved©